



Wiss, Janney, Elstner Associates, Inc.  
2 Trap Falls Road, Suite 502  
Shelton, Connecticut 06484  
203.944.9424 tel  
www.wje.com

August 18, 2022

Louis Casolo, P.E.  
Engineering Department  
City of Stamford  
888 Washington Blvd, 7th Floor  
Stamford, CT 06904

## Harbor Point- The Allure: P4 & P5- Local Slab Failure Final Report

WJE No. 2022.0759

Dear Mr. Casolo:

Per the request of the City of Stamford, CT, Wiss, Janney, Elstner Associates, Inc. (WJE) has reviewed the partial collapse of the 5<sup>th</sup> floor amenity deck at the Allure, which is located within the Harbor Point development in Stamford, CT. The following is our final report on the matter.

### DESCRIPTION OF STRUCTURE

The Allure, located at 850 Pacific Avenue, also known as P4 & P5 is a 22-Story residential structure with a single basement level. It was built ca. 2019. Level Basement through Level 4 primarily consists of parking with some apartments and amenity spaces along the perimeter of all four sides. Level 5 primarily consists of an exterior amenities terrace with a pool and planters. Apartments are located along the east elevation. The overall dimensions of Levels B-5 are approximately 420 ft. north/south by 204 ft. east/west. Floor to floor heights range between 9.75 ft. and 13 ft. Above Level 5, two residential towers referred to as the north and south tower, continue up to Level 22. The North Tower has overall plan dimensions of approximately 187 ft. north/south by 79 ft. east/west and the South Tower has overall plan dimensions of approximately 156 ft. north/south by 79 ft. east/west. Typical floor-to-floor heights of both towers are 9.75 feet (Figure 1).

The building structure is founded on pile caps that are supported by 14 in. diameter pressure injected piles. Floors 1-4 consist of either 7.5 in. or 8 in. thick, post-tensioned, cast-in-place concrete flat plates<sup>1</sup>. The flat plates have uniformly spaced draped<sup>2</sup> post tensioning monostrand tendons that are typically oriented in the east/west direction at 3 ft. on center. Banded, draped monostrand tendons are oriented in the north/south direction at the column lines. Conventional reinforcing is also provided with a continuous bottom bars in both directions and top bars in both directions at and near the columns. Additionally, stud rails<sup>3</sup> are provided at some, but not all, columns. Column spacings vary from approximately 12 ft. to 24 ft.

---

<sup>1</sup> A "flat plate" is a reinforced concrete slab of without beams or drop panels.

<sup>2</sup> Draped tendons refers to the elevation profile of the strands which are typically located high in the slab at column lines and low in the slab at midspans.

<sup>3</sup> Stud rails are welded assemblies of steel strips and headed studs that are positioned around columns to enhance the punching shear strength of the slabs

in the north/south direction and approximately 8.25 ft. to 27.75 ft. in the east/west direction. The columns consist of cast-in-place concrete and are conventionally reinforced. A 3 in. wide expansion joint separates the north side of the Level B-5 structure from the south side of the structure.

At the Level 5, the slab is 12 inches thick at the western portion where the pool and outdoor amenities terrace are located and are accessible. At inaccessible areas at the northwest and southwest portions of Level 5, the slab is 8 inches thick. At the eastern portion of Level 5, where the residential apartments are located, the slab is 7.5 in thick. The slab at Level 5 has uniformly spaced, draped, monostrand tendons that are typically oriented in the east/west direction at 3 ft. on center. Banded, draped, monostrand tendons are oriented in the north/south direction at the column lines. Conventional reinforcing is also provided with a continuous bottom mat in both directions and top bars in both directions at the columns. Additionally, stud rails are provided at select columns. At level 5, some reinforced concrete beams are provided particularly beneath the amenities space. In order to allow for transitions between the occupied interior space and occupied amenities space, a step in the slab top surface is provided to allow for the installation of waterproofing and a pedestal paver system with the amenities space. A 3 in. expansion joint is provided to separate the north side of the structure from the south side of the structure.

The north and south towers (floors 6 to 22) have the same structural system which a slab thickness of 7.5 inches. The flat plates have uniformly spaced draped tendons that typically span in the east/west direction at 3 ft. on center. The live end anchors are provided on both elevations based on the tendon layout. Draped banded tendons span in the north/south direction at the column lines. Conventional reinforcing is also provided with a continuous bottom mat in both directions and top bars in both directions at the columns. Additionally, stud rails are provided at select columns. Post-tensioned cantilever balconies are provided on all elevations.

The building is clad with an exterior insulation and finishing system (EIFS) and has a flat roof. The building design architect was EDI International (EDI) and the design structural engineer of record is Henderson Rogers Structural Engineers (HRSE). The state of Connecticut required threshold structural peer review was performed by Loureiro Engineer Associates, Inc.

## **PARTIAL COLLAPSE**

On February 1, 2022, a partial collapse of the Level 5 slab occurred in the amenities area. The collapsed area measures approximately 20 ft. east/west by 15 ft. north/south and is bound within column lines G9/G10 and TE/GA (Figures 4 & 5). The section of slab that collapsed is adjacent to a transition zone where there is a 10-inch-high step in the slab along its north and east sides. At the south edge of the collapsed area, there is an expansion joint. The step in the slab was provided to accommodate waterproofing and pavers installed at the topside of the amenities deck. The original design drawings indicate that the east/west oriented post tensioning at this area was to be continuous through slab step and the concrete slab construction was to be monolithic (Figure 6).

Immediately following the collapse, HRSE issued a letter entitled: *"Harbor Point The Allure- Local Slab Failure at the Amenities Deck"* dated February 2, 2022 (Appendix A). This letter indicates that:

- The failure is local and isolated within a segment of the stepped slab region of the amenities deck.

- The condition should not impact the global stability of the overall building structure and areas outside of the impacted region can be considered safe to occupy.
- Shoring will be needed to prevent future serviceability issues in the garage.
- The stepped slab condition within an interior bay is unique to this building and does not occur at any of the other Harbor Point P-Block Buildings.

Additionally, a second engineer, EDM was hired by BLT to review the partially collapsed structure. They issued a letter entitled: *"Emergency Investigation of Floor Failure"* dated February 1, 2022 (Appendix B). This letter indicates that:

- The failed slab appeared to be an isolated condition not having influence on the rest of the garage or residential structure. Therefore, the structural integrity of the remaining garage and residential building structure are not affected by this event and it does not present a threat to life and safety of the building's occupants.
- It was advised to shore and brace the immediate garage structure beneath the location of the failed slab to help distribute the added weight of the fallen slab. Additionally shoring directly underneath the sloping section of concrete slab will prevent motion of the damaged slab until a method of removal has been established.

Baker Concrete Construction (BCC) issued a *"Work Plan for Remedial Action"* dated February 4, 2022, which included the following (Appendix C):

- A preliminary shoring and safety plan, which was immediately installed.
- A proposed slab stabilization and removal plan which had not been implemented at the time of the WJE review.

## OBSERVATIONS

John Cocca, P.E., Andrea Shear, P.E. and Hannah Rakowski, P.E. of WJE visited the site on February 5, 2022, to review the partially collapsed slab. The following conditions were noted:

- The partially collapsed Level 5 slab measures 20 ft by 15 ft. It is a portion of the lower slab within the bay bordered by column lines G9/G10 and TE/GA. There is a crack in the west end of the slab and the east end of the collapsed portion of the slab is resting on the 4<sup>th</sup> floor level (Figures 7 and 8).
- The PT is not continuous as shown in the design and shop drawings at the slab step transition. The live (stressing) end anchorages were observed at the east end of the collapsed slab (Figure 9)
- There is a cold joint at the step in the slab at this location there is no reinforcement crossing the joint and the concrete is not roughened (Figure 10).
- Review of the failure plane indicates that there doesn't appear to be any reinforcing steel in the lower slab located higher than approximately 1-3 in. above the bottom of the slab (Figure 11 through 12).

- WJE utilized a ground penetrating radar (GPR)<sup>4</sup> to identify the PT tendons and mild reinforcing in the east/west direction of the partially collapsed slab. Starting from the north end of the slab, the first band is approximately 14.5 in. from the edge and the next two bands are spaced at approximately 36 in. and 43 in. on center. This results in an approximately 83.5 in. section of the south end of the slab that does not have any tendons (Figure 10). Furthermore, WJE used the GPR to identify the tendons at the remaining west lower slab. The existing 3 bands of tendons span over the existing B21 beam at the GA column line and continue west. Due to spray foam insulation on the ceiling, WJE was not able to verify if there are additional tendons to the south outside of the failure area as none were visually observed at the failure plane. (Figure 13-15).
- It is also noted that an additional north-south spanning beam exists between column line T12/T13 along GD that is not shown in the design or shop drawings provided to WJE (Figure 16).
- Since the tendons were observed to be anchored in the lower slab and not continuous across the step, it is unclear to WJE how the upper slab is reinforced or supported (Figure 17).

## DOCUMENT REVIEW

Following our visit, HRSE issued a report entitled: *"Harbor Point- The Allure: Opinion of Causation- Local Slab Failure"* dated February 9, 2022 which indicated the following (Appendix D):

- The cause of the collapse is a result of the discontinuity of the PT across the slab step and that a horizontal construction joint was placed within the step transition with no shear transfer mechanism resulting in inadequate slab support. The report also indicates that the PT shop drawings show the tendons as continuous.

WJE issued a report entitled: *"Harbor Point- The Allure- Local Slab Failure Progress Report"* dated February 15, 2022 (Appendix E). The report included the observations above as well as the following preliminary findings:

- Based on our initial review we agree that the likely cause of the collapse is associated with the lack of continuous PT and inadequate support at the slab step between the upper and lower slab.
- The report also requested that various documents including the full set of design drawings, approved PT shop drawings, and approved mild steel shop drawings be provided to WJE. The letter also poses questions to HRSE prior to the City's approval to remove the existing partially collapsed slab.

HRSE issued a response letter to the WJE report entitled: *"Harbor Point- The Allure: Response to WJE Letter"* dated February 15, 2022 (Appendix F). Key points from this letter are the following:

- The as-built condition of the step does not appear to conform with the structural drawings and PT shop drawings, and the Engineer-of-Record (EOR) was not notified by the special inspector about this

---

<sup>4</sup> GPR is a non-destructive testing device that is rolled along the concrete surface and probes interior conditions using high frequency radar waves. Voids in the concrete, the bottom surface, or the presence of metal embedments such as reinforcing or post-tensioning tendons, are reflected in the GPR display.

non-conformance. The EOR was not aware of this condition, and no sketches/drawings/calculations were provided to the EOR for review.

- HRSE does not have special inspection reports for this area, as they were not provided to the EOR for review.
- The as-built condition of the PT layout in the partially collapsed area does not appear to conform with the structural drawings and PT shop drawings. There should be six (6) bundles of PT cables extending from low slab into the high slab at the step and anchoring at the expansion joint. Slab assessment for missing PT cables will be conducted in our Phase 2 of the Work Plan.

WJE was requested on behalf of the city to review the February 4, 2022, BCC plan for slab stabilization and removal of the partially collapsed slab. WJE reviewed the documents and issued a letter entitled: "*Harbor Point- The Allure- Local Slab Failure Demolition Application*" dated February 18, 2022 (Appendix G). In this letter WJE provided recommendations on the proposed temporary shoring and suggested that prior to demolition, material samples be taken in the event that further analysis was required. BCC updated their demolition plan and resubmitted it on February 22, 2022 (Appendix H). The plan was ultimately approved by the city and a demolition permit was issued by the City. The following samples were taken and are currently located in the Stamford Engineering Department:

- 6 concrete cores from partially collapsed slab.
- Samples of conventional reinforcement and PT strands.

On February 18, 2022, WJE issued a report entitled: "*Harbor Point- The Allure- Special Inspection Questions*" (Appendix I). This report poses questions regarding the special inspections that were performed and HRSE's role as the special inspection coordinator. WJE requested copies of the special inspection reports for review.

HRSE responded to the WJE February 18 letter with a letter issued on February 22, 2022 entitled: "*Response: Harbor Point-The Allure-Special Inspection Questions*" (Appendix J). In this report, HRSE indicates the following:

- HRSE have been re-reviewing all of the inspection reports, PT and mild steel shop drawings, and the recently received pour sequence document, correspondence, and photographs from Baker Concrete. HRSE intends to identify locations for review with the City of Stamford and/ or their Engineering or technical representative, as well as the Design, Development, and Construction teams where HRSE finds potential discrepancies or where additional testing may be required to determine or verify as-built conditions.
- Additionally, HRSE explains they feel they performed their duty as the special inspection coordinator and provided the "*Statement of Special Inspections*" dated 2/27/2018 as well as their signoff letter dated May 18, 2020 and the special inspector, Coastal Materials Testing Lab, LLC (CMTL), signoff letter dated May 12, 2022 indicating that all inspections were completed in accordance with the statement of special inspections (Appendix K).
- Finally, HRSE provided all special inspection reports for review.

WJE reviewed the following documents to understand the design and construction of the building with a particular emphasis on the Level 5 slab as this is where the partial collapse occurred.

- Architectural Drawings issued by EDI issued for permit on October 19, 2017.
- Structural Drawings issued by HRSE for permit on January 22, 2018
- Post Tensioning Shop Drawings issued by CCL dated March 7, 2018
- Partial Rebar Shop Drawings issued by Gerdau dated April 12, 2018.

WJE reviewed the provided special inspection reports which were completed by CMTL particularly for the Level 5 slab construction. Attached in Appendix L is the Level 5 slab pour sequence as well as the special inspection reports for all pours at Level 5. None of the reports indicate that the special inspector had the PT shop drawings on site at the time of their visit, only the Gerdau rebar drawings are referenced in the reports and none of the inspection reports mention the post-tensioning or the CCL shop drawings. All reports indicate "area ready for concrete placement." When further documentation regarding the post-tensioning placement inspections were requested by the City, the only thing provided by CMTL was a March 25, 2022 letter entitled "*Building P4-P5 (Permit #B-17-782)*" stating that they did in fact inspect the post-tensioning tendons for layout, profile and bundling (Appendix M). No reports, photos or additional information was provided. Based on this, WJE recommended that two typical bays be scanned using ground penetrating radar (GPR) at the north and south sides of the structure to verify that the post-tensioning layout was done in accordance with the approved shop drawings. Additionally, GPR scanning was done directly adjacent to the partially collapsed area as directed by HRSE.

WJE reviewed the March 31, 2022 and June 7, 2022, Baker Concrete Construction (BCC) reports entitled: "*Harbor Point Allure Block P4-P5*" (Appendix N). These reports presents the findings of GPR scanning that was completed at the topside of the Level 5 slab directly adjacent to the area of the partial collapse and at the underside of two typical bays at Level 5 slab. Additionally, while on-site on May 31, 2022, WJE reviewed the markings at the underside of the slab from the scanning performed by Baker. The following was noted in the reports:

- BCC subcontracted the scanning to Ground Penetrating Radar Systems, LLC (GPRS)
- Uniformly spaced tendons were documented with spacings and drapes that appear to match the approved shop drawings at all scanning locations
- Banded tendons at the column line were documented with spacings and drapes that appear to match the approved shop drawings at all scanning locations.

On March 11, 2022, HRSE submitted their initial repair drawings and calculations to the City for approval of the repair of the partially collapsed slab. WJE was asked to peer review the design on behalf of the City. The peer review consisted of review of the repair design drawings as well as review of the calculations for the design.

While reviewing the approved shop drawings and the original design drawings for the 5<sup>th</sup> floor slab, it was determined that at all of the slab steps at the Level 5 slab, the post-tensioning was dis-continuous at the step (Appendix O). WJE reviewed a March 21, 2022, letter from HRSE entitled: *Response: Harbor Point-The Allure-Special Inspection Questions- WJE Comment 1*" which states the following (Appendix P):

- HRSE recently discovered that the post tension engineer, CCL, modified the original design intent shown on the Construction Documents at the stepped plaza deck. Instead of running the tendons continuous through the step, they were terminated at the upper and lower slab faces, similar to (but not the same) as the collapsed slab area.
- This modification altered the design and behavior from continuous flat plate spanning between columns to a cantilevered slab with opposing ends of the cantilever occurring at the step.
- CCL and HRSE independently developed new structural models of the as-built condition and they reviewed each other's models.
- One of the models found a slight overstress in three isolated locations when subject to the code prescribed live loads.
- As a result two existing beams were strengthened and one new beam was added at the garage in addition to the repairs for the partial collapse.

WJE completed the peer review of the repair design and the permit for the re-construction was issued on 4/28/2022 (Appendix Q). WJE was engaged by the City to perform construction period services during the repair of the slab. WJE reviewed the submittals approved by HRSE and performed site visits at key points during the construction. Site visit reports were provided to both the City, BCC and HRSE. All the reconstruction work was found to have been completed in accordance with the approved construction documents.

Finally, WJE was provided with a copy of the Adapt Builder models of the Level 5 slab which were independently reviewed. WJE issued a letter to HRSE with comments on the model for review (Appendix R). The comments pertained to loading of the model, material properties used and questions regarding the top bars.

HRSE responded to our comments in an August 11, 2022 letter entitled "*Response: Harbor Point- The Allure-Stamford Model Review- WJE Comments*" (Appendix S).

- HRSE provided clarifications on their model loadings that appear reasonable.
- Although HRSE did not use the ACI method to determine concrete strength based on the actual concrete break strengths, they feel as though they used conservative low-end values based on their review of the break strengths.
- Finally, there remains a couple isolated areas where the number of top bars provided at the columns does not meet the minimum requirements of ACI. HRSE has indicated and provided documentation that at these locations, the bars are not required for strength. ACI commentary indicates that these bars are provided for crack control and ductility. Due to the slab being a 2-way flat plate, ACI requires the design be based on an uncracked section therefore the bars are not needed for crack control. HRSE also cites a PTI reference for the bars not being necessary other than the code requiring them.

## CONCLUSIONS

Based on our review WJE concludes the cause of the collapse is associated with the lack of continuous PT and a cold joint at the slab step transition between the upper and lower slab. The as-built condition

results in a 20 ft. cantilevered slab span east of column line GA. This is a change to the structural system that doesn't appear in either the provided original design drawings or approved PT shop drawings.

Since the as-built condition was not documented on the shop drawings that were reviewed and approved by the EOR, and there were no issued revised sketches from the EOR, the special inspector should have issued a non-conformance report for this condition during his review of the installed post tensioning prior to the concrete pour. It is our opinion that the special inspector never reviewed the post tension layout prior to concrete placement as none of their reports mention the post tensioning or the shop drawings. The special inspection reports only reference the conventional reinforcing steel and the "ready for concrete placement" is solely based on the conventional steel placement. These reports were reviewed by HRSE and the missing information pertaining to PT was never identified.

BCC, the concrete sub-contractor, should have issued a request for information (RFI) from HRSE and CCL while installing the post-tensioning in the area of the collapse since the as-installed layout is not found in any documentation from HRSE or CCL provided to us.

HRSE, as the special inspection coordinator, should have been reviewing the special inspection reports as the work was progressing. In our opinion, they should have noticed that there was no documentation in regarding the required inspections for the post tensioning layout, drape and bundling in any of the reports nor a mention that the inspector had the CCL shop drawings with him on site. In our opinion, this oversight should have been corrected by the time the construction reached Level 5. Additionally, HRSE approved the Level 5 floor post tensioning shop drawings without realizing there was a major structural design change in the CCL drawings that resulted in additional beam repairs to the building outside of the area of the collapse.

Should you have any questions, please feel free to contact is

Sincerely,

**WISS, JANNEY, ELSTNER ASSOCIATES, INC.**



John Cocca, P.E.  
Associate Principal & Project Manager







Figure 1- Overall View of Allure. West Looking East




Figure 2- Collapse Location From Structural Drawings




Figure 3- Collapse Location from Architectural Drawings



Figure 4- Partially Collapsed 5<sup>th</sup> Level Slab. Looking East to West




Figure 5- Partial Floor Plan from HRSE Report




Figure 6- PT Step Detail from Original Drawings and HRSE Report



Figure 7- Partially Collapsed Slab looking West



Figure 8- Shear Failure at West End of collapsed slab (left arrow). Note B21 Beam (right arrow). Collapsed Area looking South



*Figure 9- Live End Anchorages at East End of Lower Collapsed Slab (Red Arrow)*



*Figure 10- Formed cold joint within transition band of stepped slab, East End of Collapsed Slab*



*Figure 11- No top reinforcement at failure plane Northwest Portion of Collapsed Slab. Note smooth formed surface at underside of upper slab at transition.*



*Figure 12- No Top reinforcing Steel Crossing Failure Plane. View Looking North to South at West Failure Plane. Exposed bars exposed are bottom bars.*



Figure 13- PT Layout at Slab Looking East to West. Red lines indicate positions of PT strands



Figure 14- Underside of lower slab to west of partial collapse. Arrow indicates 83.5 in. wide region where tendons were missing in collapsed slab. WJE could not scan because of Insulation.




Figure 15- Sketch of Existing PT Layout





Figure 16- Added Beam Not Shown in any Drawings at Line GD (arrow)



Figure 17- Upper Slab Reinforcement in the step transition Area adjacent to the Collapsed Slab is not evident (arrow band).







February 2, 2022

Mr. Tim Yahn  
Managing Director of Construction  
**Building and Land Technology**  
1 Elmcroft Road – Suite 500  
Stamford, CT 06902

**RE: Harbor Points The Allure-Local Slab Failure at Amenities Deck  
850 Pacific Street, Stamford CT**

Dear Tim:

Yesterday afternoon, we were advised of a partial floor failure at the amenities deck (Level 5) above the existing parking garage. Subsequent our discussion and review of the photos, we visited the site this morning to assess the condition in person and found the floor failure to be local and isolated within a segment of the stepped slab region of the amenities deck. Based on our findings at the time of our visit, the condition should not impact the global stability of the overall building structure and the areas outside of the impacted region can be considered safe to occupy. Shoring will be needed; however, in the shaded regions of the attached plan to prevent future serviceability issues until the area can be properly repaired. We should note that the failed stepped slab condition within the interior bay is unique to this building and does not occur at any of the other Harbor Points P-Block buildings.

We hope you find this information useful. Please contact our office should you have any questions or need additional information regarding this matter.

Respectfully,  
**Henderson Rogers Structural Engineers, LLC**

A handwritten signature in black ink, appearing to read "Madison H. Henderson".

Madison H. Henderson, P.E.  
Principal




02/02/2022

Cc: Ralph Martin (BLT); Vivek Gurjar, PE (HRSE); Ben Downing, PE (DCE)

Encl: Partial Plan

EXHIBIT A



1 5TH FLOOR PLAN - SOUTH  
 10/11/18



KEY PLAN

**CONSTRUCTION NOTES:**

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL BUILDING CODE (IBC) AND THE INTERNATIONAL MECHANICAL AND ELECTRICAL CODE (IMC).
2. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE NATIONAL ELECTRICAL CODE (NEC) AND THE NATIONAL MECHANICAL CODE (NMC).
3. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) CODES.
4. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
5. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE) CODES.
6. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
7. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
8. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
9. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
10. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
11. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
12. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
13. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
14. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
15. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
16. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
17. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
18. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
19. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.
20. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL BUILDING CODE (IBC) AND THE INTERNATIONAL MECHANICAL AND ELECTRICAL CODE (IMC).

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE NATIONAL ELECTRICAL CODE (NEC) AND THE NATIONAL MECHANICAL CODE (NMC).

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.

ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME) CODES.





February 01, 2022

**architecture**  
**engineering**  
**management**

Mr. Tim Yahn  
Managing Director of Construction  
Building and Land Technology  
1 Elmcroft Road – Suite 500  
Stamford, Connecticut 06902

Re: Emergency Investigation of Floor Failure  
Harbor Point, Block P4-P5, 850 Pacific Street, Stamford, Connecticut

Dear Mr. Yahn,

On the afternoon of February 1<sup>st</sup>, I received a phone call from you indicating that a section of concrete slab at the above referenced location had failed. You requested that I visit the site as soon as possible to make a preliminary evaluation of the failure condition. In addition, determine the nature of this structural failure and whether there was reason for concern that further damage may develop making it necessary to take additional steps to protect life and safety of those in the garage and in the adjacent residential units. I arrived on site at around 5:00 pm. My initial observations were that a section of concrete roof slab (fifth floor level) had partially collapsed with one end falling to the fourth-floor parking deck below. The other end of the of the concrete slab remained connected to the fifth floor. According to BLT staff the location of the failed concrete slab was approximately between column lines TE/GA and G9/G10 at the fifth-floor level which happens to be the roof over this section of parking.

The failed slab appeared to be an isolated condition not having influence on the rest of the garage or residential structure. Therefore, the structural integrity of the remaining garage and residential building structure are not affected by this event and does not present a threat to life and safety of the building's occupants.

It was advised to shore and brace the immediate garage structure beneath the location of the failed slab to help distribute the added weight of the fallen slab. In addition, shoring directly underneath the sloping section of concrete slab will prevent additional motion of the damaged slab until a method of removal has been established.

It does not appear that the fourth-floor parking slab was damaged as a result of the slab falling from the fifth floor and impacted the fourth-floor slab. Once the damaged slab is removed, it would be advisable to re-examine that section of the fourth-floor parking slab for damage that was not visible earlier. It would be prudent to consult with the design structural engineer to determine what may have happened.

If you have any questions regarding our preliminary observations, please contact us at your earliest convenience.

**pittsfield, ma**  
**uniorville, ct**  
**troy, ny**

Sincerely,

**edm**

Edward G. Shelomis, P.E. & L.S.  
Director of Engineering

**888.336.6600**

**www.edm-ae.com**





## Harbor Point, Block P4-P5, 850 Pacific Street, Stamford, Connecticut Work Plan for Remedial Action Level 5 Slab

The purpose of this work plan is to provide a phased approach (process) to safely stabilize and remove the affected slab area on the Allure (P4-P5) building in Stamford CT. This plan is limited to the first two phases of work:

- Preliminary Shoring and Safety
- Slab Stabilization and Removal

A work plan for the third phase, Slab Reconstruction, will be submitted separately once Henderson Rogers Structural Engineers (HRSE), the engineer of record, has prepared the plans for slab replacement.

### 1. Phase 1 - Preliminary Shoring and Safety

#### a. Initial Response

- i. Building and Land Technology (BLT) installed security fencing around the affected area on Level P4 and access to the area from the inside the building and on the Plaza Level (Level 5) was safe guarded.
- ii. BLT contacted a local structural engineer from EDM to provide a preliminary evaluation of the structure and to recommend initial safeguards of the garage and surrounding structure. See attached EDM letter dated February 1, 2022.
- iii. BLT addressed EDM's recommendation to stabilize the fallen slab by installing 6x6 dimensional wood posts on two sides of the fallen slab and steel post shores were installed on the level immediately below the affected area.
- iv. Two additional lines of 6x6 dimensional wood posts have been installed under the fallen slab to provide additional support and to further distribute the loads the fallen slab is imposing on the Level 4. The wood posts were cut and braced together as a unit beside the fallen slab and will be slid into place so that no one entered the area beneath the fallen slab.

### 2. Phase 2 - Slab Stabilization and Removal

#### a. Slab Stabilization— Reference HRSE Letter dated February 2, 2022, attached.

- i. The HRSE letter identifies the two areas that require temporary shoring, the area immediately below the fallen slab (marked in Red) and a larger area adjacent to the fallen slab (marked in Blue).
- ii. Baker has completed a temporary shoring plan showing the density and number of levels that will be temporarily shored. This sealed plan will be included as a separate document.
- iii. This temporary shoring will be installed prior to the issuance of the demolition permit.
- iv. The temporary shoring plan has been designed to allow for the garage levels Basement, Level 1, Level 2, and Level 3 to remain in use during the Slab Removal and Slab Reconstruction phases. The temporary shore layout has drive aisles to allow cars to pass through the shored areas. See the cross sections on the attached temporary shoring plan.

v. Barriers will be installed at the drive aisles to prevent any vehicles from hitting the temporary shores.

b. Slab Removal

- i. This work plan along with the attachments will be submitted to the City of Stamford, Building Inspection Department for issuance of a demolition permit.
- ii. Once the permit has been issued, Structural Technologies, a Baker subcontractor, will perform the slab removal work.

iii. The following is an overview of the slab removal plan:

- 1. Post tension slab tendons P4-84, 85 and 86 will be exposed at Level 5, adjacent to the fallen slab to relax any remaining tension. See attached CCL PT shop drawing PT 2.10 5<sup>TH</sup> Floor Slab Tendon Layout.
- 2. The fallen slab will be safely demolished using remote controlled machines so that no workers will be on or under the fallen slab during the demolition process.
- 3. The demolition work will be confined to the area safeguarded by the security fencing.
- 4. A forklift will be used to remove the concrete debris to a dumpster or dump trucks at the ground level. This debris will be removed from the premises daily.

iv. Structural Technologies will present their specific means and methods for the slab removal and safety plan in a Pre-Construction meeting prior to starting this work.

v. The shores installed to stabilize the area below the fallen slab (Red Area) will remain in place until the Slab Reconstruction phase is completed.

vi. The shores installed in the area adjacent to the fallen slab (Blue Area) will be removed once the slab tendons at Level 5 are re-stressed.

Attachment 1: EDM letter dated February 1, 2022

Attachment 2: HRSE Letter dated February 2, 2022

Attachment 3: CCL PT shop drawing PT 2.10 5TH Floor Slab Tendon  
Layout

Attachment 4: Baker Concrete Temporary Reshoring Plan and  
Calculations – Attached separately.

S105B

**HENDERSON**  
**ROGERS**  
structural engineers

February 2, 2022

Mr. Tim Yahn  
Managing Director of Construction  
**Building and Land Technology**  
1 Elmcroft Road – Suite 500  
Stamford, CT 06902


**RE: Harbor Points The Allure-Local Slab Failure at Amenities Deck  
850 Pacific Street, Stamford CT**

Dear Tim:

Yesterday afternoon, we were advised of a partial floor failure at the amenities deck (Level 5) above the existing parking garage. Subsequent our discussion and review of the photos, we visited the site this morning to assess the condition in person and found the floor failure to be local and isolated within a segment of the stepped slab region of the amenities deck. Based on our findings at the time of our visit, the condition should not impact the global stability of the overall building structure and the areas outside of the impacted region can be considered safe to occupy. Shoring will be needed; however, in the shaded regions of the attached plan to prevent future serviceability issues until the area can be properly repaired. We should note that the failed stepped slab condition within the interior bay is unique to this building and does not occur at any of the other Harbor Points P-Block buildings.

We hope you find this information useful. Please contact our office should you have any questions or need additional information regarding this matter.

Respectfully,  
**Henderson Rogers Structural Engineers, LLC**



**Madison H. Henderson, P.E.**  
Principal




02/02/2022

Cc: Ralph Martin (BLT); Vivek Gurjar, PE (HRSE); Ben Downing, PE (DCE)

Encl: Partial Plan

EXHIBIT A



1 1ST FLOOR PLAN - SOUTH

NOTES:  
1. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE BUILDING CODES AND REGULATIONS.  
2. ALL MATERIALS SHALL BE OF THE BEST QUALITY AND SHALL BE APPROVED BY THE ARCHITECT.  
3. ALL WORK SHALL BE COMPLETED WITHIN THE SPECIFIED TIME FRAME.  
4. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE DRAWINGS AND SPECIFICATIONS.  
5. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE LOCAL LAWS AND REGULATIONS.  
6. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE BEST PRACTICES OF THE INDUSTRY.  
7. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE ARCHITECT'S INSTRUCTIONS.  
8. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.  
9. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT PROGRAM.  
10. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT BUDGET.  
11. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SCHEDULE.  
12. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT QUALITY REQUIREMENTS.  
13. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SAFETY REQUIREMENTS.  
14. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT ENVIRONMENTAL REQUIREMENTS.  
15. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT COMMUNITY REQUIREMENTS.  
16. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SOCIAL REQUIREMENTS.  
17. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT ECONOMIC REQUIREMENTS.  
18. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT POLITICAL REQUIREMENTS.  
19. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT CULTURAL REQUIREMENTS.  
20. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT HISTORICAL REQUIREMENTS.  
21. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT LEGAL REQUIREMENTS.  
22. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT ETHICAL REQUIREMENTS.  
23. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT MORAL REQUIREMENTS.  
24. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPIRITUAL REQUIREMENTS.  
25. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT RELIGIOUS REQUIREMENTS.  
26. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT PHILOSOPHICAL REQUIREMENTS.  
27. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SCIENTIFIC REQUIREMENTS.  
28. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT ARTISTIC REQUIREMENTS.  
29. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT LITERARY REQUIREMENTS.  
30. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT MUSICAL REQUIREMENTS.  
31. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT THEATRICAL REQUIREMENTS.  
32. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT FILM REQUIREMENTS.  
33. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT TELEVISION REQUIREMENTS.  
34. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT RADIO REQUIREMENTS.  
35. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT INTERNET REQUIREMENTS.  
36. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT MOBILE REQUIREMENTS.  
37. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SOCIAL MEDIA REQUIREMENTS.  
38. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT VIDEO REQUIREMENTS.  
39. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT AUDIO REQUIREMENTS.  
40. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT GRAPHIC REQUIREMENTS.  
41. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT DESIGN REQUIREMENTS.  
42. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT CONSTRUCTION REQUIREMENTS.  
43. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT MAINTENANCE REQUIREMENTS.  
44. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT OPERATIONAL REQUIREMENTS.  
45. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SUPPORT REQUIREMENTS.  
46. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT TRAINING REQUIREMENTS.  
47. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT DEVELOPMENT REQUIREMENTS.  
48. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT RESEARCH REQUIREMENTS.  
49. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT ANALYSIS REQUIREMENTS.  
50. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT EVALUATION REQUIREMENTS.




EDT

HARBOR POINT  
BLOCK 2A, LPS  
SINGAPORE


NO.	DESCRIPTION	DATE
1	ISSUED FOR TENDERS	15/08/2018
2	ISSUED FOR CONTRACT	20/08/2018
3	ISSUED FOR WORK	25/08/2018
4	ISSUED FOR CORRECTION	30/08/2018
5	ISSUED FOR REVISION	05/09/2018
6	ISSUED FOR APPROVAL	10/09/2018
7	ISSUED FOR COMPLETION	15/09/2018

1ST FLOOR PLAN

S105B








ATTACHMENT 2  
1 Page

NOTES

1. ADD SOLID WOOD WEDGES TO MAKE EXISTING 2x6 S FIT SNUG
2. ADD 2x4 CLEATS TO TALLEST ROW OF POSTS
3. ADD 4x6 ON LEVEL 4 BETWEEN COLLAPSED SLAB EDGE AND COLUMN (3 LOCATIONS) SNUG FIT MAIL PLYWOOD GUSSET ON 4x6 WITH 16d NAILS @ 12" O.C. TO EACH MEMBER
4. ADD ADDITIONAL ROW OF 4x6 POSTS (SHOWN IN SECTION 2).
5. REMOVE LEFT ROW OF POSTS (IN SECTION 2), ONE AT A TIME AS THE SLAB REMOVAL PROGRESSES.
6. DETENSION CABLES  
START DEVOLUTION OF SLAB ON LEFT SIDE UPPER END OF COLLAPSED SLAB. WORK IN DOWN HILL DIRECTION TWO OR THREE FEET THEN WORK ACROSS THE SLOPE TO REMOVE THE SLAB FROM THE HIGH END TO THE LOWER END OF THE SLAB
7. MAINTAIN AS MUCH OF THE TEMPORARY SHORING UNDER THE SLAB AS POSSIBLE DURING SLAB REMOVAL.
8. RESHOPPING SHOWN ON SHEET HP-L5-R-1 DATED 02/04/22 SHALL BE IN PLACE PRIOR TO DETENSIONING THE TENDONS.



DESIGN GROUP ARCHITECTS  
700 COLONIAL AVE. SUITE 200  
HARTFORD, CONNECTICUT 06103  
TEL: 860.234.1234 FAX: 860.234.1234

PROJECT: HARBOR POINT BLOCK P4-P5  
DATE: 02/11/22  
DRAWN BY: MBS  
CHECKED BY: K.B.H.

HARBOR POINT BLOCK P4-P5  
STAMFORD, CT

DRAWN BY: MBS  
DATE: 02/11/22  
CHECKED BY: K.B.H.  
DATE: 02/17/22  
JOB #: 10900  
SCALE: 1/11

Plan North  
HARBOR POINT BLOCK P4-P5  
LEVEL 5  
SHORING  
HP-L5-F-1







February 9, 2022

Mr. Tim Yahn  
Managing Director of Construction  
**Building and Land Technology**  
1 Elmcroft Road – Suite 500  
Stamford, CT 06902

**RE: Harbor Points-The Allure: Opinion of Causation-Local Slab Failure  
850 Pacific Street, Stamford CT**

Dear Tim:

It is our understanding that the City of Stamford, CT is requesting our professional opinion regarding the reason or cause for the recent partial collapse of the 5<sup>th</sup> level amenity deck of the Allure.

The following descriptions and conclusions are based on our review of the existing structural drawings, the post tension shop drawing submittals, photographs of the collapsed slab section, discussions with our in-house Engineers (including one who visited the site), discussions with the concrete sub-contractor, and discussions with the building developer/ owner.

The slab structure at the 5<sup>th</sup> level amenity deck and the lower garage levels consists of cast-in-place, two-way, flat plate construction reinforced with post tensioning and conventional mild steel. The tendons are banded in the north-south direction, with uniformly spaced bundles of three (3) or four (4) in the east-west. The collapsed area of slab is approximately 16'-0" x 20'-0" and bound within structural grids G9/ G10 and TE/ GE (See attached SK-1 partial plan). The failed section bears on the 4<sup>th</sup> level garage at the east side and is still connected near the 5<sup>th</sup> level beam on the west side. There is a ten (10) inch step in the slab around the failure boundaries of the north and east sides and a transition zone or widened/ deepened slab soffit to allow passage and transition of the tendons from the "high" to "low" slab (See attached SK-2, Section 10/ S4.10). The transition step is shown in section 10/S4.10 as monolithic and without a construction joint(s). A review of the structural PT layout plan S105PT-B and the post tension shop drawings indicates the uniform tendons to be continuous through the slab step transition and extending west to the opposite end of the garage, approximately 80 feet (See attached SK-2 and 3).


In our recent discussions and a review of the photographs we found that the tendons across the transition zone are missing, resulting in discontinuity of the post tension reinforcing across the slab step and the ability of the slab to span to beyond the transition slab step. Additionally, it appears from the photographs that a horizontal construction joint was placed at the step transition, with no shear transfer mechanism. A 2-inch recess was observed from the underside of the remaining 5<sup>th</sup> level slab. (See attached SK-4 and Photo).

We anticipate that the uniform tendons, which extend west from the existing beam line along grid GA have also been compromised or relaxed, and that is why we requested reshoring to extend west to the edge of the next slab drop from the collapsed area.

Mr. Tim Yahn  
Building and Land Technology  
February 9, 2022  
Page 2 of 2

We hope you find this information useful. Please contact our office should you have any questions or need additional information regarding this matter.

Respectfully,  
**Henderson Rogers Structural Engineers, LLC**


  
Madison H. Henderson, P.E.  
Principal

Cc: Ralph Martin (BLT); Vivek Gurjar, PE (HRSE); Ben Downing, PE (DCE)

Encl: SK-1 thru SK-4; Photograph

  
  
02.09.2022


**SK-1**



**SK-2**

SEE PLAN FOR SLAB  
THK AND REINF

SEE PLAN  
TO SLAB



SEE PLAN FOR SLAB  
THK AND REINF

SEE PLAN  
TO SLAB

PT CABLE TO BE  
SWEEPED THROUGH  
SLAB DEPRESSION  
10A: NO PT CABLE

10 10A


SECTION

3/4" = 1'-0"


**S410**


**SK-3**

CABLES NOT CONTINUED TO THE EDGE OF EXPANSION JOINT



**SK-4**











Wiss, Janney, Elstner Associates, Inc.  
2 Trap Falls Road, Suite 502  
Shelton, Connecticut 06484  
203.944.9424 tel  
[www.wje.com](http://www.wje.com)

February 13, 2022  
Revised 2/15/2022  
Louis Casolo, P.E.  
Engineering Department  
City of Stamford  
888 Washington Blvd, 7th Floor  
Stamford, CT 06904

## Harbor Points- The Allure- Local Slab Failure Progress Report

WJE No. 2022.0759

Dear Mr. Casolo:

Per the request of the City of Stamford, CT, Wiss, Janney, Elstner Associates, Inc. (WJE) has reviewed the partial collapse of the 5<sup>th</sup> floor amenity deck at the Allure, which is located within the Harbor Points development in Stamford, CT. WJE performed a site visit on February 5, 2022 to review the in-situ, undisturbed condition of the partially collapsed concrete deck. Following our visit, WJE was asked to review and provide comments on the February 9, 2022 letter entitled "Harbor Points- The Allure: Opinion of Causation- Local Slab Failure" and its attachments issued by Henderson Rogers (HR) who is the engineer of record (EOR) for the building. The following letter contains our initial comments on the provided information.

### BACKGROUND AND DESCRIPTION OF STRUCTURE

The Allure in Stamford, CT is a 22-Story residential structure that was built circa 2019. The first 4 levels of the building contain a parking garage and the west side of the 5<sup>th</sup> level is an amenities plaza deck. The structure typically utilizes a post-tensioned (PT), flat plate framing system and has overall dimensions of approximately 500 ft. north/south by 250 ft. east/west, however there are beams supporting the slab at some locations. The 5<sup>th</sup> floor amenities slab is typically 12" thick and column spacings vary from 17 ft. to 28 ft. in both directions.

On February 1, 2022 a partial collapse of the 5<sup>th</sup> floor amenities level occurred. The collapsed area is approximately 20 ft. east/west by 15 ft. north/south and bound within column lines G9/G10 and TE/GA (Figures 1 & 2). The section of slab that collapsed is adjacent to a transition zone where there is a 10" step in the slab along the north and east sides. At the south edge of the collapsed area there is an expansion joint (Figure 2). The step in the slab allows for the installation of waterproofing and pavers at the top side of the amenities deck. The original design drawings indicate that the east/west spanning PT at this area was to be continuous through the slab step and the concrete slab construction was to be monolithic (Figure 3).

WJE reviewed the HR report in which they indicate that the cause of the collapse is a result of the discontinuity of the PT across the slab step and that a horizontal construction joint was placed within the step transition with no shear transfer mechanism resulting in inadequate slab support. The report also indicates that the PT shop drawings show the tendons as continuous.

WJE was provided with the following drawings for review:

- S105B- 5<sup>th</sup> Floor Plan dated 4.20.2018 issued for construction by EDI International, P.C.
- S105PT-B 5<sup>th</sup> Floor Plan- PT dated 4.20.2018 issued for construction by EDI International, P.C.
- PT-2.10- 5<sup>th</sup> Floor Tendon Layout dated 7.2.2018 issued for approval, not for construction by CCL. No submittal stamp was provided on the drawings from the EOR.

## **OBSERVATIONS**

WJE visited the site on February 5, 2022 to review the partially collapsed slab. The following conditions were noted:

- The partially collapsed 5<sup>th</sup> level slab is confined to a 20 ft by 15 ft. portion of the lower slab at column lines G9/G10 and TE/GA. There is a crack in the west end of the slab in the failure area approximately 3 ft. east of the face of the north-south spanning B21 beam at column line GA and the east end of the collapsed portion of the slab is resting on the 4<sup>th</sup> floor level (Figure 4 & 5).
- The PT is not continuous as shown in the design and shop drawings at the slab step. The live (stressing) end anchorages were observed at the east end of the collapsed slab (Figure 6)
- There is a construction joint at the step in the slab at this location there is no reinforcement crossing the joint and the concrete is not roughened (Figure 7).
- Review of the failure plane indicates that there doesn't appear to be any steel in the lower slab located higher than approximately 1-3 in. above the bottom of the slab (Figure 8 and 9).
- WJE utilized a ground penetrating radar device to identify the PT tendons and mild reinforcing in the east/west direction of the partially collapsed slab. Starting from the north end of the slab, the first band is approximately 14.5 in. from the edge and the next two bands are spaced at approximately 36 in. and 43 in. on center. This results in an approximately 83.5 in. section of the south end of the slab that does not have any tendons (Figure 10). Furthermore, WJE used a GPR to identify the tendons at the remaining west lower slab. The existing 3 bands of tendons span over the existing B21 beam at the GA column line and continue west. Due to spray foam insulation on the ceiling, WJE was not able to verify if there are additional tendons to the south outside of the failure area as none were visually observed at the failure plane. (Figure 11). See drawings in Appendix A.
- It is also noted that an additional north-south spanning beam exists between column line T12/T13 along GD that is not shown in the design or shop drawings provided to WJE (Figure 12).
- Since the tendons were observed to be anchored in the lower slab and not continuous across the step, it is unclear to WJE how the upper slab is reinforced or supported (Figure 13).

## **DISCUSSIONS & RECOMMENDATIONS**

Based on our initial review we agree that the likely cause of the collapse is associated with the lack of continuous PT and inadequate support at the slab step between the upper and lower slab. The as-built condition results in a 20 ft. cantilevered slab span east of column line GA. This is a change to the structural system that doesn't appear in either the provided original design drawings or PT shop drawings. If it was

not documented on the shop drawings that were reviewed and approved by the EOR, the special inspector should have issued a non-conformance report for this condition and it should have been reviewed by the Engineer of Record or corrected by the Contractor. Prior to demolition of the collapsed area, WJE, on behalf of the City of Stamford Building Department has the following initial questions for the design/construction team.

- The design drawings and PT shop drawings provided to WJE to date, do not show the as-built condition at the step in the slab. Was this condition identified the special inspector as not conforming to the design? Was the EOR or PT Specialty Engineer aware of this condition? At any point was a sketch provided or reviewed by the EOR or PT Engineer for this change? Can you provide the specific special inspection reports for this location?
- The construction documents show both a top mat and bottom mat of conventional reinforcement within the PT slab with bars in both directions. In the area of the collapse there is no top steel. Is there supposed to be a top mat of reinforcement? Was this missing steel identified by the special inspector prior to concrete placement? Can you provide the specific special inspection reports for this location? In the event the top steel is missing, how do you plan to identify and assess the extent of the non-confirming steel?
- Is the identified PT layout correct in the area of the collapsed slab? Are there only supposed to be 3 groups of tendons? The drawings seem to indicate that the tendons should be equally spaced at approximately 3 ft. on center which would indicate that 1 additional band of tendons should have been provided in this area. For the remaining portion of the lower slab that spans west to the exterior wall, is the correct post tensioning layout provided or is a band of tendons missing? If missing, how do you plan to further assess this condition? Can you provide the specific special inspection reports for this location?
- Did the design team specify the beam between column line T12/T13 along GD that is not shown in the provided drawings? There are not details for it in the provided shop drawings. Provide documentation showing the design revisions adding the beam and reason that this change was made.
- What is the geometry (layout, drape, anchorage conditions) of the PT at the upper slab at the east end of the collapse? Is there a sketch or modified drawings for this area since the PT is not continuous? Have calculations been done to show this is sufficient in the new cantilevered arrangement?
- Could the contractor provide a description of the construction sequence of the 5<sup>th</sup> floor amenity slab?
- Please provide any other relevant information to the design, construction and inspection in this area.

This letter is based on our initial review of the provided information. Additional comments or requests may be made as additional information becomes available.



Sincerely,

**WISS, JANNEY, ELSTNER ASSOCIATES, INC.**

A handwritten signature in black ink, appearing to read 'J. Cocca'.

John Cocca, P.E.  
Associate Principal & Project Manager



Figure 1- Partially Collapsed 5<sup>th</sup> Level Slab. Looking East to West




Figure 2- Partial Floor Plan from HR Report




Figure 3- PT Step Detail from Original Drawings and HR Report



Figure 4- Partially Collapsed Slab looking West



*Figure 5- Shear Failure at West End. Note B21 Beam. Collapsed Area looking South*



*Figure 6- Live End Anchorages at East End of Lower Collapsed Slab*



Figure 7- Construction Joint Between Upper and Lower Slab. East End of Collapsed Slab




Figure 8- No top reinforcement at failure plane Northwest Portion of Collapsed Slab






Figure 9- No Top Steel Crossing Failure Plane Looking North to South at West Failure Plane




Figure 10- PT Layout at Slab Looking East to West



*Figure 11- Lower Slab to West of Collapsed Portion. 83.5 in. area with No Tendons in Collapsed Area. Cannot Scan Cause of Insulation.*



*Figure 12- Added Beam Not Shown in Drawings at Line GD*



*Figure 13- Upper Slab Reinforcement in the Area of the Collapsed Slab is Unknown.*





No	Date	Description
1	09/05/16	FOR APPROVAL
2	02/02/18	FOR APPROVAL

CLIENT: BAKER CONCRETE CONSTRUCTION  
 CONTRACT: HARVARD  
 DATE: 02/02/18

PROJECT: HARBOR POINT  
 BLOCK P4-P5  
 STAMFORD, CT

DRAWING TITLE: 5TH FLOOR  
 SLAB TENDON LAYOUT

DRAWING REFERENCE: 5TH FLOOR  
 PT-2.10



SLAB TENDON LAYOUT - 5TH FLOOR (SLAB THICKNESS 7 1/2" U.N.O.)  
 SCALE: 3/32"=1'-0"

**FOR APPROVAL**  
**NOT FOR CONSTRUCTION**  
 ENCAPSULATED  
 (ENCAPSULATED AND/OR)

DESCRIPTION	QUANTITY	UNIT	REMARKS
1.0000	1.00	EA	...
1.0001	1.00	EA	...
1.0002	1.00	EA	...
1.0003	1.00	EA	...
1.0004	1.00	EA	...
1.0005	1.00	EA	...
1.0006	1.00	EA	...
1.0007	1.00	EA	...
1.0008	1.00	EA	...
1.0009	1.00	EA	...
1.0010	1.00	EA	...
1.0011	1.00	EA	...
1.0012	1.00	EA	...
1.0013	1.00	EA	...
1.0014	1.00	EA	...
1.0015	1.00	EA	...
1.0016	1.00	EA	...
1.0017	1.00	EA	...
1.0018	1.00	EA	...
1.0019	1.00	EA	...
1.0020	1.00	EA	...
1.0021	1.00	EA	...
1.0022	1.00	EA	...
1.0023	1.00	EA	...
1.0024	1.00	EA	...
1.0025	1.00	EA	...
1.0026	1.00	EA	...
1.0027	1.00	EA	...
1.0028	1.00	EA	...
1.0029	1.00	EA	...
1.0030	1.00	EA	...
1.0031	1.00	EA	...
1.0032	1.00	EA	...
1.0033	1.00	EA	...
1.0034	1.00	EA	...
1.0035	1.00	EA	...
1.0036	1.00	EA	...
1.0037	1.00	EA	...
1.0038	1.00	EA	...
1.0039	1.00	EA	...
1.0040	1.00	EA	...
1.0041	1.00	EA	...
1.0042	1.00	EA	...
1.0043	1.00	EA	...
1.0044	1.00	EA	...
1.0045	1.00	EA	...
1.0046	1.00	EA	...
1.0047	1.00	EA	...
1.0048	1.00	EA	...
1.0049	1.00	EA	...
1.0050	1.00	EA	...
1.0051	1.00	EA	...
1.0052	1.00	EA	...
1.0053	1.00	EA	...
1.0054	1.00	EA	...
1.0055	1.00	EA	...
1.0056	1.00	EA	...
1.0057	1.00	EA	...
1.0058	1.00	EA	...
1.0059	1.00	EA	...
1.0060	1.00	EA	...
1.0061	1.00	EA	...
1.0062	1.00	EA	...
1.0063	1.00	EA	...
1.0064	1.00	EA	...
1.0065	1.00	EA	...
1.0066	1.00	EA	...
1.0067	1.00	EA	...
1.0068	1.00	EA	...
1.0069	1.00	EA	...
1.0070	1.00	EA	...
1.0071	1.00	EA	...
1.0072	1.00	EA	...
1.0073	1.00	EA	...
1.0074	1.00	EA	...
1.0075	1.00	EA	...
1.0076	1.00	EA	...
1.0077	1.00	EA	...
1.0078	1.00	EA	...
1.0079	1.00	EA	...
1.0080	1.00	EA	...
1.0081	1.00	EA	...
1.0082	1.00	EA	...
1.0083	1.00	EA	...
1.0084	1.00	EA	...
1.0085	1.00	EA	...
1.0086	1.00	EA	...
1.0087	1.00	EA	...
1.0088	1.00	EA	...
1.0089	1.00	EA	...
1.0090	1.00	EA	...
1.0091	1.00	EA	...
1.0092	1.00	EA	...
1.0093	1.00	EA	...
1.0094	1.00	EA	...
1.0095	1.00	EA	...
1.0096	1.00	EA	...
1.0097	1.00	EA	...
1.0098	1.00	EA	...
1.0099	1.00	EA	...
1.0100	1.00	EA	...

NOTES:  
 1 - REFER TO DETAIL 13PT-1.01 FOR ALL TENDON SWEEP AROUND OPENINGS.  
 2 - STRESSING TAIL TO BE A MAXIMUM OF 18". REFER TO DETAIL 3PT-1.01.  
 3 - REFER TO DETAIL 13PT-1.01 FOR TENDON ANCHOR LOCATIONS.  
 4 - REFER TO DETAIL 13PT-1.01 FOR TENDON ANCHOR LOCATIONS.  
 5 - REFER TO DETAIL 13PT-1.01 FOR TENDON ANCHOR LOCATIONS.





February 15, 2022

Mr. Tim Yahn  
Managing Director of Construction  
**Building and Land Technology**  
1 Elmcroft Road – Suite 500  
Stamford, CT 06902

**RE: Harbor Points-The Allure: Response to WJE Letter  
850 Pacific Street, Stamford CT**

Dear Tim:

Please see below responses to the comments/questions noted in the "Discussions & Recommendations" section of the letter issued by WJE, dated 2/15/2022.


- The as-built condition of the step does not appear to conform with the structural drawings and PT shop drawings, and the Engineer-of-Record (EOR) was not notified by the special inspector about this non-conformance. The EOR was not aware of this condition, and no sketches/drawings/calculations were provided to the EOR for review. No, we do not have special inspection reports for this area, as they were not provided to the EOR for review.
- For clarification, there is only supposed to be a #4 size rebar mat at the bottom of the slab in each direction. Additional top bars are provided at column locations in each direction. No, the EOR was not notified of any missing steel reinforcement prior to concrete placement, and we do not have special inspection reports for this location. Slab assessment for missing steel will be conducted in Phase 2 of the Work Plan.
- No, the as-built condition of the PT layout does not appear to conform with the structural drawings and PT shop drawings. No, there should be six (6) bundles of PT cables extending from low slab into the high slab at the step and anchoring at the expansion joint. Slab assessment for missing PT cables will be conducted in Phase 2 of the Work Plan. EOR was not notified by the special inspector about the non-conformance, and we do not have special inspection reports for this area.
- There was a beam mark "B21" at the questioned location shown on drawings dated "02.23.2018", and this beam was designed to support a column for the fitness club roof. The column and beam were both removed from the "IFC" drawings dated "04.20.2018", Sheet "S105.B", because of architectural changes. However, it appears that the concrete beam (B21) was constructed per drawings dated "02.23.2018".
- Presently, we do not know the geometry (cable layout, drape and anchorage) for the upper slab condition. No, we are not aware of any sketch addressing this change that was submitted to the EOR for review and no calculations have been provided to the EOR.
- Engineer-of-record does not have a copy of pour sequence for the level 5 slab.

Mr. Tim Yahn  
Building and Land Technology  
February 15, 2022  
Page 2 of 2

- We have attached mild steel reinforcement plans from the structural drawings and the rebar submittals.

We hope you find this information useful. Please contact our office should you have any questions or need additional information regarding this matter.

Respectfully,  
Henderson Rogers Structural Engineers, LLC



Madison H. Henderson, P.E.  
Principal

Cc: Ralph Martin (BLT); Vivek Gurjar, PE (HRSE); Ben Downing, PE (DCE)

Encl: Mild steel reinforcement plans; Rebar Submittal









Wiss, Janney, Elstner Associates, Inc.  
2 Trap Falls Road, Suite 502  
Shelton, Connecticut 06484  
203.944.9424 tel  
www.wje.com

February 18, 2022

Louis Casolo, P.E.  
Engineering Department  
City of Stamford  
888 Washington Blvd, 7th Floor  
Stamford, CT 06904

## **Harbor Points- The Allure- Local Slab Failure Demolition Application**

WJE No. 2022.0759

Dear Mr. Casolo:

Per the request of the City of Stamford, CT (City), Wiss, Janney, Elstner Associates, Inc. (WJE) has reviewed the "Harbor Points- The Allure- Phased Remedial Action Plan" issued by Henderson and Rogers Structural Engineers (HR) dated February 5, 2022. The purpose of this document is to obtain a permit from the City of Stamford to revise the existing shoring layout to allow the garage to be partially occupied, and to demolish and remove the existing partially collapsed portion of the 5<sup>th</sup> floor amenity deck. The following letter contains our comments on the provided information.

### **BACKGROUND AND DESCRIPTION OF STRUCTURE**

On February 1, 2022 a partial collapse of the 5<sup>th</sup> floor post-tensioned (PT) cast-in-place amenities level slab occurred. The collapsed area is approximately 20 ft. east/west by 15 ft. north/south and bound within column lines G9/G10 and TE/GA. (Figures 1 & 2). Immediately following the collapse, temporary shoring was provided both beneath the collapsed portion of the slab to stabilize it, as well as along the remaining de-tensioned east/west span between column lines G9/G10 and GF and GA.

On February 5, 2022, HR submitted a demolition and shoring plan to the City in order to obtain a permit to remove the existing partially collapsed slab.

The submission consists of the following:

- Reshoring design calculations submitted by Baker Concrete Construction (BCC) dated 2.4.2022
- A Level 5 Reshore Layout Drawings, HP-L5-R-1 dated 2.4.2022
- A work plan entitled "Harbor Point, Block P4-P5, 850 Pacific Street, Stamford, Connecticut Work Plan for Remedial Action Level 5 Slab"
- A Letter from EDM entitled: "Emergency Investigation of Floor Failure Harbor Point, Block P4-P5, 850 Pacific Street, Stamford, Connecticut
- A Letter from HR entitled: "Harbor Points The Allure- Local Slab Failure at Amenities Deck 850 Pacific Street, Stamford, CT.
- A drawing entitled 5<sup>th</sup> Floor Slab Tendon Layout, from the PT shop drawings, indicating the PT strands to be de-tensioned.

The proposed scope within this submittal consists of the following:

- Revise the existing shoring to allow for the basement, and Levels 1-3 of the garage to be re-opened. This is accomplished by installing shoring beams at the underside of the 5<sup>th</sup> floor level to span the drive isles and reshoring to grade. Barriers will be installed to prevent vehicles from hitting the temporary shores.
- Once the shoring is modified, the three existing bands of tendons in the collapsed portion of the slab will be exposed from the topside of the 5<sup>th</sup> floor slab adjacent to the collapsed area to relieve any remaining tension. The existing partially collapsed slab will then be demolished using remote controlled machines.

## DISCUSSIONS & RECOMMENDATIONS

Based on our review, we offer the following recommendations regarding the proposed shoring and demolition submission.

- WJE takes no issue with the proposed modified shoring layout which spans the drive isles. The City may want to review the protection around the shoring prior to allowing occupancy into the garage.
- The proposed demolition procedures outlined seem acceptable, however, WJE recommends that during this demolition, all the required information be gathered in the event that the partially collapsed slab and material properties need to be further analyzed by any party involved. This would include gathering the following information:
  - Take 6 concrete cores.
  - Take samples of the existing conventional reinforcement and existing PT strands.
  - Have an engineer on-site during demolition to develop a layout of the conventional reinforcement and PT including spacing, cover, bar size and drape.

If you have any questions, please feel free to contact us.

Sincerely,

**WISS, JANNEY, ELSTNER ASSOCIATES, INC.**



John Cocca, P.E.  
Associate Principal & Project Manager



## Demolition Plan for Collapsed Level 5 Slab

### Harbor Point, Block P4-P5, 850 Pacific Street, Stamford, Connecticut

The purpose of this plan is to provide a detailed process to remove the collapsed 5<sup>th</sup> Level slab at the Allure (P4-P5) building in Stamford CT. The previously submitted Remedial Work Plan dated February 4, 2022, is attached. The items outlined in Phase 1 – Preliminary Shoring and Safety and Phase 2, a. Slab Stabilization are complete. This plan provides further detailed plans to address Phase 2, b. Slab Removal.

#### Demolition Process Overview

1. Install additional shoring and bracing to the collapsed slab as shown in the attached Baker drawing HP-L5-F-1 prior to starting the demolition process.
2. Safeguard the remaining area on the 5<sup>th</sup> Level Amenity Deck to ensure no one can access the area to be detention.
3. A representative from Henderson Rogers and the designated Special Inspection Firm will be present to collect six (6) concrete cores from the slab prior to demolition. Samples from the existing conventional reinforcement and existing post tension strands (PT) will be collected and measurements taken to prepare an as-built drawing showing the layout of the reinforcement and PT including spacing, cover, bar size, and drape. (See attached WJE Letter dated February 18, 2022.)
4. Workers in the demolition zone will wear appropriate personal protective equipment including but not limited to hard hats, safety glasses and/or face shields, reflective vests, hard soled boots, hearing protection, and N-95 respirators.
5. At the start of each work shift, the workers will be briefed on the locations of exits and a rally point in the event of unforeseen events that may jeopardize the workers safety.
6. Provide access ports in ceiling of the town home Unit 426 to allow visual inspection of the stressing ends of the above tendons. (This unit is to remain unoccupied during the demolition process)
7. Expose the ends of PT tendons P4-84, 85 and 86 at the base of the collapsed slab and cut the exposed tendons using either a side wheel grinder, chop saw, or an acetylene torch. The cutting process should be in a manner that allows the tendons to yield (elongate) prior fully severing the tendon to mitigate an abrupt release of tension.
8. When the cutting of tendons or reinforcement, a dedicated fire watchman with a fire extinguisher will be present.
9. Starting on the top of the north side of the collapsed section, crush the concrete using a remote-controlled demo robot (See attached brochure). Remove the concrete in approximately 4'-5' sections across the width of the collapse slab. (See the attached HP-L5-F-1 drawing)
10. Water will be applied to the slab as the demolition progresses to minimize dust. Water will be kept from reaching the expansion joint to prevent the water from leaking onto parking levels below.
11. Concrete debris will be loaded into power buggies to transport the debris to the Basement Level. (See attached brochure) The debris will be moved from the site periodically, no less than one time per day, to an off-site location.

12. At the completion of the demolition the area will remain safeguarded on Level 4 and Level 5 to prevent unauthorized access.
13. The schedule duration for the above will take approximately 8 to 10 days from the issuance of the demolition permit.

Attachments:

Attachment 1: Baker Remedial Work Plan dated February 4, 2022 (with attachments)

Attachment 2: Baker Drawing HP-L5-F-1 dated February 17, 2022

Attachment 3: WJE Letter dated February 18, 2022

Attachment 4: Brochure for Remote Control Robot – Husqvarna DXR 300 & DCR 100

Attachment 5: Brochure for Whiteman Power Buggies





Wiss, Janney, Elstner Associates, Inc.  
2 Trap Falls Road, Suite 502  
Shelton, Connecticut 06484  
203.944.9424 tel  
[www.wje.com](http://www.wje.com)

February 18, 2022  
Revised February 23, 2022

Louis Casolo, P.E.  
Engineering Department  
City of Stamford  
888 Washington Blvd, 7th Floor  
Stamford, CT 06904

## **Harbor Points- The Allure- Special Inspection Questions**

WJE No. 2022.0759

Dear Mr. Casolo:

Per the request of the City of Stamford, CT, Wiss, Janney, Elstner Associates, Inc. (WJE) has reviewed the "Harbor Points- The Allure- Response to WJE Letter" issued by Henderson and Rogers Structural Engineers (HR) dated February 15, 2022. The purpose of this was to respond to the comments/questions noted in the "Discussions & Recommendations" section of our report entitled: "Harbor Points- The Allure- Local Slab Failure Progress Report" dated February 15, 2022.

Based on our review of the responses, we have the following follow-up questions and comments for your review.

- HR indicates they were never notified about the non-conformance in the post-tensioning (PT) installation in the area of the partial collapse. This would either indicate that it was missed by the special inspector and the contractor built something that he had no shop drawings or details for, or that non-conformance items were not communicated to the Engineer of Record (EOR) or corrected by the contractor. Based on this, how is HR planning to ensure to the city, that there are not other areas that are either incorrectly constructed or missing required elements?
- HR indicates that they do not have the special inspection reports for the level 5 slab in the area of the collapse and that the reports were: "not provided to the EOR for review." Based on the attached: "Statement of Special Inspections" HR signed off as the Special Inspections Coordinator. This role consists of managing and coordinating the required special inspection and testing program as well as collecting reports from the inspection and testing agencies. It should also be noted that the attached version of the statement of special inspections, is only partially completed and is missing the information associated with the superstructure. Also attached, is the May 18, 2020 letter issued by HR to the City of Stamford Building Official indicating that "Based on the progress reports submitted for the tests and observations, the work requiring special inspection was, to the best of my knowledge, in conformance with the structural permitted construction plans and specifications and the approved workmanship provisions of the Building Code." Can HR provide the progress reports that were reviewed to make this determination?



- Can HR provide the proposed work plan to assess the slab for missing steel and PT cables as outlined in the letter February 15, 2022 letter?
- What is the construction of the added B21 beam that is in place? It doesn't exist on the shop drawings. Structurally, is everything sufficient with this beam?
- What is the proposed path forward for testing and analyzing the existing upper slab section that remains in place adjacent to the collapse area but is not constructed in accordance with the approved shop drawings?

If you have any questions, please feel free to contact us.

Sincerely,

**WISS, JANNEY, ELSTNER ASSOCIATES, INC.**

A handwritten signature in black ink, appearing to read "J. Cocca". The signature is stylized and cursive.

John Cocca, P.E.  
Associate Principal & Project Manager





February 22, 2022

Mr. Tim Yahn  
Managing Director of Construction  
**Building and Land Technology**  
1 Elmcroft Road – Suite 500  
Stamford, CT 06902

**RE: Response: Harbor Points-The Allure-Special Inspection Questions  
850 Pacific Street, Stamford CT**

Dear Tim:

We received the above referenced letter on February 21, 2022, written by Wiss, Janney, Elstner (WJE) and addressed to the City of Stamford, dated February 18, 2022. The letter states that there are follow up questions to the comments/ questions noted in the Discussions and Recommendations section of the report entitled "Harbor Points-The Allure-Response to WJE Letter" issued by our office and dated February 15, 2022. WJE comments from the letter and our respective responses are stated below.

WJE Comment: HR indicates they were never notified about the non-conformance in the post-tensioning (PT) installation in the area of the partial collapse. This would either indicate that it was missed by the special inspector and the contractor built something that he had no shop drawings or details for, or that the non-conformance items were not communicated to the Engineer of Record (EOR) or corrected by the contractor. Based on this, how is HR planning to ensure the city, that there are not other areas that are either incorrectly constructed or missing required elements?

*HRSE: We have been re-reviewing all of the inspection reports, PT and mild steel shop drawings, and the recently received pour sequence document, correspondence, and photographs from Baker Concrete. We intend to publish locations for review with the City of Stamford and/ or their Engineering or technical representative, as well as the Design, Development, and Construction teams where we find potential discrepancies or where additional testing may be required to determine or verify as-built conditions.*

WJE Comment: HR indicates that they do not have the special inspection reports for the level 5 slab in the area of collapse and that the reports were "not provided to the EOR for review". Based on the attached "Statement of Special Inspections" HR signed off as the Special Inspections Coordinator. This role consists of managing and coordinating the required special inspection and testing program as well as collecting reports from the inspection and testing agencies. It also should be noted that the attached version of the statement of specially inspections is only partially completed and is missing information associated with the

superstructure. Also attached is the May 18, 2020, letter issued by HR to the City of Stamford Building Official indicating that "Based on the progress reports submitted for tests and observations, the work requiring special inspection was, to the best of my knowledge, in conformance with the structural permitted construction plans and specifications and the approved workmanship of the Building Code." Can HR provide the progress reports to make this determination?

*HRSE: From the information recently submitted by Baker Concrete for the Pour Sequence at Level 5 and in the area of the collapse, we developed a Rebar Inspection Plan derived from the information collected in the inspection reports and Pour Sequence Plan. The Grid call outs for the areas inspected by the special inspector are not exact and do not overlap the impacted area, but it appears the slabs completely around the impacted area have been inspected. We have included both Baker Concrete pour sequence plan our Rebar Inspection Plan as well as the applicable inspection reports for WJE review.*

*It is our opinion that we have performed the duties of Special Inspections Coordinator (SPC) responsibly and per the intent of the Statement of Inspection letter, including requests for missing or delayed inspection/ testing reports and managing and maintaining an organized folder/ document filing system for both. We have well over 1,100 progress reports, which are organized and filed as they were during construction, and which will be submitted to WJE's review and record. Additionally, we have included the Statement of Inspections version for the superstructure, which WJE is apparently not in possession of. Note, from the Statement of Special Inspections, "The Special Inspection Coordinator shall keep records of all inspections and shall furnish inspection reports to the Building Official and RDP in Responsible Charge." The Contractor is responsible for managing and scheduling all inspections and tests on site per the construction schedule as identified in the Statement of Special Inspections. The SPC is not responsible for managing or scheduling the inspections.*

*Additionally, we have the close-out/ completion letters from both Coastal Materials Testing Lab, LLC dated May 12, 2020, and that from Down To Earth Consulting Solutions dated March 3, 2018 (File No. 0004-001.00) which state the elements inspected were found to be in compliance and with no discrepancies.*

WJE: Can HR provide the proposed work plan to assess the slab for missing steel and PT cables as outlined in the letter?

*HRSE: Subsequent this week's completion of our review, as stated in the first paragraph response of this letter, we will determine the areas that require testing and determining missing steel.*

WJE: What is the construction of the added B21 beam that is in place? It doesn't exist on the shop drawings. Structurally, is everything sufficient with this beam?


*HRSE: The concrete beam is 2'-6" W x 2'-0" D and designed to be reinforced with 8-#10 bars bottom and 6-#10 top bars. The reinforcing for the area was inspected by Coastal Materials,*

***Inspection Report #190 and #191, dated 08/16/2018 and 08/17/2018, respectively. We analyzed the beam and found the beam to be structurally sufficient for support of the applicable area of the Level 5 deck.***

**WJE:** What is the proposed path forward for testing and analyzing the upper slab section that remains in place adjacent to the collapse area but is not constructed in accordance with the approved shop drawings.

***HRSE: Additionally testing will be provided to assist in determining the as-built reinforced condition of the remaining slab. If through testing, the as-built conditions cannot be sufficiently and accurately determined and analyzed, a new structural design, which will potentially add new support members below the area will be executed.***

Respectfully,  
**Henderson Rogers Structural Engineers, LLC**



Madison H. Henderson, P.E.  
Principal

Encl:

Cc: Ralph Martin (BLT); Bruce Yahn (BLT); Donn McGinnis (Baker); Vivek Gurjar, PE (HRSE); Ben Downing (DCE)



# Statement of Special Inspections

Project: P4/P5

Location: 0 Washington Boulevard #P4

Owner: Strand/BRC Group LLC

Design Professional in Responsible Charge: Henderson and Rogers Structural Engineers, LLC

This *Statement of Special Inspections* is submitted as a condition for permit issuance in accordance with the Special Inspection and Structural Testing requirements of the Building Code. It includes a schedule of Special Inspection services applicable to this project as well as the name of the Special Inspection Coordinator and the identity of other approved agencies to be retained for conducting these inspections and tests. This *Statement of Special Inspections* encompass the following disciplines:

- Structural       Mechanical/Electrical/Plumbing  
 Architectural       Other: \_\_\_\_\_

The Special Inspection Coordinator shall keep records of all inspections and shall furnish inspection reports to the Building Official and the Registered Design Professional in Responsible Charge. Discovered discrepancies shall be brought to the immediate attention of the Contractor for correction. If such discrepancies are not corrected, the discrepancies shall be brought to the attention of the Building Official and the Registered Design Professional in Responsible Charge. The Special Inspection program does not relieve the Contractor of his or her responsibilities.

Interim reports shall be submitted to the Building Official and the Registered Design Professional in Responsible Charge.


A *Final Report of Special Inspections* documenting completion of all required Special Inspections, testing and correction of any discrepancies noted in the inspections shall be submitted prior to issuance of a Certificate of Use and Occupancy.

Job site safety and means and methods of construction are solely the responsibility of the Contractor.

Interim Report Frequency: *Monthly* or  per attached schedule.

Prepared by:

Madison(Matt) H. Henderson  
(type or print name) 111123

  
Signature

02/27/2018  
Date



Owner's Authorization:

Building Official's Acceptance:

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

# Schedule of Inspection and Testing Agencies

This Statement of Special Inspections / Quality Assurance Plan includes the following building systems:

- |  |  |
|--|--|
| <input checked="" type="checkbox"/> Soils and Foundations  | <input type="checkbox"/> Spray Fire Resistant Material         |
| <input checked="" type="checkbox"/> Cast-in-Place Concrete | <input type="checkbox"/> Wood Construction                     |
| <input type="checkbox"/> Precast Concrete                  | <input type="checkbox"/> Exterior Insulation and Finish System |
| <input checked="" type="checkbox"/> Masonry                | <input type="checkbox"/> Mechanical & Electrical Systems       |
| <input checked="" type="checkbox"/> Structural Steel       | <input type="checkbox"/> Architectural Systems                 |
| <input type="checkbox"/> Cold-Formed Steel Framing         | <input type="checkbox"/> Special Cases                         |

Special Inspection Agencies	Firm	Address, Telephone, e-mail
1. <b>Special Inspection Coordinator</b>	<i>Henderson and Rogers Structural Engineers</i>	<i>2603 Augusta Drive, Suite 800, Houston, TX - 77057 Main - 7134305800, Email - vgurjar@hendersonrogers.com</i>
2. Inspector	<i>Coastal Materials Testing Lab, LLC</i>	<i>10 Hart Street, West Haven, CT 06516, Main - 2036915966</i>
3. Inspector		
4. Testing Agency		
5. Testing Agency		
6. Other		

Note: The inspectors and testing agencies shall be engaged by the Owner or the Owner's Agent, and not by the Contractor or Subcontractor whose work is to be inspected or tested. Any conflict of interest must be disclosed to the Building Official, prior to commencing work.



# Quality Assurance Plan

---

## Quality Assurance for Seismic Resistance

Seismic Design Category *B*

Quality Assurance Plan Required (Y/N) *Y*

Description of seismic force resisting system and designated seismic systems:

*Reinforced concrete shear walls*

## Quality Assurance for Wind Requirements

Basic Wind Speed (3 second gust) *120 mph*

Wind Exposure Category *C*

Quality Assurance Plan Required (Y/N) *N*

Description of wind force resisting system and designated wind resisting components:

*Reinforced concrete shear walls*

## Statement of Responsibility

Each contractor responsible for the construction or fabrication of a system or component designated above must submit a Statement of Responsibility.

# Qualifications of Inspectors and Testing Technicians

---

The qualifications of all personnel performing Special Inspection and testing activities are subject to the approval of the Building Official. The credentials of all Inspectors and testing technicians shall be provided if requested.

## Key for Minimum Qualifications of Inspection Agents:

When the Registered Design Professional in Responsible Charge deems it appropriate that the individual performing a stipulated test or inspection have a specific certification or license as indicated below, such designation shall appear below the *Agency Number* on the Schedule.

PE/SE	Structural Engineer – a licensed SE or PE specializing in the design of building structures
PE/GE	Geotechnical Engineer – a licensed PE specializing in soil mechanics and foundations
EIT	Engineer-In-Training – a graduate engineer who has passed the Fundamentals of Engineering examination

### American Concrete Institute (ACI) Certification

ACI-CFTT	Concrete Field Testing Technician – Grade 1
ACI-CCI	Concrete Construction Inspector
ACI-LTT	Laboratory Testing Technician – Grade 1&2
ACI-STT	Strength Testing Technician

### American Welding Society (AWS) Certification

AWS-CWI	Certified Welding Inspector
AWS/AISC-SSI	Certified Structural Steel Inspector

### American Society of Non-Destructive Testing (ASNT) Certification

ASNT	Non-Destructive Testing Technician – Level II or III.
------	---

### International Code Council (ICC) Certification

ICC-SMSI	Structural Masonry Special Inspector
ICC-SWSI	Structural Steel and Welding Special Inspector
ICC-SFSI	Spray-Applied Fireproofing Special Inspector
ICC-PCSI	Prestressed Concrete Special Inspector
ICC-RCSI	Reinforced Concrete Special Inspector

### National Institute for Certification in Engineering Technologies (NICET)

NICET-CT	Concrete Technician – Levels I, II, III & IV
NICET-ST	Soils Technician - Levels I, II, III & IV
NICET-GET	Geotechnical Engineering Technician - Levels I, II, III & IV

### Exterior Design Institute (EDI) Certification

EDI-EIFS	EIFS Third Party Inspector
----------	----------------------------

### Other

---

Item	Agency # (Qualif.)	Scope
1. Shallow Foundations	PE/GE	<p><i>Inspect soils below footings for adequate bearing capacity and consistency with geotechnical report.</i></p> <p><i>Inspect removal of unsuitable material and preparation of subgrade prior to placement of controlled fill</i></p>
2. Controlled Structural Fill	PE/GE	<p><i>Perform sieve tests (ASTM D422 &amp; D1140) and modified Proctor tests (ASTM D1557) of each source of fill material.</i></p> <p><i>Inspect placement, lift thickness and compaction of controlled fill.</i></p> <p><i>Test density of each lift of fill by nuclear methods (ASTM D2922)</i></p> <p><i>Verify extent and slope of fill placement.</i></p>
3. Deep Foundations	PE/GE	<p><i>Inspect and log pile driving operations. Record pile driving resistance and verify compliance with driving criteria.</i></p> <p><i>Inspect piles for damage from driving and plumbness.</i></p> <p><i>Verify pile size, length and accessories.</i></p> <p><i>Inspect installation of drilled pier foundations. Verify pier diameter, bell diameter, lengths, embedment into bedrock and suitability of end bearing strata.</i></p>
4. Load Testing	PE/GE	NA
4. Other:		

Item	Agency # (Qualif.)	Scope
1. Mix Design	ACI-CCI ICC-RCSI	<i>Review concrete batch tickets and verify compliance with approved mix design. Verify that water added at the site does not exceed that allowed by the mix design.</i>
2. Material Certification	ACI-CCI, ICC-RCSI	<i>Verify reinforcing steel material tags from supplier on site match approved mill certificates</i>
3. Reinforcement Installation	ACI-CCI ICC-RCSI	<i>Inspect size, spacing, cover, positioning and grade of reinforcing steel. Verify that reinforcing bars are free of form oil or other deleterious materials. Inspect bar laps and mechanical splices. Verify that bars are adequately tied and supported on chairs or bolsters</i>
4. Post-Tensioning Operations	ICC-PCSI	<i>Inspect placement, stressing, grouting and protection of post-tensioning tendons. Verify that tendons are correctly positioned, supported, tied and wrapped. Record tendon elongations.</i>
5. Welding of Reinforcing	AWS-CWI	<i>Visually inspect all reinforcing steel welds. Verify weldability of reinforcing steel. Inspect preheating of steel when required.</i>
6. Anchor Rods		<i>Inspect size, positioning and embedment of anchor rods. Inspect concrete placement and consolidation around anchors.</i>
7. Concrete Placement	ACI-CCI ICC-RCSI	<i>Inspect placement of concrete. Verify that concrete conveyance and depositing avoids segregation or contamination. Verify that concrete is properly consolidated.</i>
8. Sampling and Testing of Concrete	ACI-CFTT ACI-STT	<i>Test concrete compressive strength (ASTM C31 &amp; C39), slump (ASTM C143), air-content (ASTM C231 or C173) and temperature (ASTM C1064).</i>
9. Curing and Protection	ACI-CCI ICC-RCSI	<i>Inspect curing, cold weather protection and hot weather protection procedures.</i>
10. Other: <i>Adhesive anchorage for rebar and anchor bolts to concrete</i>		<i>Inspect size, location, spacing and embedment of dowel/bolts. Verify correct adhesive used and dowel/bolts installed per the requirements of the ICC Reports: Hilti HY-150: ER-5193 and Hilti HVA:ER-5369</i>

**Masonry**Required Inspection Level:  1  2

Item	Agency # (Qualif.)	Scope
1. Material Certification	PE	Review of material certification
2. Mixing of Mortar and Grout	ICC-SMSI	Inspect proportioning, mixing and retempering of mortar and grout.
3. Installation of Masonry	ICC-SMSI	Inspect size, layout, bonding and placement of masonry units.
4. Mortar Joints	ICC-SMSI	Inspect construction of mortar joints including tooling and filling of head joints.
5. Reinforcement Installation	ICC-SMSI AWS-CWI	Inspect placement, positioning and lapping of reinforcing steel. Inspect welding of reinforcing steel.
6. Grouting Operations	ICC-SMSI	Inspect placement and consolidation of grout. Inspect masonry clean-outs for high-lift grouting.
7. Weather Protection	ICC-SMSI	Inspect cold weather protection and hot weather protection procedures. Verify that wall cavities are protected against precipitation.
8. Evaluation of Masonry Strength	ICC-SMSI	Test compressive strength of mortar and grout cube samples (ASTM C780). Test compressive strength of masonry prisms (ASTM C1314).
9. Anchors and Ties	ICC-SMSI	Inspect size, location, spacing and embedment of dowels, anchors and ties.

Item	Agency # (Qualif.)	Scope
1. Fabricator Certification/ Quality Control Procedures <input checked="" type="checkbox"/> Fabricator Exempt	AWS/AISC- SSI ICC-SWSI	<i>Review shop fabrication and quality control procedures.</i>
2. Material Certification	AWS/AISC- SSI ICC-SWSI	<i>Review certified mill test reports and identification markings on wide-flange shapes, high-strength bolts, nuts and welding electrodes</i>
3. Bolting	AWS/AISC- SSI ICC-SWSI	<i>Inspect installation and tightening of high-strength bolts. Verify that splines have separated from tension control bolts. Verify proper tightening sequence. Continuous inspection of bolts in slip-critical connections.</i>
4. Welding	AWS-CWI  ASNT	<i>Visually inspect all welds. Inspect pre-heat, post-heat and surface preparation between passes. Verify size and length of fillet welds.</i>  <i>Ultrasonic testing of all full-penetration welds.</i>
5. Shear Connectors	AWS/AISC- SSI ICC-SWSI	<i>Inspect size, number, positioning and welding of shear connectors. Inspect suds for full 360 degree flash. Ring test all shear connectors with a 3 lb hammer. Bend test all questionable studs to 15 degrees.</i>
6. Structural Details	PE/SE	<i>Inspect steel frame for compliance with structural drawings, including bracing, member configuration and connection details.</i>
7. Metal Deck	AWS-CWI	<i>Inspect welding and side-lap fastening of metal roof and floor deck.</i>

# Instructions – Preparation of the Statement of Special Inspections

1. Who Prepares the Form:

The program of inspection and testing for a project should be prepared by the Registered Design Professional (RDP) that is in responsible charge of the building system requiring inspections and testing. The Structural Engineer of Record (SER) should prepare the sections required for the structural elements such as foundations, concrete, structural steel, etc. The Architect and MEP Engineer of Record should prepare the corresponding sections of the SSI for the building systems that they are responsible for. For further explanation, please refer to the “Guide to Special Inspections and Quality Assurance”.
2. The Front Page:
  - 2-1. At the top of the page indicate the project name and location as they appear on the Contract Documents, provide the Owner’s name (individual, private company, municipality, government agency, etc.), and indicate the Design Professional In Responsible Charge. This should be the RDP in responsible charge of the building systems for which this Statement of Special Inspections is being prepared. See explanation in item 1 above.
  - 2-2. Next, read the first paragraph and check the box below indicating the discipline(s) that this SSI will encompass (Structural, Architectural, Mechanical/Electrical/Plumbing, or Other).
  - 2-3. After reading the remaining paragraphs, the RDP must indicate the frequency of “Interim Reports” required from the Special Inspection Coordinator for the project. This can be indicated directly on the page, i.e. ”weekly”, or the adjacent box can be checked to attach a more specific schedule.
  - 2-4. Near the bottom of the page, the RDP must print, sign, and date the form, and stamp the form with their professional seal in the box provided.
  - 2-5. The Owner or Owner’s agent must sign and date the front page after the SSI has been completed by the RDP.
  - 2-6. The Building Official must sign and date the form upon acceptance.
3. Page 2 – Schedule of Inspection and Testing Agencies:
  - 3-1. The top of the page lists all of the categories of building systems with a box next to each. The RDP must check the boxes for only the building systems that are going to be covered in this SSI. A completed inspection program page must be attached for each building system that is checked off. (See instruction #5 below.)
  - 3-2. The chart below is where the members of the Special Inspection Program are listed. Their names, addresses, telephone numbers, and emails should be filled out in the appropriate boxes. If the Inspectors and Testing Agencies have not been determined yet, the RDP can fill in the boxes with “To Be Determined”.
4. Page 3 – Quality Assurance Plan:
  - 4-1. The RDP must review sections 1705 and 1706 in Chapter 17 of the IBC to determine if the project requires a Quality Assurance Plan for the seismic force and wind force resisting systems and components.
  - 4-2. The RDP must indicate whether or not a Quality Assurance Plan is required by filling in the information requested on the page. It is only necessary to provide descriptions

of the seismic and wind force resisting systems if it is determined that a Quality Assurance Plan is required.

5. Inspection Program Pages For Each Building System:
- 5-1. There is a page attached for each building system where the RDP identifies the inspection requirements of each system. Fill out the pages for only the building systems included in this SSI. Do not include blank pages for building systems not covered under this SSI.
  - 5-2. Indicate the inspection or testing firm (Agency #) that will perform each inspection task. The Agency # is the number listed next to the Inspector or Testing Laboratory on the chart on page 2 of the SSI.
  - 5-3. Indicate the required qualifications of the Inspector for each inspection. A list of qualifications of Inspectors and testing technicians is provided on page 4 of the SSI for reference. The RDP may require additional qualifications beyond the ones listed if they feel it is appropriate. Suggested qualifications have been included for consideration. The RDP must determine what qualifications are appropriate for the particular project and confirm that the selected agency employs individuals with the specified qualifications.
  - 5-4. The scope of each inspection must be filled in by the RDP. The editable text provided in italics reflects the code mandated minimum inspection requirements designated in section 1704 of IBC Chapter 17. The editable text does not include the inspections requirements for seismic and wind resisting systems listed in sections 1705 through 1708. The RDP must determine if the project falls under the requirements of sections 1705 to 1708 and add the required inspections to the building systems. The final scope of the inspections required for the project must be determined by the RDP.
  - 5-5. Descriptions of all inspections must include the required frequency of each inspection or test.



**HENDERSON  
ROGERS**  
structural engineers

May 18, 2020

Building Official  
**City of Stamford**  
Code Enforcement Division/Structural Inspections  
Stamford, CT  
Attn: Chief Structural Inspector

RE: Building and Land Technology  
1 Elmcroft Road-Stamford, CT  
HRI No: 13-17015-00  
CO Stamford Permit No: B-17-782

Dear Sir or Madam,

In accordance with Chapter 17, "Structural Tests and Inspections" of the 2012 International Building Code, special inspections services were provided for the above referenced project for the following portions of the work that required special inspections and which Coastal Materials Testing Lab, LLC and Down to Earth Consulting, LLC (DTE) were employed to test and observe:

Deep Foundations (by DTE), Cast in Place Concrete, Reinforcing Steel, Masonry Walls, Post-Tensioning, Structural Steel, Welding and Bolted Connections

Based on the progress reports submitted for the tests and observations, the work requiring special inspection was, to the best of my knowledge, in conformance with the structural permitted construction plans and specifications and the approved workmanship provisions of the Building Code. If there are any questions regarding this letter please contact us at 713-430-5800.

Sincerely,  
**Henderson Rogers Structural Engineers, LLC**

**Madison "Matt" H. Henderson, P.E.**  
Principal



5/18/2020

CC:  
P:\13\2017\13-17015-00 - Harbor Point Blocks P4 & P5\1-Admin\1-Correspondence\CO Stamford Letter-Harbor Point P4\_P5.docx



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

---

May 12<sup>th</sup>, 2020

Building and Land Technology  
1 Elmcroft Road, Suite 500  
Stamford, CT 06902

RE: Building P4-P5 (Permit #B-17-782)  
Stamford, CT

To Whom it May Concern:

This letter is to certify that all testing and inspection per the Statement of Special Inspection for the above project have been completed, All reports up to date were reviewed and found in compliance with the Project Specifications with no discrepancies to report.

Items covered: Concrete, reinforcing Steel, Soils, Masonry, Post-tensioning, Perimeter Light Gauge Steel Framing, and Structural Steel

Respectfully submitted

Coastal Materials Testing Lab, LLC



Sami Hajjar, PE







# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 07/20/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 172

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** 3<sup>rd</sup> to 4<sup>th</sup> level columns at TB/T20, TC/T20, TD/T20, TE/T20, TB/T19, TC/T19, TD/T19, TA/T18, TC/T18

3<sup>rd</sup> to 4<sup>th</sup> level walls along G12.8, from GE to GF, along GE, from G12.8 to G14

Slab on deck at 5<sup>th</sup> level between TE & GH and T1 & G7.8

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05A-01 to R05A-08	Gerdau	04/11/18	1	06/12/18	
R05B-01 to R05B-14	Gerdau	04/12/18	1	06/11/18	

**Grade:** 40 \_\_\_\_\_ 60  **Welded Wire Fabric** \_\_\_\_\_ **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes \_\_\_\_\_ No

**Items to be corrected:** None \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Area ready for concrete placement \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Superintendent notified of findings:**  Yes \_\_\_\_\_ No



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 07/31/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 179

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** Slab on deck at 5<sup>th</sup> level between GA.5 & GE and GE and T1 & G1, between GE & GH and T0.5 & G2,

Between GF & GH and G2 & G6.8

4<sup>th</sup> to 5<sup>th</sup> level Columns at TD/T11, TE/T11 and TD/T12

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05B-01 to R05B-14	Gerdau	04/12/18	1	06/11/18	

**Grade:** 40  60  **Welded Wire Fabric**  **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes  No

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Also checked rebar at 5<sup>th</sup> to 6<sup>th</sup> level walls along T8, from TB to TC, along T8, from TD to TE, Columns at TA/T9, TB/T9, TC/T9, TD/T9, TE/T9, TB/T10, TC/T10, TD/T10, TE/T10, TD/T10.5 and TE/T10.5  
Area ready for concrete placement

**Superintendent notified of findings:**  Yes  No



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 08/16/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 190

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** 6<sup>th</sup> to 7<sup>th</sup> level column at GA/G6, GA/G7, 4<sup>th</sup> to 5<sup>th</sup> level crash wall along TD, from T11 to T13.5

Slab on deck at 5<sup>th</sup> level between G6.5 & G9.5 and GD & GG, between GA & GH and G9.5 & T19

(Bottom Mat only)

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05B-01 to R05B-14	Gerdau	04/12/18	1	06/11/18	

**Grade:** 40  60  **Welded Wire Fabric**  **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes  No

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Area ready for concrete placement  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Superintendent notified of findings:**  Yes  No



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 08/17/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 191

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** Slab on deck at 5<sup>th</sup> level between G6.5 & G9.5 and GD & GG, between GA & GH and G9.5 & T19

4<sup>th</sup> to 5<sup>th</sup> level column at TB/T11, TC/T11, TD/T11, TB/T12, TC/T12, TD/T12, TB/T13, TB/T14, TE/T14,

TC.5/T13.5, wall along T14.5, from TB to TC, between TD & TE and T13.5 & T14.5

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05B-01 to R05B-14	Gerdau	04/12/18	1	06/11/18	

**Grade:** 40 \_\_\_\_\_ 60  **Welded Wire Fabric** \_\_\_\_\_ **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes \_\_\_\_\_ No

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Area ready for concrete placement  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Superintendent notified of findings:**  Yes \_\_\_\_\_ No





# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 08/20/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 192

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** Slab on deck at 5<sup>th</sup> level between TE & GA.5 and T12.5 & T19

4<sup>th</sup> to 5<sup>th</sup> level column TB/T16, TC/T16, TC.5/T16, TE/T16, TB/T17, TC.5/T17, TE/T17, wall along T18,

From TB to TC and TD to TE

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05C-01 to R05C-09	Gerdau	04/11/18	N/A	N/A	

**Grade:** 40 \_\_\_\_\_ 60  **Welded Wire Fabric** \_\_\_\_\_ **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes \_\_\_\_\_ No

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Area ready for concrete placement  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Superintendent notified of findings:**  Yes \_\_\_\_\_ No



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 08/24/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 195

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** Slab on deck at 5<sup>th</sup> level between TD & GD.5 and G6 & G9.8

7<sup>th</sup> to 8<sup>th</sup> level column at TB/T1.6, TC/T1.6, TD/T1.6, TE/T1.6, TB/T3, TC/T3, TC.5/T3, TE/T3, TB/T4,

TE/T4, TB/T5, TC/T5, TB/T6, TE/T6, TC.5/T7, walls between TC & TC.5 and T6.5 & T7, along TD, from T6 to T7

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05B-01 to R05B-14	Gerdau	04/12/18	1	06/11/18	

**Grade:** 40  60  **Welded Wire Fabric**  **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes  No

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Area ready for concrete placement  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Superintendent notified of findings:**  Yes  No



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 09/06/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 203

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** 8<sup>th</sup> to 9<sup>th</sup> level column at TB/T1, TC/T1, TD/T1, TE/T1, Walls along T2, from TB to TC, along T5, from TD

To TE, between TC & TC.5 and T3 & T4, between TC.5 & TD and T3 & T4

Slab on deck at 5<sup>th</sup> level between TA & TE and T11 & T20 (Bottom Mat only)

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05C-01 to R05C-09	Gerdau	04/11/18	N/A	N/A	

**Grade:** 40  60  **Welded Wire Fabric**  **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes  No

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Area ready for concrete placement  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Superintendent notified of findings:**  Yes  No



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 09/07/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 204

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** Slab on deck at 5<sup>th</sup> level between TA & TE and T11 & T20

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R05C-01 to R05C-09	Gerdau	04/11/18	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.

**Grade:** 40  60  **Welded Wire Fabric**  **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes  No

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Area ready for concrete placement  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Superintendent notified of findings:**  Yes  No



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 09/08/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 205

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** 5<sup>th</sup> to 6<sup>th</sup> level columns at TD/T11, TE/T11, TB/T12, TC/T12, TD/T12, TE/T12, TB/T13, TC/T13, TD/T13, TE/T13, Walls between TC & TC.5 and T14.5 & T15, along TD, from T13.5 to T14.5, along T14.5, from TD to TE

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05B-01 to R05B-14	Gerdau	04/12/18	1	06/11/18	

**Grade:** 40  60  **Welded Wire Fabric**  **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  Yes  No

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Area ready for concrete placement  
\_\_\_\_\_  
Also checked rebar for slab on deck at 5<sup>th</sup> level at town house area between GF & GH and G9 & G14.5,  
\_\_\_\_\_  
Between GA.5 & GF and G14 & G14.5 (Top mat was not completed)  
\_\_\_\_\_

**Superintendent notified of findings:**  Yes  No



# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

**Client:** Building & Land Technology

**Date:** 09/11/2018

1 Elmcroft Road – Suite 500

Stamford, CT 06902

**Report No.:** R 206

**Project:** BLT - P4/P5

Stamford, CT

**Inspector:** Shehzad Ahmad

## REINFORCING STEEL INSPECTION REPORT

**Location:** Slab on deck at 5<sup>th</sup> level at town house area between GF & GH and G9 & G14.5, between G14 & G14.5 and GA.5 & GF

5<sup>th</sup> to 6<sup>th</sup> level columns at TB/T14, TC/T14, TC.5/T13.5, TC.5/T14.5, TB/T15, TD/T15, TB/T16, TC.5/T16,

Drawing No.	Drawings By	Date	Rev. No.	Rev. Date	Comments
R60-1 to R60-12	Gerdau	11/29/17	N/A	N/A	Rebar size, splicing, clearance and spacing complies with specifications.
R70-01 to R70-11	Gerdau	11/28/17	2	01/17/18	
R05B-01 to R05B-14	Gerdau	04/12/18	1	06/11/18	

**Grade:** 40 \_\_\_\_\_ 60  **Welded Wire Fabric** \_\_\_\_\_ **Size:** \_\_\_\_\_

**Forms Inspected:**  (Forms inspected for cleanliness, alignment, and symmetry only)

**Reinforcing complies with Project Specifications:**  **Yes** \_\_\_\_\_ **No**

**Items to be corrected:** None  
\_\_\_\_\_  
\_\_\_\_\_

**Note:** Discrepant items to be re-inspected prior to concrete placement.

**Remarks:** Also checked 5<sup>th</sup> to 6<sup>th</sup> level columns at TE/T16, TB/T17, TC/T17, TD/T18, TE/T17, TC.5/T17, TD/T18, TB/T19, TC/T19, TD/T19, TE/T19, TB/T20 and TC/T20

Area ready for concrete placement, refer to report dated 09/08/2018 top mat completed

**Superintendent notified of findings:**  **Yes** \_\_\_\_\_ **No**





# Coastal Materials Testing Lab, LLC

10 Hart Street West Haven, CT 06516 • Tel (203) 691-5966 • Fax (203) 691-5238

[www.coastalmaterialstesting.com](http://www.coastalmaterialstesting.com)

---

March 25<sup>th</sup>, 2022

Building and Land Technology  
1 Elmcroft Road, Suite 500  
Stamford, CT 06902

RE: Building P4-P5 (Permit #B-17-782)  
Stamford, CT

To Whom it May Concern:

This letter is to inform you that Coastal Materials Testing Performed the reinforcing inspections at the above mentioned project per the Statement of Special Inspections; these inspections included the verification of the reinforcing steel and the post tensioning tendons for layout, profile, bundling and monitoring and recording the stressing operations. Inspections were conducted per the approved shop drawings only provided by the concrete contractor.

Respectfully submitted

Coastal Materials Testing Lab, LLC

Sami Hajjar, PE







# Summary of GPR Investigation of Concrete Structure

---

Prepared For: Baker Concrete

Prepared By:  
Scott Viapiano  
Scott.Viapiano@gprsinc.com  
Project Manager -New York City  
201-401-3209  
March 31, 2022

March 31, 2022

Baker Concrete

Attn: Brian Wilkerson

Site: 850 Pacific St. Stamford, CT

We appreciate the opportunity to provide this report for our work completed on March 30, 2022.

## PURPOSE

The purpose of the project was to determine the structural components of the slab such as spacing and depth of reinforcing, specifically Post Tension Cables, within a specified area in the Rec Room and a hallway of the building.

## EQUIPMENT

- **Concrete Scanning GPR Antenna.** This GPR antenna is handheld and rolls over the surface. The antenna needs a reasonably smooth, unobstructed surface for scanning and is not able to scan within 2"-4" of obstructions such as walls and metal tracks unless they are removed prior to our work. The data is displayed on a screen during the scanning and marked on the surface in real time. The total depth achieved can be as much as 18" or more with this antenna but can vary widely depending on the types of materials being scanned through and other factors such as the spacing of the reinforcing and/or moisture content. Depth accuracy depends on the ability to obtain an accurate depth calibration for the concrete. No harmful radiation is emitted and the work can be performed at any time with people in close proximity. For more information, please visit: [Link](#)
- **1600 MHz GPR Antenna.** The antenna is approximately 6"x9" and rolls over the surface. The antenna needs a reasonably smooth, unobstructed surface for scanning so we would not be able to scan within 3" of obstructions such as walls and metal tracks unless they are removed prior to our work. The data is displayed on a screen during the scanning and marked on the surface in real time. GPR works by sending pulses of energy into a material and recording the strength and the time required for the return of the reflected signal. Reflections are produced when the energy pulses enter into a material with different electrical properties from the material it left. The strength of the reflection is determined by the contrast in signal speed between the two materials. The total depth achieved can be as much as 18" or more with this antenna but can vary widely depending on the conductivity of the materials and other factors such as the spacing of the reinforcing. ***No harmful radiation is emitted and the work can be performed at any time with people in close proximity.***  
**2000 MHz GPR Antenna.** The antenna is only approximately 4"x3.5" and rolls over the surface. The antenna needs a reasonably smooth, unobstructed surface for scanning so we would not be able to scan within 1.75" of obstructions such as walls and metal tracks unless they are removed prior to our work. The data is displayed on a screen during the scanning and marked on the surface in real time. GPR works by sending pulses of energy into a material and recording the strength and the time required for the return of the reflected signal. Reflections are produced when the energy pulses enter into a material with different electrical properties from the material it left. The strength of the reflection is determined by the contrast in signal speed between the two materials. The total depth achieved can be as much as 18" or more with this antenna but can vary widely depending on the conductivity of the materials and other factors such as the spacing of the reinforcing. ***No harmful radiation is emitted and the work can be performed at any time with people in close proximity.***

## **PROCESS**

The process begins by using GPR to collect initial scans throughout the area. These scans are used to calibrate the equipment and determine the type of slab, reinforcing patterns, maximum depth penetration, and any other potential limitations. Each location is then scanned in a grid pattern with the spacing and collection of scans being dependent on the information that is needed for the project. Relevant scan examples were saved and will be provided in this report.

## **LIMITATIONS**

Please keep in mind that there are limitations to any subsurface investigation. The equipment may not achieve maximum effectiveness due to conditions in the concrete or soil such as moisture content, age of the concrete, reinforcing size and spacing, and a variety of other factors. Depths are dependent on many factors so depth accuracy can vary throughout a site and should be treated as estimates only. No subsurface investigation or equipment can provide a complete image of what lies below. Our results should always be used in conjunction with as many methods as possible such as consulting existing plans and drawings, visual inspection of above-ground features, drilling or cutting, etc.

## **FINDINGS**

The slab scanned was a reinforced concrete slab containing post tension cables per the contract drawings provided by the client. The average depth of the scanned areas were 10-12 inches in thickness. After performing a GPR concrete analysis, I did find post tension running all throughout the rec room. The post tension I was finding and marking on the ground was consistent with the PT cable map that was provided by the client. I found that the uniform PT cables running long ways has 3-foot pattern spacing, and I also found the banded PT cables running laterally with the columns as it shows on the map. I did not find any PT cable in the hallway near where the hole in the patio area is. I only found rebar reinforcing in that carpeted area where the expansion joint is.

Please reference the attached post tension shop drawings provided by the client which highlights the approximate areas where the scanning was performed.

The following pages will provide photos and further explanation of our findings.

SUBMITTAL


No.	Date	Description	Checked	Drawn
1	05/01/18	FOR APPROVAL		
2	05/01/18	FOR APPROVAL		
3	07/27/18	FOR CONSTRUCTION	AK	FOUR



POST-TENSIONING INSTITUTE  
 CCI  
 CONCRETE CONSTRUCTION INSTITUTE

**TENDON LAYOUT LEGEND**

- 1. TENDON LAYOUT
- 2. TENDON COVERS
- 3. TENDON PROTECTIVE SHEATHING
- 4. TENDON ANCHORS
- 5. TENDON BENDS
- 6. TENDON CUTS
- 7. TENDON JOINTS
- 8. TENDON TIE-BACKS
- 9. TENDON TIE-BACKS
- 10. TENDON TIE-BACKS
- 11. TENDON TIE-BACKS
- 12. TENDON TIE-BACKS
- 13. TENDON TIE-BACKS
- 14. TENDON TIE-BACKS
- 15. TENDON TIE-BACKS
- 16. TENDON TIE-BACKS
- 17. TENDON TIE-BACKS
- 18. TENDON TIE-BACKS
- 19. TENDON TIE-BACKS
- 20. TENDON TIE-BACKS
- 21. TENDON TIE-BACKS
- 22. TENDON TIE-BACKS
- 23. TENDON TIE-BACKS
- 24. TENDON TIE-BACKS
- 25. TENDON TIE-BACKS
- 26. TENDON TIE-BACKS
- 27. TENDON TIE-BACKS
- 28. TENDON TIE-BACKS
- 29. TENDON TIE-BACKS
- 30. TENDON TIE-BACKS
- 31. TENDON TIE-BACKS
- 32. TENDON TIE-BACKS
- 33. TENDON TIE-BACKS
- 34. TENDON TIE-BACKS
- 35. TENDON TIE-BACKS
- 36. TENDON TIE-BACKS
- 37. TENDON TIE-BACKS
- 38. TENDON TIE-BACKS
- 39. TENDON TIE-BACKS
- 40. TENDON TIE-BACKS
- 41. TENDON TIE-BACKS
- 42. TENDON TIE-BACKS
- 43. TENDON TIE-BACKS
- 44. TENDON TIE-BACKS
- 45. TENDON TIE-BACKS
- 46. TENDON TIE-BACKS
- 47. TENDON TIE-BACKS
- 48. TENDON TIE-BACKS
- 49. TENDON TIE-BACKS
- 50. TENDON TIE-BACKS
- 51. TENDON TIE-BACKS
- 52. TENDON TIE-BACKS
- 53. TENDON TIE-BACKS
- 54. TENDON TIE-BACKS
- 55. TENDON TIE-BACKS
- 56. TENDON TIE-BACKS
- 57. TENDON TIE-BACKS
- 58. TENDON TIE-BACKS
- 59. TENDON TIE-BACKS
- 60. TENDON TIE-BACKS
- 61. TENDON TIE-BACKS
- 62. TENDON TIE-BACKS
- 63. TENDON TIE-BACKS
- 64. TENDON TIE-BACKS
- 65. TENDON TIE-BACKS
- 66. TENDON TIE-BACKS
- 67. TENDON TIE-BACKS
- 68. TENDON TIE-BACKS
- 69. TENDON TIE-BACKS
- 70. TENDON TIE-BACKS
- 71. TENDON TIE-BACKS
- 72. TENDON TIE-BACKS
- 73. TENDON TIE-BACKS
- 74. TENDON TIE-BACKS
- 75. TENDON TIE-BACKS
- 76. TENDON TIE-BACKS
- 77. TENDON TIE-BACKS
- 78. TENDON TIE-BACKS
- 79. TENDON TIE-BACKS
- 80. TENDON TIE-BACKS
- 81. TENDON TIE-BACKS
- 82. TENDON TIE-BACKS
- 83. TENDON TIE-BACKS
- 84. TENDON TIE-BACKS
- 85. TENDON TIE-BACKS
- 86. TENDON TIE-BACKS
- 87. TENDON TIE-BACKS
- 88. TENDON TIE-BACKS
- 89. TENDON TIE-BACKS
- 90. TENDON TIE-BACKS
- 91. TENDON TIE-BACKS
- 92. TENDON TIE-BACKS
- 93. TENDON TIE-BACKS
- 94. TENDON TIE-BACKS
- 95. TENDON TIE-BACKS
- 96. TENDON TIE-BACKS
- 97. TENDON TIE-BACKS
- 98. TENDON TIE-BACKS
- 99. TENDON TIE-BACKS
- 100. TENDON TIE-BACKS



**APPROVED FOR CONSTRUCTION**  
 (ENCAPSULATED ANCHORS)

SLAB TENDON LAYOUT - 5TH FLOOR (SLAB THICKNESS 7 1/2" U.N.O.)  
 SCALE: 3/32"=1'-0"

PLEASE SEE DETAIL SHEET FOR TENDON CHART (PAGE 2)

STATIONING	REVISION	DESCRIPTION	DATE	BY	CHKD	APP'D
100+00	1	ISSUE FOR CONSTRUCTION	07/27/18	AK	FOUR	
100+00	2	REVISION				
100+00	3	REVISION				
100+00	4	REVISION				
100+00	5	REVISION				
100+00	6	REVISION				
100+00	7	REVISION				
100+00	8	REVISION				
100+00	9	REVISION				
100+00	10	REVISION				
100+00	11	REVISION				
100+00	12	REVISION				
100+00	13	REVISION				
100+00	14	REVISION				
100+00	15	REVISION				
100+00	16	REVISION				
100+00	17	REVISION				
100+00	18	REVISION				
100+00	19	REVISION				
100+00	20	REVISION				
100+00	21	REVISION				
100+00	22	REVISION				
100+00	23	REVISION				
100+00	24	REVISION				
100+00	25	REVISION				
100+00	26	REVISION				
100+00	27	REVISION				
100+00	28	REVISION				
100+00	29	REVISION				
100+00	30	REVISION				
100+00	31	REVISION				
100+00	32	REVISION				
100+00	33	REVISION				
100+00	34	REVISION				
100+00	35	REVISION				
100+00	36	REVISION				
100+00	37	REVISION				
100+00	38	REVISION				
100+00	39	REVISION				
100+00	40	REVISION				
100+00	41	REVISION				
100+00	42	REVISION				
100+00	43	REVISION				
100+00	44	REVISION				
100+00	45	REVISION				
100+00	46	REVISION				
100+00	47	REVISION				
100+00	48	REVISION				
100+00	49	REVISION				
100+00	50	REVISION				
100+00	51	REVISION				
100+00	52	REVISION				
100+00	53	REVISION				
100+00	54	REVISION				
100+00	55	REVISION				
100+00	56	REVISION				
100+00	57	REVISION				
100+00	58	REVISION				
100+00	59	REVISION				
100+00	60	REVISION				
100+00	61	REVISION				
100+00	62	REVISION				
100+00	63	REVISION				
100+00	64	REVISION				
100+00	65	REVISION				
100+00	66	REVISION				
100+00	67	REVISION				
100+00	68	REVISION				
100+00	69	REVISION				
100+00	70	REVISION				
100+00	71	REVISION				
100+00	72	REVISION				
100+00	73	REVISION				
100+00	74	REVISION				
100+00	75	REVISION				
100+00	76	REVISION				
100+00	77	REVISION				
100+00	78	REVISION				
100+00	79	REVISION				
100+00	80	REVISION				
100+00	81	REVISION				
100+00	82	REVISION				
100+00	83	REVISION				
100+00	84	REVISION				
100+00	85	REVISION				
100+00	86	REVISION				
100+00	87	REVISION				
100+00	88	REVISION				
100+00	89	REVISION				
100+00	90	REVISION				
100+00	91	REVISION				
100+00	92	REVISION				
100+00	93	REVISION				
100+00	94	REVISION				
100+00	95	REVISION				
100+00	96	REVISION				
100+00	97	REVISION				
100+00	98	REVISION				
100+00	99	REVISION				
100+00	100	REVISION				

NOTES:  
 1 - REFER TO DETAIL SHEET 1.01 FOR ALL TENDONS CURVED AROUND OPENINGS  
 2 - STRESSING TAIL TO BE A MAXIMUM OF 10" REFER TO DETAIL 3PT-1.01  
 3 - E-O-R TO VERIFY CONSTRUCTION JOINT LOCATIONS.  
 4 - E-O-R TO VERIFY SLAB TENDON LAYOUT



No.	Date	Description	Checked	Drawn
1	05/08/16	FOR APPROVAL		
2	05/08/16	FOR APPROVAL		
3	07/27/16	FOR CONSTRUCTION		

CLIENT: BAKER CONCRETE CONSTRUCTION  
 CONTRACT DRAWINGS: SUPERSTRUCTURE  
 Date: 02/22/16

PROJECT: HARBOR POINT BLOCK P4-P5 STAMFORD, CT

DRAWING TITLE: 5TH FLOOR SLAB TENDON LAYOUT

DRAWING REFERENCE: S10PTA & S10PTB  
 PT-2.10

**REVISIONS**

No.	Date	Description
1	02/22/16	ISSUED FOR PERMITS
2	05/08/16	FOR APPROVAL
3	07/27/16	FOR CONSTRUCTION

**TECHNICAL NOTES**

- REFER TO DETAIL 10PT-101 FOR ALL TENDONS SWEEP AROUND OPENINGS.
- REFER TO DETAIL 10PT-102 FOR ALL TENDONS SWEEP AROUND OPENINGS.
- E-O-R TO VERIFY CONSTRUCTION JOINT LOCATIONS.
- E-C-R TO VERIFY SLAB TENDON LAYOUT.




SLAB TENDON LAYOUT - 5TH FLOOR (SLAB THICKNESS 7 1/2" U.N.O.)  
 SCALE: 3/32"=1'-0"

**APPROVED FOR CONSTRUCTION**

ENCAPSULATED (ENCAPSULATED ANCHORS)

REVISION	DATE	DESCRIPTION	BY	CHKD
1	02/22/16	ISSUED FOR PERMITS		
2	05/08/16	FOR APPROVAL		
3	07/27/16	FOR CONSTRUCTION		

PLEASE SEE PREVIOUS SHEET FOR TENDON CHART (PART 1)  
 NOTES:  
 1 - REFER TO DETAIL 10PT-101 FOR ALL TENDONS SWEEP AROUND OPENINGS.  
 2 - REFER TO DETAIL 10PT-102 FOR ALL TENDONS SWEEP AROUND OPENINGS.  
 3 - E-O-R TO VERIFY CONSTRUCTION JOINT LOCATIONS.  
 4 - E-C-R TO VERIFY SLAB TENDON LAYOUT.



GPR data screenshot of PT cables found in the rec room. The depth scale is on the left and the distance of the scan is across the top, forming a cross section view of the subsurface. The arrows point to the multiple pieces of PT cable that are present.



**Photo 1**

Photo of the rec room floor. Pictured above is some of the scanned area where PT cables were found. All PT cables were marked in blue tape




GPR data screenshot of more PT cables found in the rec room. All arrows point to PT cables



**Photo 2**

Photo of the rec room floor. Pictured above is another of the scanned area where PT cables were found. All PT cables were marked in blue tape




GPR data screenshot of more PT cables found in the rec room. All arrows point to PT cables



**Photo 3**

Photo of the rec room floor. Pictured above is another of the scanned area where PT cables were found. All PT cables were marked in blue tape




GPR data screenshot of the lateral PT cables bunches that ran through the columns in the rec room. All those reactions are PT cables at 5" depth



**Photo 4**

Pictured above is one of those lateral PT bunches that run through the column. All PT cables were marked in blue tape



GPR data screenshot of the carpeted hallway area near the expansion joint. No PT cables were found in this area. The reactions in this data screenshot above are rebar only.



**Photo 5**

Pictured above is the area near the expansion joint where no PT cables were found.



**Photo 6**

Pictured above are more lateral PT bunches that run through the column. All PT cables were marked in blue tape



**Photo 7**

Pictured above is another area in the rec room where more PT was found. All PT is marked in blue tape





**Photo 8**

Pictured above is another area in the rec room showing the lateral PT bunches along with the long PT cables. All PT is marked in blue tape



**Photo 9**

Pictured above is another area in the rec room showing the long PT cables spaced evenly at approximately 3'.



**Photo 10**

Pictured above is another area in the rec room where more PT was found. All PT is marked in blue tape



**Photo 11**

Pictured above is another area in the rec room where more PT was found. All PT is marked in blue tape

**CLOSING**

GPRS, Inc. has been in business since 2001, specializing in underground storage tank location, concrete scanning, utility locating, and shallow void detection for projects throughout the United States. I encourage you to visit our website ([www.gprsinc.com](http://www.gprsinc.com)) and contact any of the numerous references listed.

GPRS appreciates the opportunity to offer our services, and we look forward to continuing to work with you on future projects. Please feel free to contact us for additional information or with any questions you may have regarding this report.

Signed,

  
Scott Viapiano  
Project Manager — New York City



Direct: 201-401-3209

[Scott.Viapiano@gprsinc.com](mailto:Scott.Viapiano@gprsinc.com)

[www.gprsinc.com](http://www.gprsinc.com)

June 7, 2022

**Tim Yahn**  
**Building and Land Technology**  
**1 Elmcroft Road, Suite 500**  
**Stamford, CT 06902**

**Re: Harbor Point Allure Block P4-P5**

Dear Tim;

At your request, we have completed the Non-Destructive Testing (NDT) as required by the replacement and repair permit. The NDT was performed by GPRS using GPR scanning methods over a period of three days. We have attached a report we received from GPRS indicating their findings were consistent with the PT drawings we provided. GPRS marked the underside of the slab showing the PT tendon location and distance from the bottom of the slab. The areas scanned are shown on the attached drawings.

The following is a summary of the scans and our observations:

1. Level 5 Area 1:
  - a. This area is between gridlines GE-GD and G5-G6 adjacent to the pool structure.
  - b. The pool wall, piping, and electrical conduit made some of the areas inaccessible.
  - c. Uniform tendons are marked parallel to G5 and G6.
    - i. A total of eight (8) tendon locations are marked between the column lines plus one tendon location on gridline G6.
    - ii. The spacing between the tendon locations vary from 25 1/2" to 49 1/2" measured at the center of the bay. The average spacing is approximately 36 3/8".
    - iii. The distance from the bottom of the slab to the tendon groups are marked on the slab soffit and vary from 8" at the gridlines GE and GD to 1" in the center of the bay.
  - d. The banded tendons are marked at gridlines GE and GD.
    - i. A total of five (5) tendon locations are marked parallel to gridline GE and six (6) tendon locations are marked parallel to GD. The tendon groups sweep inward toward the center of the bay as they get closer to the pool wall. The tendon groups are spaced approximately 10" to 12" apart.
    - ii. The distance from the bottom of the slab to the tendon groups are marked on the slab soffit. The highest locations measured 8" near gridline G6 to 6" near the face of the pool slab. The lowest locations measured 2" approximately 8'0" from the face of the pool wall near gridline GD and 6'-3" from the face of the pool wall near gridline GE.

2. Level 5 Area 2:

- a. This area is between gridlines GE-GD and G12-G12 near the top of the ramp on Level 4.
- b. Uniform tendons are marked parallel to G5 and G6.
  - i. A total of ten (10) tendon locations are marked.
  - ii. The spacing between the tendon locations varies from 32" to 52 1/2" measured at the center of the bay. The average spacing is approximately 37 5/8".
  - iii. The distance from the bottom of the slab to the tendon groups are marked on the slab soffit and vary from 9" at the gridlines GE and GD to 1" near the center of the bay.
- c. Banded tendons are marked at gridlines GE and GD.
  - i. A total of 5 tendon locations are marked parallel to gridline GE and 6 tendon locations are marked parallel to GD. The tendon groups are spaced approximately 10" to 12" apart.
  - ii. The distance from the bottom of the slab to the tendon groups are marked on the slab soffit. The highest locations measured 8" near the face of the columns G11 and G12. The lowest locations measured 2.5" near the center of the bay.

3. Level 4 Area 3 and Level 1 Area 4:

- a. These areas are located between the expansion joint along gridline TE to the middle of the bay between gridline TE and GA and from the column at TE-T12 to the expansion joint parallel with gridline G10.
- b. Uniform tendons are marked parallel to gridline TE.
  - i. At each level, there are three (3) lines of uniform tendons between gridline TE and the expansion joint parallel with gridline G10.
  - ii. The distance from the bottom of the slab to the tendon groups marked on the slab soffit varies from approximately 3" at the expansion joint to 1" near the center of the bay.
- c. Banded tendons are marked parallel to the expansion joint along gridline TE.
  - i. At each level, there are three (3) lines of tendons marked parallel to the expansion joint at gridline TE spaced from 10" to 12" apart.
  - ii. The distance from the bottom of the slab to the tendon groups marked on the slab soffit varies from 3" to 4" along the length of the tendons.

Given the GPR scanning is based on the operator's interpretation of the readings, the depths and locations are approximate. However, we believe the scans of these areas confirm the PT is installed as intended on the structural drawings.



Please feel free to contact me should you have any questions.

Sincerely,

**BAKER CONCRETE CONSTRUCTION, INC.**

**Donn McGinnis, PE**  
**Design Assist Manager**

**CORPORATE OFFICE**

900 North Carver Road • Monroe, OH 45050  
Phone: 513.539.4000 • Fax: 513.539.4251

**CAROLINA OFFICE**

8918 Crump Road, Suite A • Pineville, NC 28134  
Phone: 704.967.8110

[www.bakerconcrete.com](http://www.bakerconcrete.com) • Toll Free: 800.539.2224



# Job Summary

Job Date : 5/10/2022

<b>Customer</b>	Baker Concrete Construction A/P	<b>Phone Number</b>	(513) 615-3399
<b>Billing Address</b>	<b>City</b>	<b>State</b>	<b>Zip</b>
900 N. Garver Rd	Monroe	OH	45050
<b>Job Details</b>			
<b>Jobsite Location</b>	850 PACIFIC ST		
<b>City</b>	STAMFORD		
<b>State</b>	CT		
<b>WA Number</b>	350596		
<b>Job Num</b>	10903		
<b>PO Num</b>	10903		
<b>Lead Technician</b>	VIAPIANO, SCOTT	<b>Phone</b>	201-401-3209
		<b>Email</b>	scott.viapiano@gprsinc.com
Thank you for using GPRS on your project. We appreciate the opportunity to work with you. If you have questions regarding the results of this scanning, please contact the lead GPRS technician on this project.			
<b>EQUIPMENT USED</b>			
The following equipment was used on this project:			
<ul style="list-style-type: none"> <li>Underground Scanning GPR antenna. Typically capable of detecting objects up to 8' deep or more in ideal conditions but maximum effective depth can vary widely and depends on site and soil conditions. Depth penetration is most commonly limited by moisture and clay/conductive soils. Depths provided should always be treated as estimates as their accuracy can be affected by multiple factors.</li> <li>Electromagnetic Pipe and Cable Locator. Detects electromagnetic fields. Used to actively trace conductive pipes and tracer wires, or passively detect power and radio signals traveling along conductive pipes and utilities. Depths provided should always be treated as estimates as their accuracy can be affected by multiple factors.</li> </ul>			
<b>Work Performed</b>			
Ground Penetrating Radar Systems performed the following work on this project:			
<b>Concrete Analysis</b>			
The scope of work included scanning designated areas to gather data to assist in analysis of the concrete. The data collected at each area includes:			
<ul style="list-style-type: none"> <li>4 areas were scanned on ceilings.</li> <li>Perform GPR concrete analysis for presence of PT cable spacing and patterns throughout several areas on the ceiling of the parking garage.</li> <li>The effective depth of GPR will vary throughout a site depending on a variety of conditions such as roofing material, moisture content, amount of reinforcing steel, etc. At this site, the maximum effective GPR depth was approximately 10-11 inches.</li> </ul>			



# Job Summary

Job Date : 5/10/2022

- After performing concrete analysis over four separate areas on the ceiling of the parking garage on the fourth floor the third floor and the first floor I was able to find PT cables using my GPR. I also found of rebar but the client did not need rebar to be marked. But there was substantial amount of rebar in the correct spacing that the drawings provided. I found PT cable using my GPR and I was able to distinguish the difference between PT cable and rebar through my extensive training and also my many years of work experience. I found the PT spacing to be very consistent and even as it shown in the drawings that were provided to me. I was also able to find the bunches of PT cable in between the columns using my GPR and the same as the Map provides. I found the PT cable at varying Depths and the PT cable definite definitely draped down as you went towards the middle of the columns. PT cable was found at depths of 1 inches in the middle of the columns and 8 to 10 inches as you were at the columns. All PT cable is marked in red with the words PT. Please keep off all of our marks by at least 2 inches. thank you

## Pictures



## Utility Limitations

## TERMS & CONDITIONS

[https://www.gp-radar.com/legal/terms-conditions?utm\\_source=jobsummary&utm\\_medium=referral](https://www.gp-radar.com/legal/terms-conditions?utm_source=jobsummary&utm_medium=referral)

## SIGNATURE

## Contact Name

Brian Wilkerson (513) 615-3399 WilkersonB@BakerConcrete.com



# Job Summary

Job Date : 5/10/2022



## SUBSURFACE INVESTIGATION METHODOLOGY

# POWERING THE INDUSTRY STANDARD

Proper training, multiple technologies, and a field-tested methodology are the key to a successful utility locate, concrete scan, and video pipe inspection. GPRS is a master of all three components by utilizing the SIM Specification.

### ✓ TRAINING

The industry standard recommends 8 hours as a minimum for training and 80 hours practicing GPR to become certified NDT Level I in Ground Penetrating Radar. In contrast, SIM requires 320 hours of mentorship in the field prior to 80 hours of classroom/hands-on training.

In addition, the classroom training reinforces what a technician learns in the field. This classroom setting also allows them to go deeper into the technical aspects and knowledge needed to perform their jobs at the highest level.

### ✓ EQUIPMENT

Subsurface Investigation Methodology (SIM) requires multiple technologies to be used in an investigation. With any investigation, more data points yield the best outcome. When SIM qualified technicians locate a subsurface target such as a pipe, utility, or reinforcing with more than one technology, it confirms the accuracy of the locate. This redundancy also reduces the likelihood of missing a buried target. Redundant results bear more data points; by locating pipes and other targets with different methods utilizing each tool's strengths and weaknesses, technicians reduce the risk of missing key site information.

### ✓ METHODOLOGY

The SIM specification is a tested process that allows technicians to acquire accurate and repeatable results. SIM is similar to a machine that requires multiple gears, all working in unison for it to function properly. One of the most critical gears and steps in the SIM process is the repeated methodology that technicians must know for each project.

A solid, repeatable methodology guarantees that a concrete scanning, utility locating, or video pipe inspection job can be performed by a seasoned professional but also by a new-to-the-business technician. When the SIM methodology is followed, it allows technicians to achieve the same results regardless of their experience in the field.

SIMSPEC.ORG







International, PC

10000 Old Derby Road  
Stamford, CT 06907  
Tel: 203.353.1000  
Fax: 203.353.1001  
www.edf.com

INTERNATIONAL  
TECHNOLOGY

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

GENERAL CONTRACTOR

# HARBOR POINT BLOCK P4-P5 STAMFORD, CT




1	DATE	11/15/00
2	DESCRIPTION	REVISION
3	DATE	
4	DESCRIPTION	
5	DATE	
6	DESCRIPTION	
7	DATE	
8	DESCRIPTION	
9	DATE	
10	DESCRIPTION	
11	DATE	
12	DESCRIPTION	
13	DATE	
14	DESCRIPTION	
15	DATE	
16	DESCRIPTION	
17	DATE	
18	DESCRIPTION	
19	DATE	
20	DESCRIPTION	
21	DATE	
22	DESCRIPTION	
23	DATE	
24	DESCRIPTION	
25	DATE	
26	DESCRIPTION	
27	DATE	
28	DESCRIPTION	
29	DATE	
30	DESCRIPTION	


5TH FLOOR PLAN - OVERALL

S105

- 1. REFER TO GENERAL NOTES FOR CONSTRUCTION REQUIREMENTS AND CONDITIONS.
- 2. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE BUILDING CODES AND REGULATIONS OF THE STATE OF CONNECTICUT, AND THE LATEST EDITIONS OF THE INTERNATIONAL BUILDING CODES AND REGULATIONS.
- 3. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL MECHANICAL AND ELECTRICAL CODES AND REGULATIONS.
- 4. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL PLUMBING AND MECHANICAL CODES AND REGULATIONS.
- 5. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL FIRE AND SAFETY CODES AND REGULATIONS.
- 6. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL ENERGY EFFICIENCY CODES AND REGULATIONS.
- 7. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL SUSTAINABLE DESIGN AND CONSTRUCTION CODES AND REGULATIONS.
- 8. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL ACCESSIBILITY AND UNIVERSAL DESIGN CODES AND REGULATIONS.
- 9. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL ENVIRONMENTAL DESIGN AND CONSTRUCTION CODES AND REGULATIONS.
- 10. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL HEALTH AND SAFETY CODES AND REGULATIONS.
- 11. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL QUALITY MANAGEMENT SYSTEMS CODES AND REGULATIONS.
- 12. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL PROJECT DELIVERY CODES AND REGULATIONS.
- 13. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL RISK MANAGEMENT CODES AND REGULATIONS.
- 14. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL COMMUNICATIONS CODES AND REGULATIONS.
- 15. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL DOCUMENTATION CODES AND REGULATIONS.
- 16. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL CONTRACT ADMINISTRATION CODES AND REGULATIONS.
- 17. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL LEGAL AND ETHICAL CODES AND REGULATIONS.
- 18. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL PROFESSIONAL CONDUCT CODES AND REGULATIONS.
- 19. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL PUBLIC RELATIONS CODES AND REGULATIONS.
- 20. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL SOCIAL RESPONSIBILITY CODES AND REGULATIONS.
- 21. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL CORPORATE GOVERNANCE CODES AND REGULATIONS.
- 22. ALL WORK SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE INTERNATIONAL FINANCIAL REPORTING CODES AND REGULATIONS.



1 5TH FLOOR PLAN - OVERALL





International, PC

1000 N. 17th St., Suite 100  
Columbus, OH 43261  
614.291.1200  
www.internationalpc.com

INTERNATIONAL PC  
TECHNOLOGY  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR

GENERAL CONTRACTOR  
SERVICES  
GENERAL CONTRACTOR


HARBOR POINT  
BLOCK P4-P5  
STAM-FORD, CT



PROJECT NO.	417
DATE	08/20/14
SCALE	AS SHOWN
1. GENERAL CONTRACTOR	
2. ARCHITECT	
3. STRUCTURAL ENGINEER	
4. MECHANICAL ENGINEER	
5. ELECTRICAL ENGINEER	
6. PLUMBING ENGINEER	
7. CIVIL ENGINEER	
8. LANDSCAPE ARCHITECT	
9. INTERIOR DESIGNER	
10. HISTORIC ARCHITECTURE CONSULTANT	
11. ENVIRONMENTAL ENGINEER	
12. TRANSPORTATION ENGINEER	
13. TRAFFIC ENGINEER	
14. GEOTECHNICAL ENGINEER	
15. SOIL REMEDIATION ENGINEER	
16. ASBESTOS ABATEMENT ENGINEER	
17. LEAD ABATEMENT ENGINEER	
18. MOLD ABATEMENT ENGINEER	
19. REMEDIATION ENGINEER	
20. ENVIRONMENTAL SCIENTIST	
21. ENVIRONMENTAL HEALTH AND SAFETY ENGINEER	
22. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
23. ENVIRONMENTAL HEALTH AND SAFETY ASSISTANT	
24. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
25. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
26. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
27. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
28. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
29. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
30. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
31. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
32. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
33. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
34. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
35. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
36. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
37. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
38. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
39. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
40. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
41. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
42. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
43. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
44. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
45. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
46. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
47. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
48. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
49. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
50. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
51. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
52. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
53. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
54. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
55. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
56. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
57. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
58. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
59. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
60. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
61. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
62. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
63. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
64. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
65. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
66. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
67. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
68. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
69. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
70. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
71. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
72. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
73. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
74. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
75. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
76. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
77. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
78. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
79. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
80. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
81. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
82. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
83. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
84. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
85. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
86. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
87. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
88. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
89. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
90. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
91. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
92. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	
93. ENVIRONMENTAL HEALTH AND SAFETY CONSULTANT	
94. ENVIRONMENTAL HEALTH AND SAFETY ADVISOR	
95. ENVIRONMENTAL HEALTH AND SAFETY SPECIALIST	
96. ENVIRONMENTAL HEALTH AND SAFETY MONITOR	
97. ENVIRONMENTAL HEALTH AND SAFETY SUPERVISOR	
98. ENVIRONMENTAL HEALTH AND SAFETY MANAGER	
99. ENVIRONMENTAL HEALTH AND SAFETY DIRECTOR	
100. ENVIRONMENTAL HEALTH AND SAFETY EXECUTIVE	

S104B

- 1. GENERAL CONTRACTOR SERVICES FOR CONCRETE CONSTRUCTION SHALL INCLUDE:
  - a. FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - b. ALL REINFORCING, INCLUDING THE BARRETS, TIES AND SPOOLS ON THE PLACES OF ALL CONCRETE WORK.
  - c. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - d. ALL CONCRETE WORK, INCLUDING THE CURING AND FINISHING OF ALL CONCRETE WORK.
  - e. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - f. ALL REINFORCING, INCLUDING THE BARRETS, TIES AND SPOOLS ON THE PLACES OF ALL CONCRETE WORK.
  - g. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - h. ALL CONCRETE WORK, INCLUDING THE CURING AND FINISHING OF ALL CONCRETE WORK.
  - i. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - j. ALL REINFORCING, INCLUDING THE BARRETS, TIES AND SPOOLS ON THE PLACES OF ALL CONCRETE WORK.
  - k. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - l. ALL CONCRETE WORK, INCLUDING THE CURING AND FINISHING OF ALL CONCRETE WORK.
  - m. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - n. ALL REINFORCING, INCLUDING THE BARRETS, TIES AND SPOOLS ON THE PLACES OF ALL CONCRETE WORK.
  - o. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - p. ALL CONCRETE WORK, INCLUDING THE CURING AND FINISHING OF ALL CONCRETE WORK.
  - q. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - r. ALL REINFORCING, INCLUDING THE BARRETS, TIES AND SPOOLS ON THE PLACES OF ALL CONCRETE WORK.
  - s. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - t. ALL CONCRETE WORK, INCLUDING THE CURING AND FINISHING OF ALL CONCRETE WORK.
  - u. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - v. ALL REINFORCING, INCLUDING THE BARRETS, TIES AND SPOOLS ON THE PLACES OF ALL CONCRETE WORK.
  - w. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - x. ALL CONCRETE WORK, INCLUDING THE CURING AND FINISHING OF ALL CONCRETE WORK.
  - y. ALL FORMWORK, SCAFFOLDING, BRACING, AND SHORING ON THE PLACES OF ALL CONCRETE WORK.
  - z. ALL REINFORCING, INCLUDING THE BARRETS, TIES AND SPOOLS ON THE PLACES OF ALL CONCRETE WORK.



1 4TH FLOOR PLAN - SOUTH  
08/20/14






WJE: green areas indicate steps in slab where tendons are non-continuous (start and stop) - not matching design drawing

REVISION	DATE	BY	CHK	DESCRIPTION
1	02/22/18	...	...	...
2	02/22/18	...	...	...
3	02/22/18	...	...	...
4	02/22/18	...	...	...
5	02/22/18	...	...	...
6	02/22/18	...	...	...
7	02/22/18	...	...	...
8	02/22/18	...	...	...
9	02/22/18	...	...	...
10	02/22/18	...	...	...
11	02/22/18	...	...	...
12	02/22/18	...	...	...
13	02/22/18	...	...	...
14	02/22/18	...	...	...
15	02/22/18	...	...	...
16	02/22/18	...	...	...
17	02/22/18	...	...	...
18	02/22/18	...	...	...
19	02/22/18	...	...	...
20	02/22/18	...	...	...
21	02/22/18	...	...	...
22	02/22/18	...	...	...
23	02/22/18	...	...	...
24	02/22/18	...	...	...
25	02/22/18	...	...	...
26	02/22/18	...	...	...
27	02/22/18	...	...	...
28	02/22/18	...	...	...
29	02/22/18	...	...	...
30	02/22/18	...	...	...
31	02/22/18	...	...	...
32	02/22/18	...	...	...
33	02/22/18	...	...	...
34	02/22/18	...	...	...
35	02/22/18	...	...	...
36	02/22/18	...	...	...
37	02/22/18	...	...	...
38	02/22/18	...	...	...
39	02/22/18	...	...	...
40	02/22/18	...	...	...
41	02/22/18	...	...	...
42	02/22/18	...	...	...
43	02/22/18	...	...	...
44	02/22/18	...	...	...
45	02/22/18	...	...	...
46	02/22/18	...	...	...
47	02/22/18	...	...	...
48	02/22/18	...	...	...
49	02/22/18	...	...	...
50	02/22/18	...	...	...
51	02/22/18	...	...	...
52	02/22/18	...	...	...
53	02/22/18	...	...	...
54	02/22/18	...	...	...
55	02/22/18	...	...	...
56	02/22/18	...	...	...
57	02/22/18	...	...	...
58	02/22/18	...	...	...
59	02/22/18	...	...	...
60	02/22/18	...	...	...
61	02/22/18	...	...	...
62	02/22/18	...	...	...
63	02/22/18	...	...	...
64	02/22/18	...	...	...
65	02/22/18	...	...	...
66	02/22/18	...	...	...
67	02/22/18	...	...	...
68	02/22/18	...	...	...
69	02/22/18	...	...	...
70	02/22/18	...	...	...
71	02/22/18	...	...	...
72	02/22/18	...	...	...
73	02/22/18	...	...	...
74	02/22/18	...	...	...
75	02/22/18	...	...	...
76	02/22/18	...	...	...
77	02/22/18	...	...	...
78	02/22/18	...	...	...
79	02/22/18	...	...	...
80	02/22/18	...	...	...
81	02/22/18	...	...	...
82	02/22/18	...	...	...
83	02/22/18	...	...	...
84	02/22/18	...	...	...
85	02/22/18	...	...	...
86	02/22/18	...	...	...
87	02/22/18	...	...	...
88	02/22/18	...	...	...
89	02/22/18	...	...	...
90	02/22/18	...	...	...
91	02/22/18	...	...	...
92	02/22/18	...	...	...
93	02/22/18	...	...	...
94	02/22/18	...	...	...
95	02/22/18	...	...	...
96	02/22/18	...	...	...
97	02/22/18	...	...	...
98	02/22/18	...	...	...
99	02/22/18	...	...	...
100	02/22/18	...	...	...

NOTES:  
 1- REFER TO DETAIL 19PT-1.01 FOR ALL TENDONS SWEEP AROUND OPENINGS  
 2- SITTING TAIL TO BE A MAXIMUM OF 18". REFER TO DETAIL 3PT-1.01  
 3- E-O-R TO VERIFY CONSTRUCTION JOINT LOCATIONS.  
 4- E-O-R TO VERIFY SLAB TENDON LAYOUT.



SLAB TENDON LAYOUT - 5TH FLOOR (SLAB THICKNESS 7 1/2" U.N.O.)  
 SCALE: 3/32"=1'-0"

**APPROVED  
 FOR CONSTRUCTION**

ENCAPSULATED  
 (ENCAPSULATED ANCHORS)

**REVISIONS**

No.	Date	Description
1	02/22/18	FOR APPROVAL
2	02/22/18	FOR CONSTRUCTION
3	02/22/18	FOR CONSTRUCTION

**PROJECT:** HARBOR POINT  
 BLOCK P4-P5  
 STAMFORD, CT

**CLIENT:** BAKER CONCRETE  
 CONTRACT DRAWINGS  
 Issue: 02/22/18

**DRAWING REFERENCE:** SPT-A & SPT-B  
 PT-2.09

**DRAWING TITLE:** 5TH FLOOR  
 SLAB TENDON LAYOUT

**REVISIONS:** 1- 11/15/17  
 2- 11/15/17  
 3- 11/15/17  
 4- 11/15/17  
 5- 11/15/17  
 6- 11/15/17  
 7- 11/15/17  
 8- 11/15/17  
 9- 11/15/17  
 10- 11/15/17  
 11- 11/15/17  
 12- 11/15/17  
 13- 11/15/17  
 14- 11/15/17  
 15- 11/15/17  
 16- 11/15/17  
 17- 11/15/17  
 18- 11/15/17  
 19- 11/15/17  
 20- 11/15/17  
 21- 11/15/17  
 22- 11/15/17  
 23- 11/15/17  
 24- 11/15/17  
 25- 11/15/17  
 26- 11/15/17  
 27- 11/15/17  
 28- 11/15/17  
 29- 11/15/17  
 30- 11/15/17  
 31- 11/15/17  
 32- 11/15/17  
 33- 11/15/17  
 34- 11/15/17  
 35- 11/15/17  
 36- 11/15/17  
 37- 11/15/17  
 38- 11/15/17  
 39- 11/15/17  
 40- 11/15/17  
 41- 11/15/17  
 42- 11/15/17  
 43- 11/15/17  
 44- 11/15/17  
 45- 11/15/17  
 46- 11/15/17  
 47- 11/15/17  
 48- 11/15/17  
 49- 11/15/17  
 50- 11/15/17  
 51- 11/15/17  
 52- 11/15/17  
 53- 11/15/17  
 54- 11/15/17  
 55- 11/15/17  
 56- 11/15/17  
 57- 11/15/17  
 58- 11/15/17  
 59- 11/15/17  
 60- 11/15/17  
 61- 11/15/17  
 62- 11/15/17  
 63- 11/15/17  
 64- 11/15/17  
 65- 11/15/17  
 66- 11/15/17  
 67- 11/15/17  
 68- 11/15/17  
 69- 11/15/17  
 70- 11/15/17  
 71- 11/15/17  
 72- 11/15/17  
 73- 11/15/17  
 74- 11/15/17  
 75- 11/15/17  
 76- 11/15/17  
 77- 11/15/17  
 78- 11/15/17  
 79- 11/15/17  
 80- 11/15/17  
 81- 11/15/17  
 82- 11/15/17  
 83- 11/15/17  
 84- 11/15/17  
 85- 11/15/17  
 86- 11/15/17  
 87- 11/15/17  
 88- 11/15/17  
 89- 11/15/17  
 90- 11/15/17  
 91- 11/15/17  
 92- 11/15/17  
 93- 11/15/17  
 94- 11/15/17  
 95- 11/15/17  
 96- 11/15/17  
 97- 11/15/17  
 98- 11/15/17  
 99- 11/15/17  
 100- 11/15/17

**POST-TENSIONING INSTITUTE**  
 CCI  
 CCL



**DESIGNER:** SUBMITTAL

No.	Date	Description
1	02/22/18	FOR APPROVAL
2	02/22/18	FOR CONSTRUCTION
3	02/22/18	FOR CONSTRUCTION

**PROJECT:** HARBOR POINT  
 BLOCK P4-P5  
 STAMFORD, CT

**CLIENT:** BAKER CONCRETE  
 CONTRACT DRAWINGS  
 Issue: 02/22/18

**DRAWING REFERENCE:** SPT-A & SPT-B  
 PT-2.09

**DRAWING TITLE:** 5TH FLOOR  
 SLAB TENDON LAYOUT

PT-2.10  
DRAWING NO.  
DRAWING TITLE  
5TH FLOOR  
SLAB TENDON LAYOUT

PROJECT  
HARBOR POINT  
BLOCK P4-P5  
STAMFORD, CT

CLIENT:  
BAKER CONCRETE  
CONSTRUCTION

CONTRACT DOCUMENTS  
- Issue : SUPERSTRUCTURE  
- Date : 02/23/18

No.	Date	Checked	Drawn
1	02/23/18	FOR APPROVAL	FOR APPROVAL
2	02/23/18	FOR CONSTRUCTION	FOR CONSTRUCTION
3	02/23/18	FOR CONSTRUCTION	FOR CONSTRUCTION

DATE: 02/23/18




POST-TENSIONING  
INSTITUTE  
CERTIFIED PLANT

ENCAPSULATED  
(ENCAPSULATED ANCHORS)

APPROVED  
FOR CONSTRUCTION

SLAB TENDON LAYOUT - 5TH FLOOR (SLAB THICKNESS 7 1/2" U.N.O.)  
SCALE: 3/32"=1'-0"

TENDON LAYOUT	
1	1" SLAB
2	2" SLAB
3	3" SLAB
4	4" SLAB
5	5" SLAB
6	6" SLAB
7	7" SLAB
8	8" SLAB
9	9" SLAB
10	10" SLAB
11	11" SLAB
12	12" SLAB
13	13" SLAB
14	14" SLAB
15	15" SLAB
16	16" SLAB
17	17" SLAB
18	18" SLAB
19	19" SLAB
20	20" SLAB
21	21" SLAB
22	22" SLAB
23	23" SLAB
24	24" SLAB
25	25" SLAB
26	26" SLAB
27	27" SLAB
28	28" SLAB
29	29" SLAB
30	30" SLAB
31	31" SLAB
32	32" SLAB
33	33" SLAB
34	34" SLAB
35	35" SLAB
36	36" SLAB
37	37" SLAB
38	38" SLAB
39	39" SLAB
40	40" SLAB
41	41" SLAB
42	42" SLAB
43	43" SLAB
44	44" SLAB
45	45" SLAB
46	46" SLAB
47	47" SLAB
48	48" SLAB
49	49" SLAB
50	50" SLAB
51	51" SLAB
52	52" SLAB
53	53" SLAB
54	54" SLAB
55	55" SLAB
56	56" SLAB
57	57" SLAB
58	58" SLAB
59	59" SLAB
60	60" SLAB
61	61" SLAB
62	62" SLAB
63	63" SLAB
64	64" SLAB
65	65" SLAB
66	66" SLAB
67	67" SLAB
68	68" SLAB
69	69" SLAB
70	70" SLAB
71	71" SLAB
72	72" SLAB
73	73" SLAB
74	74" SLAB
75	75" SLAB
76	76" SLAB
77	77" SLAB
78	78" SLAB
79	79" SLAB
80	80" SLAB
81	81" SLAB
82	82" SLAB
83	83" SLAB
84	84" SLAB
85	85" SLAB
86	86" SLAB
87	87" SLAB
88	88" SLAB
89	89" SLAB
90	90" SLAB
91	91" SLAB
92	92" SLAB
93	93" SLAB
94	94" SLAB
95	95" SLAB
96	96" SLAB
97	97" SLAB
98	98" SLAB
99	99" SLAB
100	100" SLAB



REVISION	REVISION #	DATE	BY	DESCRIPTION
	1	02/23/18	JL	ISSUE FOR CONSTRUCTION
	2	02/23/18	JL	ISSUE FOR CONSTRUCTION
	3	02/23/18	JL	ISSUE FOR CONSTRUCTION
	4	02/23/18	JL	ISSUE FOR CONSTRUCTION
	5	02/23/18	JL	ISSUE FOR CONSTRUCTION
	6	02/23/18	JL	ISSUE FOR CONSTRUCTION
	7	02/23/18	JL	ISSUE FOR CONSTRUCTION
	8	02/23/18	JL	ISSUE FOR CONSTRUCTION
	9	02/23/18	JL	ISSUE FOR CONSTRUCTION
	10	02/23/18	JL	ISSUE FOR CONSTRUCTION
	11	02/23/18	JL	ISSUE FOR CONSTRUCTION
	12	02/23/18	JL	ISSUE FOR CONSTRUCTION
	13	02/23/18	JL	ISSUE FOR CONSTRUCTION
	14	02/23/18	JL	ISSUE FOR CONSTRUCTION
	15	02/23/18	JL	ISSUE FOR CONSTRUCTION
	16	02/23/18	JL	ISSUE FOR CONSTRUCTION
	17	02/23/18	JL	ISSUE FOR CONSTRUCTION
	18	02/23/18	JL	ISSUE FOR CONSTRUCTION
	19	02/23/18	JL	ISSUE FOR CONSTRUCTION
	20	02/23/18	JL	ISSUE FOR CONSTRUCTION
	21	02/23/18	JL	ISSUE FOR CONSTRUCTION
	22	02/23/18	JL	ISSUE FOR CONSTRUCTION
	23	02/23/18	JL	ISSUE FOR CONSTRUCTION
	24	02/23/18	JL	ISSUE FOR CONSTRUCTION
	25	02/23/18	JL	ISSUE FOR CONSTRUCTION
	26	02/23/18	JL	ISSUE FOR CONSTRUCTION
	27	02/23/18	JL	ISSUE FOR CONSTRUCTION
	28	02/23/18	JL	ISSUE FOR CONSTRUCTION
	29	02/23/18	JL	ISSUE FOR CONSTRUCTION
	30	02/23/18	JL	ISSUE FOR CONSTRUCTION
	31	02/23/18	JL	ISSUE FOR CONSTRUCTION
	32	02/23/18	JL	ISSUE FOR CONSTRUCTION
	33	02/23/18	JL	ISSUE FOR CONSTRUCTION
	34	02/23/18	JL	ISSUE FOR CONSTRUCTION
	35	02/23/18	JL	ISSUE FOR CONSTRUCTION
	36	02/23/18	JL	ISSUE FOR CONSTRUCTION
	37	02/23/18	JL	ISSUE FOR CONSTRUCTION
	38	02/23/18	JL	ISSUE FOR CONSTRUCTION
	39	02/23/18	JL	ISSUE FOR CONSTRUCTION
	40	02/23/18	JL	ISSUE FOR CONSTRUCTION
	41	02/23/18	JL	ISSUE FOR CONSTRUCTION
	42	02/23/18	JL	ISSUE FOR CONSTRUCTION
	43	02/23/18	JL	ISSUE FOR CONSTRUCTION
	44	02/23/18	JL	ISSUE FOR CONSTRUCTION
	45	02/23/18	JL	ISSUE FOR CONSTRUCTION
	46	02/23/18	JL	ISSUE FOR CONSTRUCTION
	47	02/23/18	JL	ISSUE FOR CONSTRUCTION
	48	02/23/18	JL	ISSUE FOR CONSTRUCTION
	49	02/23/18	JL	ISSUE FOR CONSTRUCTION
	50	02/23/18	JL	ISSUE FOR CONSTRUCTION
	51	02/23/18	JL	ISSUE FOR CONSTRUCTION
	52	02/23/18	JL	ISSUE FOR CONSTRUCTION
	53	02/23/18	JL	ISSUE FOR CONSTRUCTION
	54	02/23/18	JL	ISSUE FOR CONSTRUCTION
	55	02/23/18	JL	ISSUE FOR CONSTRUCTION
	56	02/23/18	JL	ISSUE FOR CONSTRUCTION
	57	02/23/18	JL	ISSUE FOR CONSTRUCTION
	58	02/23/18	JL	ISSUE FOR CONSTRUCTION
	59	02/23/18	JL	ISSUE FOR CONSTRUCTION
	60	02/23/18	JL	ISSUE FOR CONSTRUCTION
	61	02/23/18	JL	ISSUE FOR CONSTRUCTION
	62	02/23/18	JL	ISSUE FOR CONSTRUCTION
	63	02/23/18	JL	ISSUE FOR CONSTRUCTION
	64	02/23/18	JL	ISSUE FOR CONSTRUCTION
	65	02/23/18	JL	ISSUE FOR CONSTRUCTION
	66	02/23/18	JL	ISSUE FOR CONSTRUCTION
	67	02/23/18	JL	ISSUE FOR CONSTRUCTION
	68	02/23/18	JL	ISSUE FOR CONSTRUCTION
	69	02/23/18	JL	ISSUE FOR CONSTRUCTION
	70	02/23/18	JL	ISSUE FOR CONSTRUCTION
	71	02/23/18	JL	ISSUE FOR CONSTRUCTION
	72	02/23/18	JL	ISSUE FOR CONSTRUCTION
	73	02/23/18	JL	ISSUE FOR CONSTRUCTION
	74	02/23/18	JL	ISSUE FOR CONSTRUCTION
	75	02/23/18	JL	ISSUE FOR CONSTRUCTION
	76	02/23/18	JL	ISSUE FOR CONSTRUCTION
	77	02/23/18	JL	ISSUE FOR CONSTRUCTION
	78	02/23/18	JL	ISSUE FOR CONSTRUCTION
	79	02/23/18	JL	ISSUE FOR CONSTRUCTION
	80	02/23/18	JL	ISSUE FOR CONSTRUCTION
	81	02/23/18	JL	ISSUE FOR CONSTRUCTION
	82	02/23/18	JL	ISSUE FOR CONSTRUCTION
	83	02/23/18	JL	ISSUE FOR CONSTRUCTION
	84	02/23/18	JL	ISSUE FOR CONSTRUCTION
	85	02/23/18	JL	ISSUE FOR CONSTRUCTION
	86	02/23/18	JL	ISSUE FOR CONSTRUCTION
	87	02/23/18	JL	ISSUE FOR CONSTRUCTION
	88	02/23/18	JL	ISSUE FOR CONSTRUCTION
	89	02/23/18	JL	ISSUE FOR CONSTRUCTION
	90	02/23/18	JL	ISSUE FOR CONSTRUCTION
	91	02/23/18	JL	ISSUE FOR CONSTRUCTION
	92	02/23/18	JL	ISSUE FOR CONSTRUCTION
	93	02/23/18	JL	ISSUE FOR CONSTRUCTION
	94	02/23/18	JL	ISSUE FOR CONSTRUCTION
	95	02/23/18	JL	ISSUE FOR CONSTRUCTION
	96	02/23/18	JL	ISSUE FOR CONSTRUCTION
	97	02/23/18	JL	ISSUE FOR CONSTRUCTION
	98	02/23/18	JL	ISSUE FOR CONSTRUCTION
	99	02/23/18	JL	ISSUE FOR CONSTRUCTION
	100	02/23/18	JL	ISSUE FOR CONSTRUCTION

PLEASE SEE PREVIOUS SHEET FOR TENDON CHART (PART 1)

NOTES:

- 1- REFER TO DETAIL SPT-1.01 FOR ALL TENDONS SWEEP AROUND OPENINGS.
- 2- REFER TO DETAIL SPT-1.02 FOR ALL TENDONS SWEEP AROUND OPENINGS.
- 3- E-O R TO VERIFY CONSTRUCTION JOINT LOCATIONS.
- 4- E-O R TO VERIFY SLAB TENDON LAYOUT.





March 21, 2022

Mr. Tim Yahn  
Managing Director of Construction  
**Building and Land Technology**  
1 Elmcroft Road – Suite 500  
Stamford, CT 06902

**RE: Response: Harbor Points-The Allure-Special Inspection Questions-WJE Comment 1  
850 Pacific Street, Stamford CT**

Dear Tim:

This letter is a follow up to our previous response letter dated February 22, 2022. In response to the first paragraph comment from the Wiss, Janney, Elstner (WJE) letter dated February 18, 2022, we stated the following:

*We have been reviewing all of the inspection reports, PT and mild steel shop drawings, and the recently received pour sequence document, correspondence, and photographs from Baker concrete. We intend to publish locations for review with the City of Stamford and/ or their Engineering or technical representative, as well as the Design, Development, and Construction teams where we find potential discrepancies or where additional testing may be required to determine or verify as-built conditions.*

We have completed a thorough review and analysis of the existing conditions based on additional reviews of the shop drawings, test reports, photographs, recently developed pour sequences, and technical discussions with Baker Concrete and their post tension Engineer/ Supplier, CCL. From our review, we discovered that the post tension Engineer, CCL modified the original design intent shown on the Construction Documents at the stepped plaza deck. Instead of running the tendons continuous through the step, they were terminated at the upper and lower slab faces, similar to (but not the same) as the collapsed slab area. This modification altered the design and behavior from a continuous flat plate spanning between columns to a cantilevered slab, with opposing ends of the cantilever occurring at the step.

Upon discovery, we contacted CCL to ask if the modification was intentional, as we had not been notified of the change. Simultaneously, we developed a new post-tension analysis model of the entire garage roof and plaza deck, implementing our understanding of the as-built conditions. CCL's subsequent response to our inquiry revealed that the modified design was not their intent, so we requested that they engineer and develop a separate model for comparison.

The two (2) models reflecting the as-built conditions were completed and reviewed thoroughly last week by our firm and CCL. The results of the models were very close; however, in one of the models we found a slight overstress in three (3) isolated locations when subjected to the code prescribed superimposed live loads. As a result, we have engineered a design for a new concrete beam to be added along Grid G9, between Grids GD and GE and a design to strengthen the two (2) beams at Grids G7 and G8, between GD and GE. With the new beam addition and the strengthening of the two (2) existing




Tim Yahn  
Building and Land Technology  
March 21, 2022  
Page 2 of 2

beams, the code prescribed limit states for both models are satisfied. Each model, a plan, and details for entire garage deck will be submitted to the City of Stamford and WJE for review.

As previously mentioned, we have completed our overall review of the plaza deck and garage. Based on the information collected, including photographs, inspection reports, shop drawings, pour sequence documents, and correspondence, it is our opinion that the design and construction discrepancies stated in this letter are limited to the radial step that occurs on the plaza deck. We have photographs and inspection reports to confirm the general construction and reinforcing layout of the as-built conditions in several locations, but we recommend that the radial stepped section be scanned to confirm what we modeled and designed per Sheet S105D. A complete scan of all exposed surfaces of the plaza deck is not reasonable in our opinion, based on what we discovered from our review.

We hope that you find this information useful and believe this response should satisfy the outstanding response stated in the WJE letter. Please contact our office should you have any questions or need additional information.

Respectfully,  
**Henderson Rogers Structural Engineers, LLC**



Madison H. Henderson, P.E.  
Principal



03/21/2022

Cc: Ralph Martin (BLT); Bruce Yahn (BLT); Donn McGinnis (Baker); Vivek Gurjar, PE (HRSE); Ben Downing (DCE)





B-22-322

## Engineering approval

### Building Permit

**Status:** Complete

**Became Active:** 03/15/2022

**Assignee:** Louis Casolo

**Completed:** 04/27/2022

### Applicant

Carla Catanzaro  
ccatanzaro@bltoffice.com  
1 Elmcroft Road  
Suite 500  
stamford , ct 06902  
2036441554

### Location

850 PACIFIC STREET Unit P 4&5  
Unit P 4&5  
STAMFORD, CT 06902

### Owner:

HPP-FOUR LLC  
PO BOX 110295 STAMFORD, CT 06911-0295

### Comments

**Louis Casolo, Apr 27, 2022 at 10:16am**

These are the engineering conditions of approval:

- Applicant to provide WJE with copies of all shop drawings being transmitted for repairs and copies of all exchanges in the shop drawing submittal process between the contractor and designer of record with comments and approvals.
- Applicant to provide a repair project schedule to WJE
- The applicant is responsible for coordinating the following: 1.Prior to the start of construction, WJE will attend a kick-off meeting with the team to go over the schedule and work plan. 2. During construction, WJE will perform site visits prior to the pouring of all concrete to confirm that the installation is completed in accordance with the design drawings and shop drawings.
- Applicant to provide WJE with all certification letters of approval following the construction repair from the design engineer of record (HRSE) and from the special inspectors that the work was completed per the approved plans.
- Applicant shall complete all scanning of slabs as previously requested by WJE that have not yet been completed.

The final version of the calculations and drawings approved by WJE are dated April 15, 2022 and are attached to this permit.



Wiss, Janney, Elstner Associates, Inc. (WJE) has completed a peer review of the five analytical models that make up the Level 5 slab at the Harbor Points project in Stamford, CT. This peer review was focused particularly on slab steps and how they were modified analytically to reflect recently discovered as-built conditions regarding the termination of post-tensioning anchorages. The five models were all constructed using the commercial software ADAPT Builder. Our comments and questions are as follows:

1. For slab steps highlighted red in Figure 1, the EOR's analytical approach appeared to be the following: The "upper slab" and "lower slab" were modeled separately. To simulate the support provided by the lower slab, the upper slab was modeled with a concrete wall at the location of the step, and the lower slab was modeled with applied loads (intended to be reactions from the wall) at the same location.

In the "upper slab" models, the wall was modeled with moment fixity at the slab connection (i.e. moments were not released). However, no applied moments were then transferred to the "lower slab" models (only vertical forces). This is analytically inconsistent and should be resolved.




Figure 1. 5th Floor Overall

2. As described above, "lower slab" models included applied loads at the location of the step, which were intended to simulate support of the upper slab. At the two slab steps indicated with orange arrows in Figure 1, these loads were not linearly applied as would be expected, but were instead point loads located at column locations only. This load application is not consistent with the "lower slab as a continuous support of the upper slab" analytical concept and should be corrected.

Additionally, the applied point loads along the steps indicated with orange arrows appear somewhat light for the load cases "Roof Live Load" and "Snow Load." For each case, the point load magnitudes (approximately 2 to 3-kips or less) correspond to applied area loads of about 10 pounds per square foot (psf) or less. The design drawings indicate Roof Live Loads of 20 psf and flat roof Snow Loads of 30 psf.

3. Similarly, for the slab step indicated with a blue arrow in Figure 1, the applied loads in the "lower slab" model appear somewhat light. In the "upper slab" model at this location, linear reactions at the slab step "wall support" are approximately 1500-2000 pounds per linear foot (plf) for "Dead Load" and 600-800 plf for "Live Load." In the "lower slab" model, applied reactions are only 1300-1600 plf for "Dead Load" and only 250-350 plf for "Live Load." These discrepancies should be resolved.
4. In all analytical models, concrete slabs were modeled with 28-day compressive strengths ( $f_c'$ ) ranging from 6,700 to 9,000 pounds per square inch (psi), compared to the design strength (indicated on S002) of only 5,000 psi. Please clarify. Are the modeled compressive strengths reflective of construction testing data?
5. While just a "spot check" and not a comprehensive review, we noted seven locations in which ADAPT called for a greater number of top reinforcing bars than is shown on the design drawings. These are indicated on the attached excerpted sheets (S105RR-A and S105RR-B).



International, PC

1000 WEST 10TH AVENUE  
DENVER, CO 80202  
TEL: 303.733.1100  
WWW.EDF.COM

INTERNATIONAL  
TECHNOLOGY  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION

INTERNATIONAL  
CORPORATION



# HARBOR POINT BLOCK P4-P5 STAMFORD, CT



PROJECT NO.	1101000
DATE	08/11/00
SCALE	AS SHOWN
DRAWN BY	EDF
CHECKED BY	EDF
DATE	08/11/00

5TH FLOOR PLAN  
- REIN -  
S105RRR-A

- REVISIONS:
1. REVISIONS TO THE PLAN
  2. REVISIONS TO THE PLAN
  3. REVISIONS TO THE PLAN
  4. REVISIONS TO THE PLAN
  5. REVISIONS TO THE PLAN



1 5TH FLOOR REINFORCEMENT PLAN - NORTH



International PC  
 7-11-33-4  
 1609 W. 20th St. #4  
 New York, NY 10011  
 212-312-3121  
 www.edf.com  
**INTERNATIONAL PC**  
 ENGINEERING AND  
 TECHNOLOGY  
 1912-52-99  
 1912-52-99  
 1912-52-99  
 1912-52-99  
**CONTRACT**  
 PROJECT NO.  
 CONTRACT NO.  
**DESIGN & DRAW**  
 PROJECT NO.  
 CONTRACT NO.  
**CLIENT**  
 PROJECT NO.  
 CONTRACT NO.  
**COLLECTIVE MEMBERSHIP**  
 COLLECTIVE MEMBERSHIP  
 COLLECTIVE MEMBERSHIP  
**MEMBER FIRMS**  
 PROJECT NO.  
 CONTRACT NO.  
**PROJECT TITLE**  
 PROJECT NO.  
 CONTRACT NO.

**HARBOR POINT  
 BLOCK P4-P5  
 STAMFORD, CT**

ENGINEERED BY  
 PROJECT NO.  
 CONTRACT NO.  
 SHEET NO.





1. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST EDITIONS OF THE ACI 318-11 AND ACI 308-11.

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.

3. ALL REINFORCEMENT SHALL BE SUBJECT TO INSPECTION AND TESTING.

4. THE CONTRACTOR SHALL MAINTAIN RECORDS OF ALL REINFORCEMENT INSTALLED.



1 5TH FLOOR REINFORCEMENT PLAN - SOUTH

S105RR-B







August 11, 2022

Mr. John Cocca, P.E.  
Associate Principal  
**WJE Engineers & Architects, P.C.**  
2 Trap Falls Road, Suite 502  
Stamford, CT 06484

**RE: Response: Harbor Points-The Allure Stamford Model Review-WJE Comments  
850 Pacific Street, Stamford CT**

Dear John:

We received the above referenced letter, dated July 22, 2022, with comments from Wiss Janney Elstner (WJE) and addressed to Henderson and Rogers Structural Engineers, LLC (HRSE). The letter requests responses to follow up questions regarding the building design models (Adapt Builder) submitted by our office to WJE for review. WJE's comments and our subsequent responses are attached with this letter.

We hope that you find this information useful, and that our responses address all outstanding questions or concerns. Please contact our office should you need any additional information regarding this matter.

Respectfully,  
**Henderson Rogers Structural Engineers, LLC**

A handwritten signature in blue ink, appearing to read "Madison H. Henderson".

Madison H. Henderson, P.E.  
Principal



08/11/2022

Cc: Donn McGinnis (Baker); Vivek Gurjar, PE (HRSE)

Wiss, Janney, Elstner Associates, Inc. (WJE) has completed a peer review of the five analytical models that make up the Level 5 slab at the Harbor Points project in Stamford, CT. This peer review was focused particularly on slab steps and how they were modified analytically to reflect recently discovered as-built conditions regarding the termination of post-tensioning anchorages. The five models were all constructed using the commercial software ADAPT Builder. Our comments and questions are as follows:

1. For slab steps highlighted red in Figure 1, the EOR's analytical approach appeared to be the following: The "upper slab" and "lower slab" were modeled separately. To simulate the support provided by the lower slab, the upper slab was modeled with a concrete wall at the location of the step, and the lower slab was modeled with applied loads (intended to be reactions from the wall) at the same location.

In the "upper slab" models, the wall was modeled with moment fixity at the slab connection (i.e. moments were not released). However, no applied moments were then transferred to the "lower slab" models (only vertical forces). This is analytically inconsistent and should be resolved.

HRSE: THE MOMENTS WERE NOT RELEASE AT THE LOW SLAB SUPPORT CONDITION, THESE MOMENT VALUES ARE VERY SMALL AS THE UNIFORM CABLES ARE PARALLEL TO THE STEP AND TRANSFER THE FORCE TO THE BANDED CABLE THAT FRAME INTO THE COLUMN.




Figure 1. 5th Floor Overall

2. As described above, "lower slab" models included applied loads at the location of the step, which were intended to simulate support of the upper slab. At the two slab steps indicated with orange arrows in Figure 1, these loads were not linearly applied as would be expected, but were instead point loads located at column locations only. This load application is not consistent with the "lower slab as a continuous support of the upper slab" analytical concept and should be corrected.

HRSE: See attached sheet for explanation.

Additionally, the applied point loads along the steps indicated with orange arrows appear somewhat light for the load cases "Roof Live Load" and "Snow Load." For each case, the point load magnitudes (approximately 2 to 3-kips or less) correspond to applied area loads of about 10 pounds per square foot (psf) or less. The design drawings indicate Roof Live Loads of 20 psf and flat roof Snow Loads of 30 psf.

HRSE: See attached sheet for load calculation.

3. Similarly, for the slab step indicated with a blue arrow in Figure 1, the applied loads in the "lower slab" model appear somewhat light. In the "upper slab" model at this location, linear reactions at the slab step "wall support" are approximately 1500-2000 pounds per linear foot (plf) for "Dead Load" and 600-800 plf for "Live Load." In the "lower slab" model, applied reactions are only 1300-1600 plf for "Dead Load" and only 250-350 plf for "Live Load." These discrepancies should be resolved.

HRSE: See response to question number 2, a similar concept was applied.

4. In all analytical models, concrete slabs were modeled with 28-day compressive strengths ( $f_c'$ ) ranging from 6,700 to 9,000 pounds per square inch (psi), compared to the design strength (indicated on S002) of only 5,000 psi. Please clarify. Are the modeled compressive strengths reflective of construction testing data?

HRSE: Construction documents specify concrete compressive strengths for floor framing as 5,000 psi with the understanding that 6,000 psi concrete will be installed to be able to stress the cables at 24 hour break. For checking the existing structure in its as-built condition we have used the lower values for concrete strength from the testing reports. In our professional opinion this is a reasonable inference given that the concrete breaks range from 7,000 to 9,000 psi for in-situ concrete.

5. While just a "spot check" and not a comprehensive review, we noted seven locations in which ADAPT called for a greater number of top reinforcing bars than is shown on the design drawings. These are indicated on the attached excerpted sheets (S105RR-A and S105RR-B).

HRSE: See attached sheet for comments.



EDF International, PC

3000 W. 10th Street  
Stamford, CT 06907  
Tel: 203.353.1000  
Fax: 203.353.1001  
www.edf.com

INTERNATIONAL  
TECHNOLOGY  
CORPORATION

GENERAL CONTRACTOR

ARCHITECT

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

CIVIL ENGINEER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER


# HARBOR POINT STAMFORD, CT



DATE	11/11/00
BY	EDF
PROJECT	HARBOR POINT
DESCRIPTION	5TH FLOOR PLAN
SCALE	AS SHOWN
REVISIONS	

5TH FLOOR PLAN  
- REINFC  
S105RR-A

- 1. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 2. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 3. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 4. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 5. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 6. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 7. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 8. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 9. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.
- 10. ALL REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE REINFORCEMENT SCHEDULE.






1 5TH FLOOR REINFORCEMENT PLAN - NORTH



INTERNATIONAL, P.C.  
 311 N. 13th St., Suite 100  
 Stamford, CT 06901  
 Tel: (203) 340-1100  
 Fax: (203) 340-1101  
 WWW.EDF.COM  
**EDF INTERNATIONAL, P.C.**  
 REGISTERED PROFESSIONAL ENGINEERS  
 CIVIL ENGINEERS  
 MECHANICAL ENGINEERS  
 ELECTRICAL ENGINEERS  
 CHEMICAL ENGINEERS  
 COLLECTIVE DESIGN  
 INCORPORATED  
 2010-2011  
 STATE OF CONNECTICUT  
 REGISTRATION NO. 06575-REG-001

HARBOR POINT  
 BLOCK P4-P5  
 STAMFORD, CT

DATE: 11/11/10  
 DRAWN BY: JAK  
 CHECKED BY: JAK  
 PROJECT NO.: S105RR-B  
 SHEET NO.: 1



1 8TH FLOOR REINFORCEMENT PLAN - SOUTH


**2. Load Distribution and Calculation**

**2a.**


The load distribution assumptions we made are as follows. The uniform tendons in those locations run plan north-south. The uniform tendons are supported by the banded tendons that run east-west. Therefore the uniform tendons carry the load from the slab to the banded tendons and the banded tendons carry the load to the columns. A point load was used to where the banded tendons at the high slab connect to the banded tendons on the low slab.

**2b.**


1. An area load (Roof Live & Snow) was applied on the lower slab as shown in with the yellow area:



2. The tributary area for the column at G1/GD on the plan left side of the column is shown by the red box. Since the tributary area overlaps the area load for the roof live and snow load, the load shown in blue was calculated and applied as the point load.



**SLAB REINFORCEMENT REQUIREMENT FOR STRENGTH**



**Column Reactions Plan\_Envelope**

**Harbor Point P4P5  
Level 5 - Pours 3 & 6**

07/29/22

08:17:11

\\VLC\_06\_Pour\_3\_6\_Podium\_newells.adm