



[illegible]


QTY	KEY	BOTANICAL NAME	COMMON NAME	SIZE	ROOT	REMARKS	PLANTING HT.	MATURE HT.
7	AR	ACER RUBRUM 'ARMSTRONG'	ARMSTRONG MAPLE	2-2 1/2" CAL.	B&B	COLUMNAR TREE	12-14' HT.	35-40' HT.
5	DH	BETULA NIGRA 'DURA HEAT'	DURA HEAT BIRCH	8-10' HT.	B&B	MULTISTEM TREE	8-9' HT.	20-28' HT.
6	GR	GINKGO 'PRINCETON SENTINEL'	PRINCETON SENTINEL GINKGO	2-2 1/2" CAL.	B&B	COLUMNAR	12-14' HT.	35-40' HT.
10	HL	GLEDITSIA TRIACANTHOS 'SHADEMASTER'	SHADEMASTER HONEY LOCUST	3-3 1/2" CAL.	B&B	SHADE TREE	12-14' HT.	45-50' HT.
1	QB	QUERCUS BICOLOR	SWAMP WHITE OAK	3-3 1/2" CAL.	B&B	SHADE TREE	12-14' HT.	50-60' HT.
6	OP	QUERCUS PALustris 'PACIFIC BRILLANCE'	PIN OAK	2 1/2-3" CAL.	B&B	SHADE TREE	12-14' HT.	50-60' HT.
4	10	ILEX OPACA	AMERICAN HOLY	5-6" HT.	B&B	EVERGREEN NATIVE	5-6" HT.	25-30' HT.
6	PA	PICEA ABIES	NORWAY SPRUCE	7-8" HT.	B&B	EVERGREEN	7-8" HT.	60-70' HT.
6	PA	THUJA GREEN GANT	GREEN GANT ARBORVITAE	5-6" HT.	B&B	EVERGREEN	5-6" HT.	30-35' HT.
46	CR	CLETHRA ALNIFOLIA 'RUBY SPICE'	RUBY SPICE CLETHRA	3-4' HT.	CONT.	FRAGRANT FLOWERS		
15	LS	HYPERICUM ERONOCOSMUM 'SUNBURST'	SUNBURST ST. JOHN'SWORT	18-24" HT.	CONT.	YELLOW FLOWERS		
29	IG	ILEX GLABRA 'SHAMROCK'	COMPACT INKBERY	2-3" HT.	CONT.	EVERGREEN		
8	IV1	ILEX VERUTICULARIA 'SOUTHERN GENTLEMAN'	SOUTHERN GENTLEMAN HOLLY	2-3" HT.	CONT.	NATIVE, MALE		
26	IV2	ILEX VERUTICULARIA 'WINTER RED'	WINTER RED WINTERBERRY	2-3" HT.	CONT.	RED BERRIES, NATIVE		
29	J5	JUNIPERUS CHINENSIS VAR. 'SARGENTI'	SARGENT JUMPER	2-3 SPN.	CONT.	EVERGREEN		
29	LP	SPRAEA 'LITTLE PRINCESS'	LITTLE PRINCESS SPREA	2-3" HT.	CONT.	WHITE FLOWERS		




NEW DECIDUOUS SMALL TREE




NEW EVERGREEN TREE



NEW SHRUB



NEW LIGHT POLE



NEW WALL MOUNTED LIGHT

4. PLANTING METHODS SHALL BE IN ACCORDANCE WITH THE "AMERICAN STANDARDS FOR NURSERY STOCK", LATEST EDITION, AS PUBLISHED BY THE AMERICAN NURSERY & LANDSCAPE ASSOCIATION.

5. THIS PLAN FOR PLANTING PURPOSES ONLY. SEE PLANS BY OTHERS FOR ADDITIONAL INFORMATION.

6. SPRAY NEW PLANTINGS IMMEDIATELY AFTER INSTALLATION WITH A WHITE-TAILED DEER REPELLENT AND CONTINUE AS NEEDED TO MAINTAIN PLANTS FREE OF SIGNIFICANT DEER BROWSING.

7. SEED LAWN AREAS WITH A HIGH QUALITY FESCUE AND SEED AREAS AT THE METHODS AND RATE RECOMMENDED BY THE MANUFACTURER.

REVISIONS	
1	2.8.23
2	2.27.23
3	3.6.23

PER CITY COMMENTS

PER CITY COMMENTS

PER REVISED SITE PLAN

ENVIRONMENTAL LANDSCAPE ARCHITECTURE

E L S

8 KNIGHT STREET, SUITE 203
NORWALK, CONNECTICUT 06851

Tel: (203) 855-7879 Fax: (203) 855-7836

info@elslcn.net www.elsslcn.net

ENVIRONMENTAL LAND SOLUTIONS, LLC

Landscape Architecture and Environmental Planning

23 BARRY PLACE
STAMFORD, CONNECTICUT


DATE: 12.14.22

SCALE: 1"=20'

DRAWING NO.: LP.1

DRAWING TITLE: LANDSCAPE PLAN


PROJECT: 23 BARRY PLACE
STAMFORD, CONNECTICUT

REVISIONS:		
3	3.6,23	PER CITY COMMENTS
2	2.27,23	PER CITY COMMENTS
1	2.8,23	PER REVISED SITE PLAN
<div>ENVIRONMENTAL LAND SOLUTIONS, LLC Landscape Architecture and Environmental Planning 8 KNIGHT STREET, SUITE 203 NORWALK, CONNECTICUT 06851 Tel: (203) 855-7879 Fax: (203) 855-7836 info@elslcn.net www.elslcn.net</div>		
<div>LANDSCAPE PLAN PROJECT: 23 BARRY PLACE STAMFORD, CONNECTICUT</div>		<div>SCALE: </div>
DATE: 12.14.22		SCALE: 1"=20'
DRAWING NO.: LP.1		

- LEGEND**
- PROPERTY LINE
 - EXISTING CONTOUR
 - PROPOSED CONTOUR
 - NEW / EX. LAWN AREA
 - EX. DECIDUOUS / EVERGREEN TREE TO REMAIN
 - EX. TREE TO BE REMOVED
 - NEW DECIDUOUS SHADE TREE
 - NEW DECIDUOUS SMALL TREE
 - NEW EVERGREEN TREE
 - NEW SHRUB
 - NEW LIGHT POLE
 - NEW WALL MOUNTED LIGHT


LANDSCAPE LIGHTING NOTES:

- SITE LIGHTING INFORMATION AND LIGHTING PLANS PREPARED BY ENVIRONMENTAL LAND SOLUTIONS, LLC ARE DESIGNED FOR GENERAL LANDSCAPE AESTHETIC PURPOSES ONLY. LIGHTING INFORMATION SHOWN ON THIS PLAN SHALL NOT BE USED FOR SECURITY OR SAFETY PURPOSES.
- CONDITIONS, SITE AND ARCHITECTURAL PLAN REVISIONS, USE OF EXISTING LIGHTING (IF ANY), NEW LIGHTING, AND CONSULTATIONS WITH LIGHTING CONSULTANT AND/OR MANUFACTURER.
- THIS PLAN ASSUMES THAT THE BUILDING WILL HAVE WALL MOUNTED FIXTURES (BY OTHERS) TO LIGHT EXTERIOR DOORS.
- INSTALL LIGHT FIXTURES AS RECOMMENDED BY THE MANUFACTURER.
- LIGHT POLES LOCATED WITHIN LANDSCAPE AND PEDESTRIAN AREAS SHALL BE ON A BASE FLUSH WITH GRADE LOCATED A MINIMUM OF 3' FROM THE EDGE OF VEHICLE PAVEMENT IF FEASIBLE.



- NOTES:**
1. LIGHT FIXTURE (LINC LITEPACK) BY HUBBELL OUTDOOR LIGHTING.
 2. LIGHT COLOR SHALL BE SIMILAR TO BUILDING COLOR.
 3. SEE ELECTRICAL PLANS FOR FINAL MOUNTING HEIGHT AND PLACEMENT.
 4. LIGHT FIXTURE TO BE 3000K AND HAVE AN ACRYLIC DIFFUSER.
- LIGHT POLE (TYP.)**
- SCALE: NOT TO SCALE

- WALL LIGHT (TYP.)**
- SCALE: NOT TO SCALE



REVISIONS:		BREAKING TITLE:
		LANDSCAPE PLAN
3	3.6.23	PER CITY COMMENTS
2	2.27.23	PER CITY COMMENTS
1	2.8.23	PER REVISED SITE PLAN

ENVIRONMENTAL LAND SOLUTIONS, LLC	SCALE:	DATE:
Landscope Architecture and Environmental Planning		12.14.22
8 KNIGHT STREET, SUITE 203	SCALE: 1"=20'	
NORWALK, CONNECTICUT 06851	DRAWING NO.:	
Tel: (203) 855-7879 Fax: (203) 855-7836		LP.2
info@elslinc.net www.elslinc.net		