MAYOR Caroline Simmons



ZONING BOARD
LAND USE BUREAU
888 WASHINGTON BOULEVARD
STAMFORD, CT 06904 -2152

DIRECTOR OF OPERATIONS

Matthew Quiñones

Land Use Bureau Chief Ralph Blessing

Principal Planner **Vineeta Mathur** (203) 977-4716 <u>vmathur@stamfordct.gov</u>

Associate Planner Lindsey Cohen (203) 977-4388 lcohen@stamfordct.gov



August 4, 2023

Ms. Theresa Dell, Chair, Planning Board Land Use Bureau, City of Stamford 888 Washington Blvd. Stamford, CT 06904 AUG 4 202

LANNING BOARD

RE: 223-35 -Rockrimmon Country Club Inc, 2949 Long Ridge Road, Stamford, CT – Special Permit and a General Development Plan- Applicant is proposing to create a new parking lot, 4 pickle ball courts, and modifying application 219-17 to include 0 Long Ridge Road as part of the Special Permit Use.

Dear Ms. Dell:

In accordance with Section C6-40-10 of the Charter of the City of Stamford, the above captioned Applications for a Special Permit and a General Development Plan are hereby referred to the Planning Board of the City of Stamford for its advisory report.

A public hearing has not yet been scheduled. Referral comments should be filed with the Zoning Board Office by *September 8, 2023*.

If you have any questions, please feel free to contact me at (203) 977-4716.

Sincerely,

Vineeta Mathur Principal Planner



July 27, 2021

City of Stamford Zoning Board c/o Ralph Blessing, Land Use Bureau Chief 888 Washington Boulevard Stamford, CT 06901

Re: 2949 Long Ridge Road & 0 Long Ridge Road (003-8745)

Special Permit & Site and Architectural Plan and/or requested uses applications

Dear Mr. Blessing,

As discussed, on behalf of Rockrimmon Country Club Inc. (the Applicant), enclosed please find applications and supportive materials for Special Permit and General Development Plan to create new parking lot, 4 pickle ball courts, and modifying approval 219-17 to include 0 Long Ridge Road as part of the Special Permit Use. Application details and design elements are described further in the attached Project Narrative and reflected in the enclosed plans.

In support of the applications, enclosed please find:

- 1. A check in the amount of \$1,460 for:
 - a. Special Permit Fee: \$460;
 - b. Public Hearing Fee: \$1,000
- 2. Special Permit Application;
- 3. GDP Application;
- 4. Approval 219-17
- 5. Project Narrative;
- 6. Drawing List;
- 7. General Property Description;
- 8. Zoning Data Chart;
- 9. Aerial Exhibit;
- 10. Existing Condition Surveys;
- 11. Engineering Plans;
- 12. Landscape Plans;
- 13. Drainage Report;
- 14. Letter of Authorization:

Please feel free to contact us with any questions or comments. We look forward to working with you and the Planning and Zoning Boards to help improve one of Stamford's longstanding social and recreational institutions.

Sincerely

Richard W. Redniss, FAICP

Enclosures

cc: Vineeta Mathur, AICP Principal Planner



July 27, 2023

City of Stamford Planning Board c/o Ralph Blessing, Land Use Bureau Chief 888 Washington Boulevard Stamford, CT 06901

Re: 2949 Long Ridge Road & 0 Long Ridge Road (003-8745)

Special Permit & Site and Architectural Plan and/or requested uses applications

Dear Mr. Blessing,

Please let this letter serve as our formal request for members of the consultant team to speak, should the Planning Board have any questions for the applicant at the forthcoming referral meeting on the proposed Special Permit and Final Site Plan applications. Please let us know if you have any questions or would like additional information.

Sincerely,

Richard W. Redniss, FAICP

Enclosures

CC: V. Mathur, Principal Planner



APPLICATION FOR SPECIAL PERMIT


Complete, notorize, and forward thirteen (13) hard copies and (1) electronic copy in PDF format to Clerk of the Zoning Board with a \$1,000.00 Public Hearing Fee and the required application filling fee (see Fee Schedule below), payable to the City of Stamford.

NOTE: Cost of required advertisements are payable by the Applicant and performance of required mailing to surrounding property owners is the sole responsibility of the applicant. **LAND RECORDS RECORDING FEE**: \$60.00 for First page - \$5.00 for each additional page)

Fee Schedule

7 00 001100010	
Special Permit 20,000 sq. ft. or less	\$460.00
Special Permit more than 20,000 sq. ft.	\$460.00 + \$30 per 1,000 sq. ft. or portion thereof in excess of 20,000 sq. ft

APPLICANT NAME (S): ROCKRIMMON COUNTRY CLUB INC
APPLICANT ADDRESS: <u>c/o Redniss & Mead - 22 First Street Stamford</u> , CT 06905
APPLICANT PHONE #: c/o 203-327-0500
IS APPLICANT AN OWNER OF PROPERTY IN THE CITY OF STAMFORD? Yes
LOCATION OF PROPERTY IN STAMFORD OWNED BY APPLICANT (S):
2949 Long Ridge Road & 0 Long Ridge Road (003-8745)
ADDRESS OF SUBJECT PROPERTY: 2949 Long Ridge Road & 0 Long Ridge Road (003-8745)
PRESENT ZONING DISTRICT: RA-2
TITLE OF SITE PLANS & ARCHITECTURAL PLANS: Please see attached Drawing List
REQUESTED SPECIAL PERMIT: (Attach written statement describing request)
Please see attached Project Narrative
LOCATION: (Give boundaries of land affected, distance from nearest intersecting streets, lot depths and Town Clerk's Block Number)
Please see attached General Property Description
NAME AND ADDRESS OF OWNERS OF ALL PROPERTY INVOLVED IN REQUEST: NAME & ADDRESS LOCATION
ROCKRIMMON COUNTRY CLUB INC 2949 Long Ridge Road &
2949 LONG RIDGE RD 0 Long Ridge Road (003-8745) STAMFORD CT 06903-1116 Stamford, CT 06903
STAMFORD, CT 06903-1116 Stamford, CT 06903 DOES ANY PORTION OF THE PREMISES AFFECTED BY THIS APPLICATION LIE WITHIN 500 FEET OF THE BORDER LINE WITH GREENWICH, DARIEN OR NEW CANAAN? Yes (If yes, notification must be sent to Town Clerk of neighboring community by registered mail within 7 days of receipt of application – PA 87-307).
DOES THE PROJECT RESULT IN THE CREATION OF 10 OR MORE UNITS OR 10,000 SF OR MORE IN FLOOR AREA OR DISTURBANCE OF 20,000 SF OR MORE IN LAND AREA, THROUGH NEW DEVELOPMENT, RECONSTRUCTION, ENLARGEMENT OR SUBSTANTIAL ALTERATIONS? No (If yes, then complete the Stamford Sustainability Scorecard per Section 15.F).





Zoning Board · Land Use Bureau Government Center · 888 Washington Boulevard · Stamford, CT 06904-2152 Phone: 203.977.4719 · Fax: 203.977.4100

DATED AT STAMFORD, CONNECTICUT, THIS DAY OF SIGNED: NOTE: Application cannot be scheduled for Public Hearing until 35 days have elapsed from the date of referral to the Stamford Planning Board. If applicant wishes to withdraw application, please notify the Zoning Board at least three (3) days prior to Public Hearing so that the Board may have sufficient time to publicize the withdrawal. STATE OF CONNECTICUT 20 23 **COUNTY OF FAIRFIELD** signer of the foregoing application, who made oath to Personally appeared the truth of the contents thereof, before me. DAVID PINTO Notary Public, State of Connecticut Notary Public - Commissioner of the Superior Court My Commission Expires Mar 31, 2026 **FOR OFFICE USE ONLY** APPL. #: _223-35 Received in the office of the Zoning Board: Date:

Revised 09/02/2020

By:



APPLICATION FOR APPROVAL OF SITE & ARCHITECTURAL PLANS AND / OR REQUESTED USES

Complete, notorize, and forward thirteen (13) hard copies and one (1) electronic copy in PDF format to Clerk of the Zoning Board with a \$1,000.00 Public Hearing Fee and the required application filling fee (see Fee Schedule below), payable to the City of Stamford.

NOTE: Cost of required Public Hearing advertisements are payable by the Applicant and performance of required mailing to surrounding property owners is the sole responsibility of the applicant. **LAND RECORDS RECORDING FEE**: \$60.00 for First page - \$5.00 for each additional page)

Fee Schedule -WITHOUT GDP

Site Plans 20,000 sq. ft. or less of building area application feewithout GDP	\$460.00
Site Plans more than 20,000 sq. ft. of building area-application Fee –without GDP	\$460.00 + \$30 per 1,000 sq. ft. or portion thereof in excess of 20,000 sq. ft.

Fee Schedule -WITH GDP

Site Plans 20,000 sq. ft. or less of building area application fee –with GDP.	\$260.00
Site Plans more than 20,000 sq. ft. of building area-application Fee –with GDP.	\$260.00 + \$10 per 1,000 sq. ft. or portion thereof in excess of 20,000 sq. ft.

APPLICANT NAME (S): ROCKRIMMON COUNTRY CLUB INC
APPLICANT ADDRESS: c/o Redniss & Mead - 22 First Street Stamford, CT 06905
APPLICANT PHONE #: c/o 203-327-0500
IS APPLICANT AN OWNER OF PROPERTY IN THE CITY OF STAMFORD? Yes
LOCATION OF PROPERTY IN STAMFORD OWNED BY APPLICANT (S):
2949 Long Ridge Road & 0 Long Ridge Road (003-8745)
ADDRESS OF SUBJECT PROPERTY: 2949 Long Ridge Road & 0 Long Ridge Road (003-8745
PRESENT ZONING DISTRICT: RA-2
TITLE OF SITE PLANS & ARCHITECTURAL PLANS: Please see attached Drawing List
REQUESTED USE: Please see attached Project Narrative
LOCATION: (Give boundaries of land affected, distance from nearest intersecting streets, lot depths and Town Clerk's Block Number)
Please see attached General Property Description
NAME AND ADDRESS OF OWNERS OF ALL PROPERTY INVOLVED IN REQUEST: NAME & ADDRESS LOCATION
ROCKRIMMON COUNTRY CLUB INC 2949 Long Ridge Road &
2949 LONG RIDGE RD 0 Long Ridge Road (003-8745)
STAMFORD, CT 06903-1116 Stamford, CT 06903
DOES ANY PORTION OF THE PREMISES AFFECTED BY THIS APPLICATION LIE WITHIN 500 FEET OF THE BORDER LINE WITH GREENWICH, DARIEN OR NEW CANAAN? Yes (If yes, notification must be sent to Town Clerk of neighboring community by registered mail within 7 days of receipt of application – PA 87-307).
DOES THE PROJECT RESULT IN THE CREATION OF 10 OR MORE UNITS OR 10,000 SF OR MORE IN FLOOR AREA OR DISTURBANCE OF 20,000 SF OR MORE IN LAND AREA, THROUGH NEW DEVELOPMENT, RECONSTRUCTION, ENLARGEMENT OR SUBSTANTIAL ALTERATIONS?NO(If yes, then complete the Stamford Sustainability Scorecard per Section 15.F).





DATED AT STAMFORD, CONNECTICUT, THIS 25 NOTE: The application cannot be scheduled for public hearing until 35 days have elapsed from the date of referral to the Stamford Planning Board. If applicant wishes to withdraw the application, this must be done in writing, and be received by the Zoning Board at least three (3) working days prior to public hearing in order to provide sufficient time to publicize the withdrawal. Applications withdrawn less than three (3) days prior to a schedule hearing date will not be rescheduled within 90 days. STATE OF CONNECTICUT ss STAMFORD **COUNTY OF FAIRFIELD** signer of the foregoing application, who made oath to Personally appeared he truth of the bolitents lifereof, before me. Notary Public, State of Connecticut My Commission Expires Mar 31, 2026 Notary Public - Commissioner of the Superior Court **FOR OFFICE USE ONLY** 223-35 Received in the office of the Zoning Board: Date:

Revised 9/02/20

By: _

INSTR # 2019013728

VOL 12209 PG 116

RECORDED 09/04/2019 03:10:23 PM
LYDA RUIJTER
CITY & TOWN CLERK STAMFORD CT

BLOCK 403

Block#:403

ZONING BOARD CERTIFICATE

I, David Stein, Chairman of the ZONING BOARD at the CITY OF STAMFORD in compliance with Special Act. No 619 of the 1953 General Assembly hereby certify that on July 29, 2019, a Public Hearing was held by the ZONING BOARD on the application of:

Application 219-17 – Rockrimmon Country Club, 2949 Long Ridge Road, Special Exception and a General Development Plan,

Requesting approval of a Special Exception and General Development Plan in connection with the proposed renovations and minor additions to the main clubhouse and pool area, resurface existing tennis courts, addition of a tennis court, realignment of a portion of the parking area and renovation and realignment of portions of the golf course include the 18th Green, cart path and the practice range. The site borders and extends into Pound Ridge, NY (115 Acres ±) and consists of 32± acres in Stamford and further described as follows:

Area:

Stamford, CT: 32 Acres ± 115 Acres ± 147 Acres ± 147 Acres ±

Description:

All that area of land commonly referred to as 2949 Long Ridge Road, Stamford, CT (Assessor Card #001-9366) and 301 Long Ridge Road, Pound Ridge, NY (9316-2) NY. Said land is located on the southeasterly corner of the intersection of Long Ridge Road and Lower Shad Road, and generally bounded as follows:

Beginning at a point on the intersection of the southerly side of Lower Shad Road and the easterly side of Long Ridge Road, said land is generally bounded as follows:

Northerly: $4,270' \pm by$ the southerly side of Lower Shad Road;

Easterly: $1,850' \pm \text{by land n/f of Rockcorp LLC}$;

Southerly: 6,340' ± by lands n/f of Rockcorp LLC, Rock Rimmon Country Club,

Haroche Gilbert 2008 REV TR and Haroche Charlene 2008 REV TR, Luders John M 80.56 and Luders Carol 9.72%, Tansil Douglas T and Dhuanne S, Rehfield Family Trust; the northerly side of Rock Rimmon Road; lands n/f of Riordan Robert E and Riordan Lauren F, Holm Jeffrey H and Holm Elizabeth W, Greenfield & Company Land TR, Rockrimmon Country Club, INC, and Kim Dale and Gascho Jennifer; each in part;

Westerly: $1,470' \pm by$ the easterly side of Long Ridge Road.

And the land affected is owned by and located on the following street:

NAME STREET

Rockrimmon Country Club INC 2949 Long Ridge Road Stamford, CT 06903-1116

2949 Long Ridge Road Stamford, CT 06903-1116

And that the following is a statement of its findings: APPROVED AS MODIFIED on July 29, 2019, by passage of the following motion:

WHEREAS: the Zoning Board has reviewed applications for Special Exception and General Development Plan approval related to proposed renovations and minor additions to the main clubhouse and pool area, resurfacing of existing tennis courts, addition of a tennis court, realignment of a portion of the parking area and renovation and realignment of portions of the golf course include the 18th Green, cart path and the practice range;

WHEREAS: the Zoning Board conducted a duly called public hearing on July 29, 2019 and has considered the submitted comments of other interested City agencies, officials and the general public; and

WHEREAS: the approved Special Exception and General Development Plan applications are more particularly described in the following plans:

Sheet	Titled	Prepared by	Date
-	Plot Plan	Edward J. Frattaroli, Inc.	6/19/2019
-	Map Showing Property of	Edward J. Frattaroli, Inc.	6/4/1973
	Rockrimmon Country Club		
GDP	Rockrimmon Country Club	Wesley Stout Associates	2019
1	Existing Conditions Survey	Edward J. Frattaroli, Inc.	6/19/2019
2	Existing Conditions Plan	Wesley Stout Associates	2019
3	Existing Conditions Aerial	Wesley Stout Associates	2019
4	Proposed Site Plan	Wesley Stout Associates	7/29/2019
5	Dining Terrace	Wesley Stout Associates	2019
6	Main Floor Plan	Wesley Stout Associates	2019
7	Grill Room – Exterior	Wesley Stout Associates	2019
8	Grill Room – Interior	Wesley Stout Associates	2019
9	Pool Area	Wesley Stout Associates	2019
10	Lower Level Plan	Wesley Stout Associates	2019
11	Tennis Courts	Wesley Stout Associates	2019
12	Tennis Courts	Wesley Stout Associates	2019
13	Driving Range 18th Green Complex	Wesley Stout Associates	2019

and such related materials and exhibits constituting the application file as may be amended to be consistent with representations made during the public hearing on July 29, 2019, and conditions contained herein. Together all of these documents are referred to hereinafter as the Building and Site Plans.

WHEREAS, the Zoning Board makes the following special findings:

- The application is consistent with the purposes, standards and goals of the Master Plan, RA-2 zoning district and the standards and limitations within Sections 7.2, 19.3, Definition 27, as amended, as well as all other applicable requirements of the Stamford Zoning Regulations:
- The "Country Club or Golf Club" use is a permitted, special exception use in the RA-2 zoning district and the use and overall site improvements are in accord with the public convenience and welfare after taking into consideration all of the standards and conditions in Section 19.3.2 of the Stamford Zoning Regulations;
- The proposed parking standard provides an adequate number of parking spaces for the use which is consistent with similar uses in the City; and
- The approval of a General Development Plan will facilitate thoughtful planning and development
 on these large recreational sites so as not to be injurious to the neighborhood or impair future
 development.

NOW THEREFORE BE IT RESOLVED that the Zoning Board UNANIMOUSLY APPROVED AS MODIFIED Application 219-17, subject to the following conditions:

Site Specific Conditions

- General Development Plan (GDP) Approval is granted for new site and building additions
 with associated parking, driveways, landscaping, and related site improvements, as
 generally depicted on plan(s) submitted by the applicant: 1) Rockrimmon Country Club
 2019 General Development Plan (sheets 1-14) as updated per sheet 4 "Proposed Site Plan"
 dated July 29, 2019. Such approval and related conditions herein shall supersede those of
 prior ZBA approvals.
- 2. The General Development Plan (GDP) is a conceptual master plan showing the general location, size and use of new structures, facilities and site improvements, but does not entitle the property to final approval of any specific structure, facility or improvement. Final zoning approval shall be issued by the Land Use Bureau Chief after the proposed improvements have received necessary permits and endorsements from the EPB, Engineering Bureau, WPCA, Health Department, Traffic Transportation and Parking Bureau and Fire Department, as applicable, and any other agency that has regulatory oversight of

the proposed improvements, whose review and analysis shall be independent from this Zoning approval.

- 3. Plans submitted for Building Permit shall be generally consistent with the location, scale, organization, and setback of all proposed buildings, parking and drives, as shown on the approved General Development Plan. Minor changes to the size and location of proposed improvements, within the Area(s) of Development as depicted on the approved GDP, may be permitted by the Land Use Bureau Chief or designee, or administratively by the Zoning Board, provided that the approved floor area for any proposed building or addition is not increased by more than 10%, the approved total floor area continues to conform to applicable Zoning standards and limitations, and that all other conditions of this approval are met. Changes to the GDP deemed by the Land Use Bureau chief to not be minor may require amendment of the GDP by the Zoning Board.
- 4. Permitting, bonding, and construction of improvements may be submitted and processed separately for each phase/area of work.
- 5. Exterior lighting of buildings, parking lots, and driveways shall be designed and landscaped to mitigate light spillage onto neighboring properties.
- 6. No lighting shall be installed on the existing and/or proposed tennis courts.
- 7. Between March 1 and October 31 there shall be no more than thirty-three (33) employees living on the property. At all other times there shall be no more than ten (10) employees living on the property, provided that an additional five (5) employees may be added (not to exceed fifteen (15) employees) pursuant to administrative approval by Zoning Board staff.
- 8. There shall be a landscape buffer of evergreen trees, located in the area between the parking area and the property known as 2891 Long ridge Road. Said landscape buffer shall be planted and perpetually maintained so as to minimize any view of the pool house building addition from the residence located at 2891 Long Ridge Road.
- 9. This GDP approval shall expire after ten (10) years from the effective date, subject to not more than two (2) extensions of three (3) years each, with good cause shown, and pursuant to the prior review and approval of the Zoning Board.

Standard Conditions

10. Prior to the issuance of a Building Permit, the Applicant shall submit a Construction Staging and Management Plan to ensure safe, adequate and convenient vehicular traffic circulation and operations, pedestrian circulation and protection of environmental quality through the

mitigation of noise, dust, fumes and debris subject to final approval of the Land Use Bureau Chief or his designee. Such Construction Management Plan shall address, but not be limited to, reasonable restrictions on times when deliveries can be made to the job site, measures to control dust, staging areas for materials and construction worker parking as well as temporary measures requiring the timely removal of construction debris and/or litter from the jobsite.

- 11. Signage plans shall be subject to approval by Zoning Board staff.
- 12. Prior to the issuance of a Building Permit, sewer and storm drainage plans shall be submitted and subject to final review of design specification and construction by the Engineering Bureau.
- 13. Applicable property boundaries and work areas shall be staked in the field by a Connecticut surveyor prior to the start of any site activity.
- 14. Temporary erosion/construction controls shall be installed and approved by EPB Staff prior to the start of any site disturbance.
- 15. Prior to issuance of a Building Permit, Applicant shall submit a performance bond, certified check or other acceptable form of surety to secure the timely and proper performance of sediment and erosion controls, drainage, landscaping, professional supervision, and certifications. A detailed estimate of these costs shall be supplied to EPB Staff for approval prior to the submission of the performance surety. The performance surety shall be submitted to EPB Staff prior to the start of any site activity and issuance of a building permit.
- 16. Prior to the release of surety, transfer of title and issuance of a signature authorizing the issuance of a Certificate of Occupancy, the Applicant shall execute and file a standard, City of Stamford "Drainage Maintenance Agreement" on the Stamford Land Records to ensure the full and proper function of all installed drainage facilities.
- 17. Prior to the release of surety, transfer of title and issuance of a signature authorizing the granting of a Certificate of Occupancy, the Applicant shall execute and file a standard, City of Stamford "Landscape Maintenance Agreement" on the Stamford Land Records to ensure the success of the planted features.
- 18. All final grading, drainage, utilities, walls, final stabilization measures, and other engineered elements shall be completed under the supervision of a Connecticut registered professional engineer and land surveyor with an improvement location survey (surveyor) and written certifications (engineer) submitted to EPB Staff prior to the release of surety and signature authorizing the issuance of certificate of occupancy/completion.

- 19. No significant mechanical equipment shall be installed within view of any public street without prior approval of the Zoning Board staff.
- 20. A Street Opening Permit shall be required for any and all work within any City of Stamford street right of way.
- 21. The Applicant shall maintain all facades facing and visible from public Right of Way in first class condition.
- 22. Applicants shall make best efforts to keep the property in good condition up until and during the construction process. Existing lawn areas shall be mowed and maintained, and construction debris shall be kept to a reasonable minimum.

Effective date of this decision: August 14, 2019

DAVID STEIN, CHAIRMAN

Dated at the City of Stamford, CT, this 4th day of September 2019

Project Narrative Rockrimmon Country Club 2949 Long Ridge Road & 0 Long Ridge Road (003-8745) Special Permit & General Development Plan July 27, 2023

1. Club History and Mission

The idea to create Rockrimmon Country Club (The club) began at a dinner party in 1947 by a few "visionary" Stamford residents who wanted to build one of the finest golf courses in New England. After purchasing "Ayers Farm" a 218-acre parcel in Connecticut and New York (now reduced to $147\pm$ acres), the Clubs first 9 holes were completed in 1949. After operating out of the original farmhouse, today's green superintendent's residence, a small clubhouse was built in 1950. This structure contained men's and women's locker rooms, a lounge, dining room and kitchen. In 1955, with land acquired from the adjoining estate, the second nine holes were finished and the 18-hole layout, as it is played today, was complete and open for play. Lake Calmon, adjacent to the 5th fairway, was also built to supply the course with needed water.

As the club flourished, and its membership grew, demand for additional space and amenities increased. In 1961 the present clubhouse was constructed, and the former clubhouse building became pool locker rooms and staff housing. A major renovation of the clubhouse was completed in 1996 resulting in a larger and more open dining room and significant facilities upgrades. Subsequent projects have included newly renovated locker rooms, expanded patio space and updated decor. The club is host to many WGA, MGA and USGA competitions.

The success of Rockrimmon has always been rooted in its ability to change with the times and to react to the needs and desires of its members. Today, Rockrimmon events are more likely to include family barbecues than formal dinner dances, but it remains a casually elegant "Club in the Country".

Rockrimmon is defined by a relaxed and family friendly atmosphere where no activity is ever too far away. With continuously upgraded amenities and spectacular grounds, the Club provides a diverse and vibrant community for golf, tennis, swimming, and social engagement.

2. Existing Conditions

The Club property consists of 147± acres of land, of which 32± acres are located in Stamford in the RA-2 Zone with its main frontage and entrance on Long Ridge Road. The club has also owned and maintained for the last 25 years a vacant 1-acre parcel that is contiguous to its existing parking and tennis areas.

Some major features of The Club include:

- 18-hole Golf Course (NY/CT)
- Driving Range (CT)



- Club House (CT)
 - o Dining Rooms
 - o Lounge
 - Locker Rooms
 - Pro Shop
 - o Admin Offices
- Swimming Pools and Deck (CT)
- Tennis Courts (CT)
- Play Area and Storage Sheds (CT)
- Turn House (CT)
- Groundskeeper's Residence (NY)
- Storage Barn (NY)
- Associated parking areas (NY/CT)

3. Recent Approvals/Improvements

In 2019 Rockrimmon submitted a GDP application and plans to improve the property, including:

- renovation and expansion of the grill room and patio
- renovation and expansion of the lobby
- renovations for the Kids Camp area
- resurfacing and addition of new tennis courts and shade pergola
- realigning of cart path and access between the clubhouse and greens
- modification of the 18th green and practice tee area

All proposed improvements, except for the green/practice tee changes, have been completed.

4. Proposed Changes

Since the 2019 approvals, the club's membership has grown from 269 to 303. This is a result of their successful efforts to maintain and enhance their member experience.

To continue that effort, and to accommodate their membership growth, the club is proposing to expand their parking and recreational facilities to the contiguous 1-acre parcel. Improvements will include a new parking area with a net addition of 52 spaces, 4 pickleball courts, and a small open deck adjacent to the courts. ¹

The pickleball courts will be located along the boundary of the main parcel and adjacent to existing tennis areas with new proposed walkway connections. The new parking area will be accessed from the existing lot/driveway and maintain a minimum of 20' from adjacent properties. In addition to the new spaces, the applicant will be converting 6 existing spaces to accommodate EV charging stations.



¹ If approved, the 1-acre parcel would be consolidated into the main parcel, thereby removing any interior lot lines.

A robust planting plan consisting of both evergreen and deciduous trees, various shrubs, and other ground cover will provide an ample buffer between neighboring properties.

The proposed improvements will further the Rockrimmon Country Club (Applicant) longstanding goals of:

- Being Stamford's premier Golf and Country Club;
- Responding to the evolving needs of the membership community
- Remaining an attractive opportunity for recreation and social engagement for Stamford residents
- Enhancing both member and visitor experience (safety, parking, circulation, wayfinding, and amenities);

5. Action Items

To facilitate the proposed changes, the applicant has filed the following applications and requests:

- A. Special Permit Pursuant to Appendix A, Table 1, item 13 "Clubs Country, Golf" to extend the existing use to include the 1-acre parcel.
- B. General Development Plan Pursuant to the process outlined in Section 5.E (Use Regulations) for "Country Clubs or Golf Clubs" the applicant is seeking to amend the existing GDP to include the 1-acre parcel and proposed improvements.

6. Statement of Findings

The Applicant submits that each and every one of the applicable criteria contained in the Stamford Zoning Regulations Article V, Section 19.C.2 "Standards and Conditions" are met for the following specific reasons:

- a. Special Permit may be granted by the reviewing board upon a finding that the proposed use or structure or the proposed extension or alteration of an existing use or structure is in accord with the public convenience and welfare after taking into account, where appropriate:
- (1) The location and nature of the proposed site including its size and configuration, the proposed size, scale and arrangement of structures, drives and parking areas and the parking of existing dwellings and other structures.

The Club is conveniently located on Long Ridge Road, a State right-of-way. The site occupies roughly 33 acres in Stamford and 115 acres in Pound Ridge. The existing size, scale and arrangement of structures, drives and parking areas remain largely unchanged. All vehicular access will remain at their existing location(s) with no new curb cuts proposed.



(2) The nature and intensity of the proposed use in relation to its site and the surrounding area. Operations in connection with Special Permit uses shall not be injurious to the neighborhood shall be in harmony with the general purpose and intended regulations and shall not be more objectionable to nearby properties by reason of noise, fumes, vibrations, artificial lighting and other potential disturbances to the health, safety or peaceful enjoyment of the property and the public necessity demands.

The site utilizes only a small fraction of the permitted floor area, building coverage and ground coverage. All proposed improvements are for the convenience and/or recreation of the club's existing members, and are sufficiently screened and/or distanced from adjacent properties.

(3) The resulting traffic patterns, the adequacy of existing streets to accommodate the traffic associated with the proposed use, the adequacy of proposed off-street parking and loading, and the extent to which proposed driveways may cause a safety hazard, or traffic nuisance.

All of the improvements are qualitative, with no impact on associated traffic. Vehicular circulation will remain generally unchanged while onsite parking capacity is being improved.

(4) The nature of the surrounding area and the extent to which the proposed use and feature might impair its present and future development.

The Club is an asset to the surrounding area and greater Stamford community. Its continued success serves as not only a recreational and social community but as a guarantee that over 100 acres of land in two states will remain, largely, undeveloped.

(5) The Master Plan to the City of Stamford and all statements are the intent of these regulations.

The Stamford portion of the site lies in Master Plan Category 1 (Residential – Very Low Density Single-Family) with a Category 15 (Open Space/Conservation Overlay) designation and meets the stated goals in that it provides a "compatible use" (e.g. clubs) permitted by Special Permit that is "in general harmony with and supportive of very low-density single-family neighborhoods". The site also maintains and protects acres of land reserved for "open spaces for active and passive use". The proposed improvements comply with all applicable standards of the Zoning Regulations.





Drawing List Special Permit & Site and Architectural Plan and/or requested uses applications 2949 Long Ridge Road & 0 Long Ridge Road (003-8745) July 27, 2023

Sheet #	Title/Description	Prepared by	Date
<u>Civil</u>			
	Improvement Location Survey "As-Built" Plan	Edward J. Frattaroli, Inc.	5/30/2023
	Improvement Location Survey "As-Built" Plan	Edward J. Frattaroli, Inc.	5/30/2023
	Plot Plan	Edward J. Frattaroli, Inc.	6/19/2019
	Existing Conditions Plan	Edward J. Frattaroli, Inc.	10/20/2022
SE-1	Site Development Plan	Redniss & Mead	7/12/2023
SE-2	Site Grading Plan	Redniss & Mead	7/12/2023
SE-3	Drainage & Utility Plan	Redniss & Mead	7/12/2023
SE-4	Sediment & Erosion Control Plan	Redniss & Mead	7/12/2023
SE-5	Details	Redniss & Mead	7/12/2023
SE-6	Details & Soil Data	Redniss & Mead	7/12/2023
Landscape			
SP-1.0	Landscape Layout Overall Plan	Wesley Stout Associates	7/24/2023
SP-2.0	Site Lighting and Landscape Details	Wesley Stout Associates	7/24/2023
SL-1	Photometric Calculation	Illuminate	7/24/2023

General Property Description 2949 Long Ridge Road & 0 Long Ridge Road (003-8745) Special Permit & Site and Architectural Plan and/or requested uses applications July 27, 2023

Block #: 403

Area: $33 \text{ Acres } \pm$

Description:

All that area of land commonly referred to as 2949 Long Ridge Road (Assessor Card #001-9366) and 0 Long Ridge Road (Assessor Card #003-8745). Said land is located on the easterly side of Long Ridge Road, and generally bounded as follows:

Beginning at the intersection of the easterly side of Long Ridge Road and the northwesterly side of land n/f of Dale Kim et al, said land is generally bounded as follows:

Westerly: $115' \pm \text{by the westerly side of Long Ridge Road}$;

Northerly: $1,850' \pm \text{by land n/f of Rock Rimmon Country Club};$

Easterly: 1,787' ± by lands n/f of Gilbert Haroche et ux, Margaret M. Ludders et

al, Doudlas T. Tansill et al, and allison Rowe, each in part;

Southerly: $1,595' \pm \text{by the northerly side of Rockrimmon Road, land n/f of simon J}$

mendez, John L. DeForest, Greenfield & Company Land Tr, and Minh

Nguyen, each in part.

Westerly: 1,162'± by the easterly side of Long Ridge Road, land n/f of Tessitore

Vanessa and Dale Kim et al each in part.

Rock Rimmon Country Club

2949 Long Ridge Road & 0 Long Ridge Road (003-8745)

Zoning Data Chart (1)


	Req/Allowed	Approved/	Existing	Propo	sed	Notes
Zoning District	RA-2					
						§19 requires 2x min acreage of applicable RA2 zone.
Min Lot Area	4 acres	1,406,927	32.30	1,450,574	33.30	Proposed assumes consolidation of parcels.
Min Frontage	200'	425'	±	450'	±	Long Ridge Road and Rockrimmon Road
Max Floor Area Ratio	0.10	36,908	0.03	36,908	0.03	Ratio slightly reduced.
Max Building Coverage	10%	31,500	2.2%	33,100	2.3%	Proposed includes relocated sheds and new deck (+1,600sf).
Max Ground Coverage	25%	167,500	11.9%	194,000	13.4%	Proposed includes new parking, courts, deck, walks (+26,500sf).
Max Building Stories	3	2	2		ange	Appendix B, Table III
Max Building Height	35'	TBD		No Change		Appendix B, Table III
Min Building Setbacks						
Front	60'	600'	+	No Cha	ange	Measured from clubhouse building to Long Ridge Road
Side	35'	135	135'		ange	Measured from clubhouse building to nearest property line (west)
Rear	n/a	n/a	n/a			No rear yard. Multiple site frontages.
Min Landscape Buffers						
Front	30'	30'±	30'±		ange	Measured to parking along NY border
Side	10'	0'	0'		ange	Existing nonconformity to remain. All new areas 16'+.
Rear	n/a	n/a		n/a		No rear yard. Multiple site frontages.
Min. Parking	176 ⁽²⁾	191 ((3)	243 ⁽	4)	See Footnotes below


Footnotes


- 1. All figures are based on land located in Stamford unless otherwise noted.
- 2. Conservative requirement based on 303 memberships and 100 active employees. No credit taken for employees on separate shifts.
- 3. Striped spaces. Includes employee parking lot partially located in NY portion of the property, but excludes all parking associated with groundskeeper residence, maintenance areas, and other paved areas.
- 4. Net addition of 52 spaces.





























_ CENTER OF CDS STRUCTURE, SCREEN CYLINDER AND INLET AND SUMP OPENING TOP SLAB ACCESS - (SEE FRAME AND COVER PVC HYDRAULIC SHEAR 60" I.D. MANHOLE STRUCTURE CONTRACTOR TO GROUT **CWNTECH** TO FINISHED GRADE RINGS/RISERS SOLUTIONS... FIBERGLASS SEPARATION CYLINDER AND INLET INLET PIPE FRAME AND COVER (MULTIPLE INLET PIPES MAY -(DIAMETER VARIES) BE ACCOMMODATED) N.T.S. GENERAL NOTES

1. CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE. POOL ELEV. 2. DIMENSIONS MARKED WITH () ARE REFERENCE DIMENSIONS. ACTUAL DIMENSIONS MAY VARY. OIL BAFFLE SKIRT — 3. FOR FABRICATION DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHTS, PLEASE CONTACT YOUR CONTECH CONSTRUCTION PRODUCTS REPRESENTATIVE. www.contech-cpi.com 4. CDS WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. 5. STRUCTURE SHALL MEET AASHTO HS20 AND CASTINGS SHALL MEET AASHTO M306 LOAD RATING, ASSUMING GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. 6. PVC HYDRAULIC SHEAR PLATE IS PLACED ON SHELF AT BOTTOM OF SCREEN CYLINDER. REMOVE AND REPLACE AS NECESSARY DURING MAINTENANCE CLEANING. SEPARATION SCREEN INSTALLATION NOTES

1. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED PVC HYDRAULIC SHEAR 2. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CDS MANHOLE STRUCTURE (LIFTING CLUTCHES PROVIDED). 3. CONTRACTOR TO ADD JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS, AND ASSEMBLE STRUCTURE. 4. CONTRACTOR TO PROVIDE, INSTALL, AND GROUT PIPES. MATCH PIPE INVERTS WITH ELEVATIONS SHOWN. 5. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS STORAGE SUMP SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED. **ELEVATION A-A** CDS2020-5-C INLINE CDS **CD2** STANDARD DETAIL THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF THE FOLLOWING U.S. PATENTS: 5,788,846; 6,641,725; 6,511,585; 6,561,78 RELATED FOREIGN PATENTS, OR OTHER PATENTS PENDING. (FINAL SIZING PRIOR TO THE BUILDING PERMIT) **OIL GRIT SEPARATOR (OGS#I)**

TEST PIT DATA

	Subsurface Soil Inves	tigation	
	Soil Profile		
Test Pit #: 1		Date: 02/24/203	
Inspector: BDH		Sanitarian: N/A	
Ledge at: N/A		Mottling at: 42"	
Water at: N/A		Roots at: 33"	
Depth: 87"	Soil Description		
0"-11"	Topsoil/Organics		
11"-38"	Orange Brown Silty Loam		
38"-87"	Tan Sand and Gravel		

Subsurface Soil Investigation Soil Profile

Soil Description

Topsoil/Organics

Orange Brown Silty Loam

Test Pit #: 2

Inspector: BDH

Ledge at: N/A

Water at: 96"

Depth: 106'

0"-12"

12"-26"

26"-106"

gation	
Date: 02/24/203	Test
Sanitarian: N/A	Inspe
Mottling at: N/A	Ledg
Roots at: 12"	Wate
	ĺ

	Subsurface Soil Investig	ation
	Soil Profile	
est Pit #: 3		Date: 02/24/203
nspector: BDH		Sanitarian: N/A
edge at: N/A		Mottling at: N/A
Vaterat: 70"		Roots at: 14"
Depth: 96"	Soil Description	
0''-14"	Topsoil/Organics	
14"-32"	Orange Brown Silty Loam	
32"-96"	Tan Sand and Gravel	

Tan Sand and Gravel (Mod. Compacted)

	Subsurface Soil Inve	stigation	
	Soil Profile		
Test Pit #: 4		Date: 02/24/203	
Inspector: BDH		Sanitarian: N/A	
Ledge at: N/A		Mottling at: 20"	
Water at: 40"		Roots at: N/A	
Depth: 72"	Soil Description		
0''-12"	Topsoil/Organics		
12"-36"	Orange Brown Silty Loam		
36"-72"	Tan Sand and Gravel		

15

	Subsurface Soil Investigation	
	Soil Profile	
Test Pit #: 5	Date: 0	02/24/203
Inspector: BDH	Sanitar	rian: N/A
Ledge at: N/A	Mottlin	ng at: 26"
Water at: 52"	Roots	at: 22"
Depth: 70"	Soil Description	
0''-10''	Topsoil/Organics	
10"-26"	Orange Brown Silty Loam	
26"-35"	Mottled Sand and Gravel	
26"-35"	Compacted Sand and Gravel	

	Subsurface Soil Investigation	
	Soil Profile	
Test Pit #: 6	Date: 02/24/203	
Inspector: BDH	Sanitarian: N/A	
Ledge at: N/A	Mottling at: N/A	
Water at: N/A	Roots at: 16"	
Depth: 93"	Soil Description	
0''-16''	Topsoil/Organics	
16"-36"	Orange Brown Silty Loam	
36"-93"	Mottled Sand and Gravel with Some Cobbles	

HC TEST RESULTS

HC#	Pre-Soak Date:	1 7/5/2023		HC#	Pre-Soak Date:	7/5/2022		HC#	Pre-Soak Date:	3 7/5/2023		PT#	Pre-Soak Date:	4 7/5/2023	
	Pre-Soak Time:	9:55 AM			Pre-Soak Time:				Pre-Soak Time:				Pre-Soak Time:	8:38 AM	
	Test Date:	7/5/2023			Test Date:				Test Date:				Test Date:	7/5/2023	
	Hole Depth (in.):	30"			Hole Depth (in.):	30"			Hole Depth (in.):	36"			Hole Depth (in.):	39"	
	Reading	Time	Drop		Reading	Time	Drop		Reading	Time	Drop		Reading	Time	Drop
FILL	2	11:55 AM	Χ	FILL	2	12:10 PM	Χ	FILL	2	10:50 AM	Х	FILL	1 14/16	10:38 AM	Χ
	21 4/16	12:10 PM	19 4/16		18 7/16	12:25 PM	16 7/16		23 2/16	11:05 AM	21 2/16		27 8/16	10:53 AM	25 10/1
	25 12/16	12:25 PM	23 12/16		23 13/16	12:40 PM	21 13/16		26 7/16	11:20 AM	24 7/16		31 7/16	11:08 AM	29 9/1
	28 12/16	12:40 PM	26 12/16		27	12:55 PM	25		29 8/16	11:35 AM	27 8/16		35 2/16	11:23 AM	33 4/16
	30	12:55 PM	28		29	1:10 PM	27		29 15/16	11:50 AM	27 15/16		36	11:38 AM	34 2/16
FILL	1 15/16	12:55 PM	Χ	FILL	2 2/16	1:10 PM	Χ	FILL	2 1/16	11:50 AM	Х	FILL	2 1/16	11:38 AM	Х
	18 6/16	1:10 PM	16 7/16		17 6/16	1:25 PM	15 4/16		22 11/16	12:05 PM	20 10/16		25 11/16	11:53 AM	23 10/1
	23 2/16	1:25 PM	21 3/16		23	1:40 PM	20 14/16		25 13/16	12:20 PM	23 12/16		30 4/16	12:08 PM	28 3/16
	27	1:40 PM	25 1/16		26 7/16	1:55 PM	24 5/16		28 13/16	12:35 PM	26 12/16		33 8/16	12:23 PM	31 7/16
	29 10/16	1:55 PM	27 11/16		28 5/16	2:10 PM	26 3/16		29 4/16	12:50 PM	27 3/16		36 2/16	12:38 PM	34 1/1
FILL	1 15/16	1:55 PM	Χ	FILL	2 4/16	2:10 PM	Χ	FILL	2 2/16	12:50 PM	Х	FILL	2	12:38 PM	Χ
	18 12/16	2:10 PM	16 13/16		16 9/16	2:25 PM	14 5/16		22 9/16	1:05 PM	20 7/16		23 12/16	12:53 PM	21 12/1
	22 12/16	2:25 PM	20 13/16		22 7/16	2:40 PM	20 3/16		25 9/16	1:20 PM	23 7/16		29 9/16	1:08 PM	27 9/1
	26 5/16	2:40 PM	24 6/16		25 15/16	2:55 PM	23 11/16		28 7/16	1:35 PM	26 5/16		32 14/16	1:23 PM	30 14/16
	28 13/16	2:55 PM	26 14/16		28 2/16	3:10 PM	25 14/16		28 15/16	1:50 PM	26 13/16		35 7/16	1:38 PM	33 7/16
FILL	2	2:55 PM	Χ	FILL	2 15/16	3:10 PM	Х	FILL	2 3/16	1:50 PM	Х	FILL	3	1:38 PM	Х
	16	3:10 PM	14		16 10/16	3:25 PM	13 11/16		22 7/16	2:05 PM	20 4/16		25 12/16	1:53 PM	22 12/10
	22	3:25 PM	20		21 15/16	3:40 PM	19		24	2:20 PM	21 13/16		30 2/16	2:08 PM	27 2/16
	24 15/16	3:40 PM	22 15/16		25 13/16	3:55 PM	22 14/16		26 9/16	2:35 PM	24 6/16		33 11/16	2:23 PM	30 11/16
	27 13/16	3:55 PM	25 13/16		28 4/16	4:10 PM	25 5/16		28	2:50 PM	25 13/16		33 13/16	2:38 PM	30 13/16

Average Drop (in/hr): 27 2/16 Average Drop (in/hr): 26 2/16 Applicable Rate (in/hr): 13 9/16 Applicable Rate (in/hr): 13 1/16

Average Drop (in/hr): 26 15/16 Applicable Rate (in/hr): 13 8/16

Average Drop (in/hr): 33 2/16 Applicable Rate (in/hr): 16 9/16

INFILTRATION SYSTEM NOTES

GALLERIES.

PRECAST

GALLERY

FILTER

FABRIC

 $1\frac{1}{4}$ " STONE OR SCREENED

GRAVEL

CONCRETE ---

ACCESS COVER

(END UNITS ONLY)


7 REINFORCING

END UNITS TO BE INSTALLED AT ENDS

36" GALLERY DETAIL

OF ALL GALLERY RUNS.


- 1. ALL GALLERIES TO HANDLE H-20 LOADINGS AND SHALL COMPLY WITH THE DETAIL. INTERIOR SECTIONS TO HAVE NO END WALLS. END SECTIONS TO HAVE ONE END WALL.
- 2. ALL GALLERY SECTIONS TO HAVE HOLES BROKEN TO ALLOW FLOW
- PRIOR TO PLACEMENT. 3. THERE SHALL BE A 6" LAYER OF 11/4" CRUSHED STONE BELOW ALL
- 4. THERE SHALL BE A MINIMUM OF 1' OF 11/4" CRUSHED STONE BETWEEN
- THE ROWS OF GALLERIES. 5. THERE SHALL BE A MINIMUM OF 1' OF 11/4" CRUSHED STONE ON THE
- SIDES OF THE OUTER GALLERIES. MIN. 6" SOIL COVER 6. A 6" BY 5' BY 4' CONCRETE SLAB (1-2-3 CONCRETE) SHALL BE INSTALLED AT ANY PIPE ENTRANCE TO THE GALLERIES TO PREVENT
 - EROSION. 7. EACH GALLERY RUN TO HAVE ACCESS MHS AS SHOWN ON THE PLAN. CASTING AND COVER SHALL BE EQUAL TO PATTERN NO. 1201 AS MANUFACTURED BY CAMPBELL FOUNDRY COMPANY, HARRISON, NJ. RAISE CASTING TO GRADE USING SOLID CONCRETE BLOCK AND
 - 8. REMOVE ANY TOPSOIL PRIOR TO INSTALLATION OF GALLERY.
 - 9. CONTACT THE DESIGN ENGINEER THREE DAYS PRIOR TO EXCAVATION FOR THE GALLERIES. DURING THE EXCAVATION, THE DESIGN ENGINEER MAY REVISE THE ELEVATIONS OF THE GALLERIES IF FIELD CONDITIONS DICTATE.
 - 10. ALL CRUSHED STONE SHALL BE GRADATION NO. 4 AS PER CT D.O.T. FORM 818, ARTICLE M.01.01. STONE SHALL CONSIST OF SOUND, TOUGH, DURABLE PARTICLES FREE FROM SOFT, THIN, ELONGATED, LAMINATED, FRIABLE, MICACEOUS, OR DISINTEGRATED PIECES, MUD, DIRT, OR OTHER DELETERIOUS MATERIAL.



48" GALLERY DETAIL

INFILTRATION SYSTEM NOTES

- 1. ALL GALLERIES TO HANDLE H-20 LOADINGS AND SHALL COMPLY WITH THE DETAIL. INTERIOR SECTIONS TO HAVE NO END WALLS. END SECTIONS TO HAVE ONE END WALL.
- 2. ALL GALLERY SECTIONS TO HAVE HOLES BROKEN TO ALLOW FLOW PRIOR TO PLACEMENT.
- 3. THERE SHALL BE A 6" LAYER OF 11/4" CRUSHED STONE BELOW ALL
- 4. THERE SHALL BE A MINIMUM OF 1' OF 11/4" CRUSHED STONE BETWEEN THE ROWS OF GALLERIES.
- 5. THERE SHALL BE A MINIMUM OF 1' OF 11/4" CRUSHED STONE ON THE SIDES OF THE OUTER GALLERIES.
- 6. A 6" BY 5' BY 4' CONCRETE SLAB (1-2-3 CONCRETE) SHALL BE INSTALLED AT ANY PIPE ENTRANCE TO THE GALLERIES TO PREVENT
- 7. EACH GALLERY RUN TO HAVE ACCESS MHS AS SHOWN ON THE PLAN. CASTING AND COVER SHALL BE EQUAL TO PATTERN NO. 1201 AS MANUFACTURED BY CAMPBELL FOUNDRY COMPANY, HARRISON, NJ. RAISE CASTING TO GRADE USING SOLID CONCRETE BLOCK AND
- 8. REMOVE ANY TOPSOIL PRIOR TO INSTALLATION OF GALLERY.
- 9. CONTACT THE DESIGN ENGINEER THREE DAYS PRIOR TO EXCAVATION FOR THE GALLERIES. DURING THE EXCAVATION, THE DESIGN ENGINEER MAY REVISE THE ELEVATIONS OF THE GALLERIES IF FIELD CONDITIONS DICTATE.
- 10. ALL CRUSHED STONE SHALL BE GRADATION NO. 4 AS PER CT D.O.T. FORM 818, ARTICLE M.01.01. STONE SHALL CONSIST OF SOUND, TOUGH, DURABLE PARTICLES FREE FROM SOFT, THIN, ELONGATED, LAMINATED, FRIABLE, MICACEOUS, OR DISINTEGRATED PIECES, MUD, DIRT, OR OTHER DELETERIOUS MATERIAL.



General Notes

- 1. Existing conditions, utilities, and topography information provided by Edward J Frattaroli Inc. -Land Surveyors & Consultants, 62 Mill River Street, Samford, CT 06902, email: info@frattaroli.com, tel: 203-359-2235.
- 2. Proposed site improvement information provided by Redniss & Mead Land Surveyors, Engineers, and Land Planners, 22 1st Street, Stamford, CT 06905, tel: 203-327-0500.
- 3. Prior to the start of any work, contact "call before you dig" 1-800-922-4455 at least 72 hours prior to any earthwork activities to locate utilities. Contractor shall be responsible for repair of existing utilities damaged, without further charge to the owner.
- Contract limit lines are property lines. Contractor is responsible for repair of, damage, or disturbance to other areas which may occur as the result of his or her work whether within or outside of the contract
- 5. All development to be undertaken within street rights of way or other public lands shall comply fully with applicable town, city, and state standards.
- 6. Verify locations, elevations and dimensions in field prior to construction. notify the owner and appropriate consultant of any discrepancies.
- Install erosion controls and tree protection prior to any excavation and/or clearing.
- 8. Removal and disposal of all materials to comply with any and all state and/or local codes.
- 9. Existing plant material to be saved and protected where possible.
- 10. Contractor is responsible for securing all construction permits and licenses required to complete the work.
- 11. Contractor shall be aware of all subsurface drainage and all utilities. Protect lines from damage and debris. Contractor shall be responsible for repair of all damaged lines at no additional cost to
- the owner. 12. Final grade in all cases shall slope away from the building a minimum of 1/4" per foot and all paved areas shall have a minimum wash of 1/8" per foot.
- 13. Blend new work smoothly with existing grades. Avoid sharp breaks in grade. Round top and bottoms of slopes.
- 14. Protect trees to remain with a 4 ft. ht. snow or construction fence in accordance with the tree protection detail. Maintain protection throughout construction period. Do not store materials or equipment within fence or drip line of tree. Install tree protection prior to any earthwork or clearing. 15. All disturbed areas shall be topsoiled, reseeded
- 16. Paving dimensions are from the face of curb or edging to face of curb or edging opposite.

1. Notify Landscape Architect 72 hours minimum in

2. Be aware of all underground utilities prior to any

3. All work to be performed by a qualified state of

Connecticut licensed electrical contractor.

4. All work to meet or exceed all local and national

6. Contractor shall be required to carry workmen's

compensation insurnace and comprehensive

general liability insurance. Certificates will be

7. Contractor shall provide all fixtures, accessories, and related materials for complete installation. See engineers drawings for additional information.

8. Lighting shown on these plans for location only -

9. Pole Lights to be on single circuit with shut off

10. See architectural drawings for additional lighting

11. All light fixtures have a lead time. Contractor to call

12. See Proposed Lighting Schedule on Sheet SP-1.0 for additional information on lighting fixtures.

13. See Proposed Lighting Fixture Character Images

See electrical plans for details and specification of

without further charge to the owner.

5. Contractor is responsible for obtaining all

required prior to signing contracts.

building code requirements.

all work shown on drawings.

layout and detail information.

supplier to order as needed.

and Dimensions on Sheet SP-2.0

advance of starting onsite operations. Receive

approval for layout of all fixture locations prior to

excavation operations. Contact "CALL BEFORE

YOU DIG" prior to excavation. Contractor shall be

responsible for repir of existing utilities damaged,

necessary licenses and permits required to perform

Lighting Notes

installation.

Planting Notes

- 1. Be aware of all underground utilities prior to any planting operations. Contact "CALL BEFORE YOU DIG" prior to excavation.
- 2. All plantings are to be installed by a qualified landscape contractor.
- 3. The contractor shall be required to carry workmen's compensation insurance and comprehensive general liability insurance. Certificates will be required prior to signing contracts.
- 4. Notify owner or landscape architect 72 hours minimum in advance of starting planting operations. Receive approval for layout of all bed lines and material locations prior to installation.
- 5. The landscape architect reserves the right to reject inferior plant materials and substitutions. The landscape architect is willing to make two trips to suppliers to review and approve materials. Previously unapproved materials may be rejected at the site. Minimally, all materials will conform to the "American Standard for Nursery Stock" (ANSI Z60.1 - 1996) of the american association of nurserymen.
- 6. When there is a discrepancy between plant quantities shown on the plant list & the plan, use the quantities from the plant list.
- 7. Test soil for ph and nutrients, adjust as required and receive approval prior to planting.
- 8. Pit to be 2 times wider than root ball or widest
- spread of container or bare roots. 9. Set crown of root ball 2" above finished grade.
- 10. Do not add fertilizer to planting soil for fall plantings.
- 11. All planting beds to receive 3" of mulch, sweet peat
- or equal. Submit sample for approval. 12. All disturbed areas not otherwise noted to be
- seeded turf. 13. Irrigation shall be provided as a design / build
- contract. 14. All plant material shall be guaranteed by the contractor to be in good, healthy and flourishing condition for a period of one year from the date of acceptance. The contractor shall replace, as soon as weather and seasonal conditions permit, all dead plants and all plants not in a vigorous, thriving condition, as determined by the landscape architect during, and at the end of the guarantee period. Warranty replacement will be provided at no cost to the owner and include materials and labor. Contractor is responsible for repair of any damage incurred during replacement of warranty materials. Warranty period to begin at the final approval of plantings by Landscape Architect and client. Contractor is responsible for maintaining

Irrigation Notes


- 1. Irrigation System shall be provided as needed by the Owner. Contractor shall identify location of items that require interface with other disciplines (power to controller, water supply connection,
- criteria to provide 50% reduction in use of potable water. Therefore planting is heavily oriented to native / adaptive plantings.
- 3. Temporary drip irrigation will be used for
- 4. Once plantings are established in areas with off and/or only used during extreme weather
- 5. Landscape Architect shall review irrigation shop drawings and approve irrigation types and

will include watering the plants.

backflow preventor, etc.)

the plant material until final approval is given. This

- 2. Intent is to create a system consistent with LEED
- establishing trees, shrubs, perennials, and ground
- temporary irrigation, the systems maybe be turned
- conditions. locations.



Proposed Planting Schedule

Trees Qty. Symbol Botanical Name

	- ,	
4	AA	Amelanchier x grandiflora 'Autumn Brilliance'
9	PO	Picea omorika
3	QR	Quercus rubrum
14	TC	Tsuga canadensis
22	TDC	Thuis plicate 'Croop Cient'

Thuja plicata 'Green Giant' Ulmus americana 'Princeton'

Symbol ls Liriope spicata

Groundcover **Botanical Name** Serviceberry Serbian Spruce Red Oak Canadian Hemlock Western Arborvitae

Common Name

6'-8' HT. 8'-10' HT. 3"-3.5" CAL 8'-10' HT. 8'-10' HT. American Elm 3"-3.5" CAL.

1 GAL

Installed Size

15'-25' WD. x 15'-25' HT. 20'-25' WD. x 40'-60' HT.

40'-60' WD. x 50'-70' HT. 25'-35' WD. x 40'-70' HT. 12'-20' WD. x 50'-60' HT. 30'-50' WD. x 50'-70' HT.

Mature Size

Mature Size 12"-24" WD. x 9"-18" HT.

B&B

Cond Remarks

B&B

B&B

B&B

B&B

CONT. Full, nicely shaped, well rooted, planted @ 18" o.c

Full, nicely shaped, natural character, matching

Full, nicely shaped, multi-stem, natural character, matching Full to ground, heavy foliage, nicely shaped, natural character Full to ground, heavy foliage, nicely shaped, natural character Full to ground, heavy foliage, nicely shaped, natural character Full, nicely shaped, vase shaped character, matching

Proposed Lighting Schedule Qty. Description Type L1 Pole Lights 'VIPER AREA SIZE 2' (VP2) LED Pole Light, 3000K color Temp, Type 4 Forward Area Strike Optics, Black Textured Color (BLT), Decorative Upswept Arm Mount with Matching 5" Square Pole, See Plans for Single or Double Fixture per Pole, Mounted at 14' Height, as manufactured by Beacon/Hubbell Lighting, Inc., 2041 58th Avenue Circle East, Bradenton, FL 34203, www.currentlighting.com and supplied by illuminate Lighting, contact Cliff Gilbert, tel: 203-788-0814, email: cgilbert@illuminatene.com. Contractor to submit manufacturer's cut sheet for approval prior to ordering. **—** L2 Pole Lights 'VIPER AREA SIZE 2' (VP2) LED Pole Light, 3000K color Temp, Type 4 Forward Area Strike Optics, Black Textured Color (BLT), Decorative Upswept Arm Mount with Matching 5" Square Pole, See Plans for Single or Double Fixture per Pole, Mounted at 18' Height, as manufactured by Beacon/Hubbell Lighting, Inc., 2041 58th Avenue Circle East, Bradenton, FL 34203, www.currentlighting.com and supplied by illuminate Lighting, contact Cliff Gilbert, tel: 203-788-0814, email: cgilbert@illuminatene.com. Contractor to submit manufacturer's cut sheet for approval prior to ordering. 5 @ 14' Poles 'SSA-B Series' Aluminum Pole, Black Textured Color (BLT), See Plans for Single or Double Fixture per Pole, Mounting Heights per Fixture Type, as manufactured 8 @ 18' by Beacon/Hubbell Lighting, Inc., 2041 58th Avenue Circle East, Bradenton, FL 34203, www.currentlighting.com and supplied by illuminate Lighting, contact Cliff Gilbert, tel: 203-788-0814, email: cgilbert@illuminatene.com. Contractor to submit manufacturer's cut sheet for approval prior to ordering.




Symbol Legend





















REFERENCE NOTES

- 1. Landscape Layout: Overall Plan, General Notes, Planting Note, Lighting Notes, Planting Schedule, and Lighting Schedule - See Sheet SP-1.0
- 2. Site Lighting, and Landscape Details See Sheet 3. Site Development Plan, Grading and Drainage Plan,
- Site Utilities Plan, and Other Site Details See Civil Engineer Drawings





Landscape Layout: Overall Plan

Scale: 1" = 20'


Date: 7/24/2023





















Not to Scale





Shrub Planting





Not to Scale

Not to Scale

Not to Scale

1. Landscape Layout: Overall Plan, General Notes, Planting Note, Lighting Notes, Planting Schedule,


ROCKRIMMON


2949 Long Ridge Road Stamford, CT 06903

COUNTRY CLUB

- and Lighting Schedule See Sheet SP-1.0

 2. Site Lighting and Landscape Details See Sheet
- 3. Site Development Plan, Grading and Drainage Plan, Site Utilities Plan, and Other Site Details - See Civil Engineer Drawings





Site Lighting and Landscape Details Date: 7/24/2023 Scale: As noted

No: Revision:

Date:

SHIPPING CONTAINER

S.L.R.

TO BE RELOCATED (6,0) (6,04 PARKING SPACES TO BE REMOVED 0.0 0.0 0.0 0.0 0.0 0.0 0.0 EXISTING LICHTOPOLE BE RELOCATED. 1 0.2 0.2 0.9 0.3 0.3 0.2 0.2 0.1 Dale Kim et Concrete PAD TO BE REMOVED 156 S.L.R. RELOCATED 0.00.6 1.0 1.7 2.5 1.3 1.03 PICKLEBALL 2 †7.6 | 18.9 22CQURT #1 24.4 | 24.9 22.9 19.6 20.4 21.9 22.2 | 4.2 1.9 1.1 0.5 0.3 0.0 0.0 0.0 0.0 0.0 0.0 0.1PROPOSED LIGHT POLES TO 0.0ASRHALT PARKING LOT $0.0 \quad 0.0 \quad 0.0 \quad 0.12 \quad 0.12 \quad 0.13 \quad 0.1$ 0.022.6 COURT9.#33.0 24.9 24.4 GOURT0.#42.5 18 50.5 2777 1.3 0.6 0.3 0.0____ 20' 3.9 2.7 1.8 1.2 0.7 0.6 0.8 7.1.6 3.2 5.1 8.0 1.2/6///1.5 0.6 0.3 0.2 arcel "A" Map [28].1 23.3 20.7 18.4 19.3 21.2 21.0 18.5 18.1 19.8 21.3 20.7 0.0014 S.L.R. 0.00.0 0.0 0.0 0.0 0.1 0.1 0.2 0.1 0.2 0.1 0.2 0.10.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0
 0.0</t Greefield & N/F Company Land Tr. Minh Nguyen to to to Lot 2 Map 11477 Vol. 8970 Pg. 201

S.L.R.

N/F
Rock Rimmon
C. C.
Parcel "A"
Map No. 9360
S.L.R.

Luminaire Schedule								
Qty	Label	Luminaire	Total	Arrangement	LLF	Description		
		Watts	Watts					
8	L2	238.56	1908.48	Single	0.900	Beacon VP-ST-2-72L-240-3K7-4F-UNV-A-x TOF @ 18FT AFG		
3	L1B	108.2	324.6	Single	0.900	Beacon VP-ST-1-36L-105-3K7-4W-UNV-A-x TOF @ 14FT AFG		
3	L1	105	315	Single	0.900	Beacon VP-ST-1-36L-105-3K7-4F-UNV-A-x-BC TOF @ 14FT AFG		

Calculation Summary							
Label	Units	Avg	Max	Min	Avg/Min	Max/Min	Grid Height
Pickleball Court	Fc	19.80	25.3	10.1	1.96	2.50	3
Site	Fc	1.44	13.4	0.0	N.A.	N.A.	0
Parking & Drive Lane	Fc	3.56	9.1	0.6	5.93	15.17	

Rockrimmon CC Pickle Ball Court & Parking Lot Detail: Photometric Calculation Date: 7/24/2023 Cliff Gilbert Specifications - Southern CT Scale: 1" = 15'-0" (203) 788-0814 illominate Drawing Number: 263 Winn Street SL-1 Burlington, MA 01803 (781) 935-8500 333 Pleasant Valley Road South Windsor, CT 06074 Sheet 1 of 1 (860) 282-0597



ROCKRIMMON COUNTRY CLUB

2949 Long Ridge Road, Stamford, CT 06903 Phone 203-322-3408 Fax 203-329-1664

www.rockrimmoncc.org

July 25, 2023

City of Stamford Planning & Zoning Boards c/o Ralph Blessing, Land Use Bureau Chief 888 Washington Boulevard Stamford, CT 06901

Re: 2949 Long Ridge Road & 0 Long Ridge Road (003-8745) - Stamford, CT

Dear Mr. Blessing and Board Members:

This letter serves to authorize Redniss & Mead, with offices at 22 First Street in Stamford, CT, to act as our agent in connection with the preparing, filing, and processing of any and all applications required for Planning and Zoning approvals relating to the above referenced properties.

Thank you for your acknowledgement of said authority.

Sincerely,

William Aron

President